

# GALLERY SPECIFICATION GUIDE

2019

Gallery



Galleries are a source of endless inspiration, creativity and fresh thinking. Our innovative collection is no exception. Defined by iconic designs that create a centrepiece in any development, Gallery blends modern European influences and traditional craftsmanship in a way that will inspire every customer. From modern minimal styling to rustic charm, this essential collection takes your interiors in a new direction, to transform space, add value and turn every house into a home.

We reserve the right to change any descriptions, or dimensions given in this specification guide without notice.

Illustrations act as a guide only. The illustrations in this guide are intended as a representation only and must not be considered as scaled or detailed.

Colour reproduction in this guide is as accurate as printing techniques will allow.

Errors and omissions excepted. Gallery is a registered trademark of the Symphony Group plc.

# Gallery

by Symphony®

The Symphony Group PLC,  
Pen Hill Estate, Park Spring Road,  
South Yorkshire. S72 7EZ

General Enquiries:  
Tel: 01226 446000  
Fax: 01226 711185

[www.symphony-group.co.uk](http://www.symphony-group.co.uk)



When you have finished with this brochure please recycle it.

# CHOOSING YOUR OWN STYLE



## CONTENTS

### RANGE OVERVIEW

CONTEMPORARY

CLASSIC

INLINE

### LUXURY ACCESSORIES

WIREWORK & STORAGE

DRAWER ACCESSORIES

WASTE DISPOSAL

### UNIT CONTENT

### RANGED ACCESSORIES

BLENDER PANELS

CORNICE & PELMETS

PILASTERS

MANTLES & ACCESSORIES

### LIGHTING

### HANDLES

### FINISHING TOUCHES

### WORK SURFACES

SPLASHBACKS & UPSTANDS

# ORDERING CHECKLIST



**Please check through the list below to ensure we have all the information we need to supply your exact requirements.**

## General

Give details of the delivery site address, including development names (where applicable), site phone number and name of site contact.

Specify your required week commencing delivery date.

Give your Symphony quotation reference number and Symphony CAD drawing number (if applicable).

## Specification

State your required cabinet specification:

- 18mm Gallery Standard
- 18mm Gallery Premium

For further information on cabinet specifications please refer to pages 06 and 07.

## Door Style and Colour

Choose from our Inline, Contemporary or Classic kitchen ranges. Then state the chosen style and colour, for example, Cranbrook Sage.

## Cabinet Colour

Select the chosen exterior cabinet colour, for example, Ivory.

## Replacement Ends

Our ranges are available with frontal co-ordinating replacement end panels which negate the need for blender panels. Simply select the cabinets that require a replacement end and follow the instruction on page 27 to order.

## Units

State the full unit code for each item and state the appropriate handings where required.

- The side of the hinge on single cabinets (e.g. LHH Left Hand Hinge)
- The side of the blanked end of corner cabinets (e.g. LHB Left Hand Blank)

- The position of the drainer on sink cabinets (e.g. LHD Left Hand Drainer, for cabinet with a right hand dummy drawer)
- The side of dummy drawer on double base units (e.g. LHS Left Hand Side)

## Handle Option

Each range is available with a choice of handles. Select the handle option that is required.

## Worktops

22mm and 40mm Laminate, 34mm Earthstone and Solid Surface worktops are available. See pages 22 to 24 for colours options.

If your requirements are complicated, include a detailed plan showing dimensions, cut out positions and sizes and places where worktops abut.

If you require Mason Mitre Joints, please refer to page 80. Alternatively contact your local representative or contact Symphony's Sales Office on 01226 446000.

## Finishing Touches

State which finishing touches are required, for example, lighting, splashbacks, cornice, pelmet and storage.

When ordering appliances state the manufacturer's name and the model number of the appliance to be fitted, together with the aperture size if known.

## Sinks

Give the sink code, the handing of the drainer and the colour required (if applicable). State whether waste/overflow kits and accessory packs are required.

## Inline Ranges

Inline is available in selected units that suit the style of the door. Those units not available are detailed on the relevant pages.





## Please Note

The illustrations in this booklet are intended as representations only and are not necessarily correctly scaled, proportioned or detailed.

All sizes given are nominal. If exact unit, door or other dimensions are required, please contact your local Symphony representative or contact Symphony's Sales Office on 01226 446000.

All units are manufactured within industry standards for dimensional tolerance.

## Important

Symphony's corner post is designed to avoid handle clash and requires an additional allowance in both floor space and worktop.

This is frequently overlooked and can result in problems on-site.

**SYMPHONY CANNOT ACCEPT RESPONSIBILITY FOR A HANDLE CLASH IF A NON STANDARD HANDLE IS CHOSEN OR HANDLES ARE FITTED IN A NON STANDARD POSITION.**

**PLEASE REFER TO PAGES 125 TO 131 FOR FULL DETAILS OF CORNER ARRANGEMENTS.**

If you require any additional information or assistance please contact your local Symphony representative or Symphony's Sales Office on 01226 446000.

## Unit Codes

### Prefix Letters

These indicate the type of unit, such as BU for base unit; WU for wall unit; BR for broom unit; LU for larder unit; OH for oven housing unit.

### Numbers

The numbers indicate the width of the unit followed either by the depth, or in case of wall units, the height. For example a WU1056 is a wall unit 1000mm wide and 561mm high. A BU56 is a base unit 500mm wide and 600mm deep.

## Suffix Letters

Any letters following the number code indicate a variant of the type as follows:

<b>A</b>	} Variations of corner base unit or appliance housing formats
<b>B</b>	
<b>C</b>	
<b>D</b>	
<b>E</b>	

**F** - Full height door base unit

**D** - Drawer line base unit

**DD** - Single base unit or corner base unit with a dummy drawer

**DAI** - Double base unit with two dummy drawers

**DAC** - Double base unit with one dummy drawer

**BO** - Corner base unit with no corner post

**BS** - Corner base unit with dummy drawer and no corner post

**FP** - Corner base unit with flexible corner post

**GL** - Unit with left hand replacement end

**GR** - Unit with right hand replacement end

**G2** - Unit with two replacement ends

**IN** - Inset Handle

## Unit Dimensions


All dimensions are expressed as follows:

Width - side to side

Depth - front to back

Height - top to bottom

All dimensions in this document are shown in millimetres




## Tolerance Allowances

Plaster allowances vary depending on the type of finish used. Unless instructed otherwise of a particular customer's requirement, our designers will allow 30mm per wall on dry lining and dot and dab, 12.5mm per wall on stud walls with taped joints, and 15mm per wall on skimmed stud walls. Symphony's Design Department will allow 50mm wall to wall building tolerance. This allows for extra length on worktops and the distance units finish from a wall. Where a freestanding appliance terminates a run against a wall allow 620mm minimum for the appliance (600mm for the appliance and 20mm for skirting boards) plus the required building tolerance (see above paragraph).


# STANDARD CABINET SPECIFICATION

## WALL UNIT CABINET FEATURES



- 1 18mm colour co-ordinated cabinet with matching interior/exterior finish
- 2 3 wall unit heights (561mm, 724mm & 900mm)
- 3 285mm deep cabinet
- 4 3mm hardboard solid back panel
- 5 Concealed fully adjustable wall hanging bracket (*see fig. A*)
- 6 Metal shelf supports (*see fig. D*)
- 7 18mm shelves, glazed cabinets include glass shelves as standard
- 8 Cam and dowel construction
- 9 3-way fully adjustable soft close all metal clip-on hinge (*see fig. C*)

## BASE UNIT CABINET FEATURES



- 1 Removable back with void of 66mm for pipes, etc
- 2 Atira metal drawer box with full extension and soft-closing action. Pan drawers have glass sides (*see Fig. F*)\*
- 3 3-way fully adjustable drawer front (*see Fig. G*)
- 4 18mm colour co-ordinated cabinet with matching interior/exterior finish
- 5 Cam and dowel construction
- 6 18mm shelves with metal shelf supports (*see Fig. D*)
- 7 3-way fully adjustable all-metal clip-on hinge with soft-close buffer (*see Fig. C*)
- 8 Clip-on continuous plinth with optional plinth dust seal (*order separately*)
- 9 Adjustable legs min. 140mm - max. 180mm

\*Oak drawer box available as upgrade on Classic ranges (*see Fig. H*)



### Replacement Cabinet Ends

A selection of our ranges are available with frontal matched replacement cabinet ends, allowing you to create a fully co-ordinated kitchen.

Available on both Standard and Premium specifications.

Please speak with your designer for further information.

Cabinet Replacement End shown: White Cabinet with Avola Grey replacement ends.



A few features of an In-Frame New England cabinet vary as detailed below:

- 2 wall unit heights (724mm and 900mm only)
- A special width drawer box to allow for the frame (*see Fig. J*)
- A special designed 3-way fully adjustable soft close clip on hinge (*see Fig. I*)




Fig. A




Fig. B




Fig. C





Fig. D

# PREMIUM CABINET SPECIFICATION

## WALL UNIT CABINET FEATURES



- 1 18mm colour co-ordinated cabinet with matching interior/exterior finish
- 2 3 wall unit heights (561mm, 724mm & 900mm)
- 3 **330mm deep cabinet**
- 4 **8mm one piece solid back panel**
- 5 **2mm PVC edging to all front cabinet and shelf edges**
- 6 Concealed fully adjustable wall hanging bracket (*see fig. B*)
- 7 Metal shelf supports (*see fig. D*)
- 8 18mm shelves, glazed units include glass shelves as standard
- 9 Cam and dowel construction
- 10 3-way fully adjustable soft close all metal clip-on hinge (*see fig. C*)

## BASE UNIT CABINET FEATURES



- 1 **Removable 15mm solid back** with void of 66mm for pipes, etc
- 2 Atira metal drawer box with full extension and soft-closing action. Pan drawers have glass sides (*see Fig. F*)\*
- 3 3-way fully adjustable drawer front (*see Fig. G*)
- 4 18mm colour co-ordinated cabinet with matching interior/exterior finish
- 5 Cam and dowel construction
- 6 18mm shelves with metal shelf supports (*see Fig. D*)
- 7 3-way fully adjustable all-metal clip-on hinge with soft-close buffer (*see Fig. C*)
- 8 Clip-on continuous plinth with optional plinth dust seal (*order separately*)
- 9 Adjustable legs min. 140mm - max. 180mm

\*Oak drawer box available as upgrade on Classic ranges (*see Fig. H*)

### DRAWER UPGRADES



Oak drawer box (*Fig. H*)




Cutlery tray options for the Atira drawer box



Blonde Oak



Ivory



White



Fig. E



Fig. F




Fig. G




Fig. I




Fig. J

# RANGE OVERVIEW – CONTEMPORARY

## ALTA (GLOSS)



### Door colour options



**Door/drawer front thickness**  
18mm

**Door/drawer material and construction**  
Gloss Painted and Lacquered MDF

**Recommended cabinet colour**  
Ivory or White

### Replacement end colour

Frontal Matched  
(internal colour is  
Matt Frontal Colour)

**Glazed door style**  
Frosted Glass



**Handle drilling information**  
Undrilled

**Recommended handle**



HPK651



HPK734

### Recommended worktop

	40mm	Premium	22mm
Gloss Mussel	Copper Slate	Volcanic Ash	Mystic Pine
Gloss Pure White	Brazilian Walnut	Liberty Rock	Brazilia
Gloss Dusk Grey	Brazilian Walnut	Woodstone	Rustic Oak
Gloss Pearl Grey	Brazilian Walnut	Platinum Metallic	Mystic Pine


### Curved units available

Yes – Convex and Concave


### EKO timber drawer box available

No

## ALTA (MATT)



### Door colour options



**Door/drawer front thickness**  
18mm

**Door/drawer material and construction**  
Matt MDF

**Recommended cabinet colour**  
White

### Replacement end colour

Frontal Matched  
Anthracite and Pure White  
(internal colour as external)

Frontal Matched – Vertical Grain  
Dark Walnut and Rustic Oak  
(internal colour as external)

**Glazed door style**  
Frosted Glass



**Handle drilling information**  
Undrilled

**Recommended handle**



HPK651



HPK734

### Recommended worktop

	40mm	Premium	22mm
Anthracite	Marble Siroco	Cloudy Cement	Rustic Oak
Dark Walnut	Marble Siroco	Cloudy Cement	Designer White
Pure White	Brazilian Walnut	Liberty Rock	Brazilia
Rustic Oak	Dark Ash	Liberty Rock	Rustic Oak

### Curved units available

No

### EKO timber drawer box available

No

# RANGE OVERVIEW – CONTEMPORARY



## Door colour options



**Door/drawer front thickness**  
18mm


**Door/drawer material and construction**  
Matt Painted MDF

**Recommended cabinet colour**  
White

## Handle drilling information

Undrilled

## Recommended handle



## Recommended worktop


	40mm	Premium	22mm
Anthracite	Marble Siroco	Cloudy Cement	Rustic Oak
Cashmere	Brazilian Walnut	Volcanic Ash	Mystic Pine
Clay	Alaska	Woodstone	Designer White
Cobble Grey	Marble Siroco	Woodstone	Rustic Oak
Cooks Blue	Marble Siroco	Woodstone	Rustic Oak
Dove Grey	Dark Ash	Volcanic Ash	Brazilia
Duck Egg Blue	Dark Ash	Liberty Rock	Brazilia
Indigo	Marble Siroco	Woodstone	Designer White
Ivory	Copper Slate	Volcanic Ash	Mystic Pine
Platinum	Brazilian Walnut	Volcanic Ash	Mystic Pine
Pumice	Dark Ash	Volcanic Ash	Mystic Pine
Sage	Alaska	Volcanic Ash	Mystic Pine
Skylon Grey	Brazilian Walnut	Liberty Rock	Mystic Pine
Snow White	Brazilian Walnut	Liberty Rock	Brazilia
Stone	Alaska	Platinum Metallic	Mystic Pine

## Curved units available

Yes – Convex only

## EKO timber drawer box available

No



## Door colour options

Avola Grey

**Door/drawer front thickness**  
18mm

**Door/drawer material and construction**  
Textured Horizontal Grain  
PVC-edged MFC

**Recommended cabinet colour**  
White

## Replacement end colour

Avola Grey – Vertical Grain  
(internal colour is Avola Grey)

## Handle drilling information

Drawer Front Drillings: 160mm  
Door Drillings: 160mm

## Recommended handle



## Recommended worktop

40mm	Premium	22mm
Alaska	Woodstone	Designer White

## Curved units available


No

## EKO timber drawer box available

No

# RANGE OVERVIEW – CONTEMPORARY

## NEW YORK (GLOSS)



### Door colour options



Gloss Cashmere Gloss Dusk Grey Gloss Ivory



Gloss Pearl Grey Gloss White

**Door/drawer front thickness**  
22mm

**Door/drawer material and construction**  
Gloss Painted and Lacquered MDF

**Recommended cabinet colour**  
Ivory or White

### Replacement end colour

Frontal Matched  
(internal colour is  
Matt Frontal Colour)

**Glazed door style**  
Frosted Glass



**Handle drilling information**  
N/A

**Recommended handle**  
N/A


### Recommended worktop

	40mm	Premium	22mm
Gloss Cashmere			
Gloss Dusk Grey			
Gloss Ivory			
Gloss Pearl Grey			
Gloss White			

**Curved units available**  
Yes – Convex and Concave

**EKO timber drawer box available**  
No

## NEW YORK (MATT)



**Door colour options**  
Matt Anthracite

**Door/drawer front thickness**  
22mm

**Door/drawer material and construction**  
Matt Painted MDF

**Recommended cabinet colour**  
White

### Replacement end colour

Matt Anthracite  
(internal colour is Matt Anthracite)

**Handle drilling information**  
N/A

**Recommended handle**  
N/A

### Recommended worktop

40mm	Premium	22mm

**Curved units available**  
No

**EKO timber drawer box available**  
No

# RANGE OVERVIEW – CONTEMPORARY



## Door colour options



**Door/drawer front thickness**  
22mm

**Door/drawer material and construction**  
Matt Painted MDF

**Recommended cabinet colour**  
White

## Glazed door style



**Handle drilling information**  
N/A


**Recommended handle**  
N/A

## Recommended worktop


	40mm	Premium	22mm
Anthracite	Marble Siroco	Cloudy Cement	Rustic Oak
Cashmere	Copper Slate	Volcanic Ash	Mystic Pine
Clay	Alaska	Woodstone	Designer White
Cobble Grey	Marble Siroco	Woodstone	Mystic Pine
Cooks Blue	Alaska	Woodstone	Designer White
Dove Grey	Brazilian Walnut	Volcanic Ash	Brazilia
Duck Egg Blue	Brazilian Walnut	Volcanic Ash	Brazilia
Indigo	Marble Siroco	Woodstone	Designer White
Ivory	Copper Slate	Volcanic Ash	Mystic Pine
Platinum	Brazilian Walnut	Liberty Rock	Mystic Pine
Pumice	Brazilian Walnut	Volcanic Ash	Dark Oak
Sage	Marble Siroco	Volcanic Ash	Designer White
Skylon Grey	Brazilian Walnut	Liberty Rock	Brazilia
Snow White	Brazilian Walnut	Liberty Rock	Mystic Pine
Stone	Alaska	Platinum Metallic	Mystic Pine

**Curved units available**  
Yes – Convex and Concave

**EKO timber drawer box available**  
No



## Door colour options



**Door/drawer front thickness**  
18mm

**Door/drawer material and construction**  
Textured Horizontal Grain  
PVC-edged MFC

**Recommended cabinet colour**  
White

## Replacement end colour

Frontal Matched – Vertical Grain  
(internal colour is Frontal Matched)

**Handle drilling information**  
Undrilled

**Recommended handle**



HPK643



HPK472

## Recommended worktop

	40mm	Premium	22mm
Cashmere	Copper Slate	Platinum Metallic	Mystic Pine
Cobble Grey	Marble Siroco	Woodstone	Rustic Oak
Mussel	Brazilian Walnut	Cinnamon	Mystic Pine
Porcelain	Tectonica	Liberty Rock	Mystic Pine
Stone	Alaska	Platinum Metallic	Mystic Pine

**Curved units available**  
No

**EKO timber drawer box available**  
No



# RANGE OVERVIEW – CONTEMPORARY



QUADRA

## Door colour options



Cobble Grey White

**Door/drawer front thickness**  
18mm

**Door/drawer material and construction**  
Matt PVC Pressed MDF

**Recommended cabinet colour**  
White

## Replacement end colour

Matt Cobble Grey/White  
(Internal colour is Frontal Matched)

**Handle drilling information**  
Undrilled

## Recommended handle



HPK712



HPK644

## Recommended worktop


	40mm	Premium	22mm
Cobble Grey			
White			

## Curved units available

No

## EKO timber drawer box available

No



VIRGINIA OAK

## Door colour options

Oak

**Door/drawer front thickness**  
18mm

**Door/drawer material and construction**  
Vertical Grain PVC-edged MFC

**Recommended cabinet colour**  
Blonde Oak

## Handle drilling information

Drawer Front Drillings: 160mm  
Door Drillings: 160mm

## Recommended handle



HPK644



HPK643

## Recommended worktop

40mm	Premium	22mm

## Curved units available

No

## EKO timber drawer box available

No

# RANGE OVERVIEW – CONTEMPORARY



## Door colour options



**Door/drawer front thickness**  
18mm

**Door/drawer material and construction**  
Gloss Painted MFC

**Recommended cabinet colour**  
Ivory or White

## Replacement end colour

Frontal Matched  
(Internal colour is Frontal Matched)

## Handle drilling information

Drawer Front Drillings:  
128mm, 160mm  
Door Drillings: 128mm, 160mm

## Recommended handle



## Recommended worktop

	40mm	Premium	22mm
Gloss Anthracite	Marble Siroco	Cloudy Cement	Rustic Oak
Gloss Cashmere	Copper Slate	Volcanic Ash	Mystic Pine
Gloss Ivory	Brazilian Walnut	Cinnamon	Dark Oak
Gloss Platinum	Dark Ash	Volcanic Ash	Mystic Pine
Gloss White	Brazilian Walnut	Liberty Rock	Brazilia

## Curved units available

Yes – Convex only

## EKO timber drawer box available

No

# RANGE OVERVIEW – CLASSIC

## ASHBOURNE IVORY



**Door colour options**  
Ivory

**Door/drawer front thickness**  
18mm

**Door/drawer material and construction**  
Grained Foil Wrapped MDF with Chamfered Frame

**Recommended cabinet colour**  
Ivory

**Glazed door style**  
Clear Glass



**Handle drilling information**  
Undrilled

**Recommended handle**



HPK465



HPK631

**Recommended worktop**

40mm	Premium	22mm
		N/A
Oak Block	Chalet Oak	

**Curved units available**  
Yes – Convex only

**EKO timber drawer box available**  
Yes

## ASHBOURNE PAINT TO ORDER\*



**Door colour options**



**Door/drawer front thickness**  
18mm

**Door/drawer material and construction**  
Grained Painted Foil Wrapped MDF with chamfered frame

**Recommended cabinet colour**  
Ivory or White

**Glazed door style**  
Clear Glass



**Handle drilling information**  
Undrilled

**Recommended handle**



HPK465



HPK631


**Recommended worktop**

	40mm	Premium	22mm
All Colours			N/A
	Oak Block	Chalet Oak	

**Curved units available**  
Yes – Convex only

**EKO timber drawer box available**  
Yes

## AUSTIN IVORY



**Door colour options**  
Painted Ivory

**Door/drawer front thickness**  
20mm

**Door/drawer material and construction**  
Ash Veneered Frame and Centre Panel

**Recommended cabinet colour**  
Ivory

**Glazed door style**  
Clear Glass



**Handle drilling information**  
Drawer Front Drillings:  
128, 160, 192, 224mm  
Door Drillings:  
128, 160, 192, 224mm

**Recommended handle**



HPK447



HPK644

**Recommended worktop**

40mm	Premium	22mm
		N/A
Oak Block	Chalet Oak	

**Curved units available**  
Yes – Convex only

**EKO timber drawer box available**  
Yes

# RANGE OVERVIEW – CLASSIC

## AUSTIN PAINT TO ORDER\*



### Door colour options



**Door/drawer front thickness**  
20mm

**Door/drawer material and construction**  
Ash Veneered Frame with Veneered Centre Panel

**Recommended cabinet colour**  
Ivory or White

**Glazed door style**  
Clear Glass



**Handle drilling information**  
Undrilled

**Recommended handle**



HPK447



HPK442

### Recommended worktop

	40mm	Premium	22mm
All Colours			N/A

**Curved units available**  
Yes – Convex and Concave

**EKO timber drawer box available**  
Yes

## CRANBROOK



### Door colour options



**Door/drawer front thickness**  
22mm

**Door/drawer material and construction**  
Foil Wrapped MDF

**Recommended cabinet colour**  
Ivory or White

**Replacement end colour**  
Cobble Grey/Ivory/Platinum /Sage/Stone  
(Internal colour is Frontal Matched)

**Glazed door style**  
Clear Glass



**Handle drilling information**  
Undrilled

**Recommended handle**



HPK465



HPK752

### Recommended worktop

	40mm	Premium	22mm
Cobble Grey			
Ivory			
Platinum			
Sage			
Stone			

**Curved units available**  
Yes – Convex only

**EKO timber drawer box available**  
Yes

# RANGE OVERVIEW – CLASSIC

## NEW ENGLAND PAINT TO ORDER\*



### Door colour options



**Door/drawer front thickness**  
22mm

**Door/drawer material and construction**  
Painted Ash Veneered Frame with Veneered Centre Panel

**Recommended cabinet colour**  
Ivory or White

### Glazed door style Clear Glass



**Handle drilling information**  
Undrilled

### Recommended handle




HPK442



HPK629

### Recommended worktop

	40mm	Premium	22mm
All Colours			N/A

**Curved units available**  
Yes – Convex and Concave

**EKO timber drawer box available**  
Yes

## NEWPORT IVORY



**Door colour options**  
Ivory

**Door/drawer front thickness**  
19mm

**Door/drawer material and construction**  
PVC Wrapped

**Recommended cabinet colour**  
Ivory

**Handle drilling information**  
Drawer Front Drillings: 128mm, 160mm  
Door Drillings: 128mm, 160mm

### Recommended handle



HPK346



HPK672

### Recommended worktop

40mm	Premium	22mm
		

**Curved units available**  
No

**EKO timber drawer box available**  
Yes

# RANGE OVERVIEW – CLASSIC

## OAKHAM



**Door colour options**  
Blonde Oak

**Door/drawer front thickness**  
20mm

**Door/drawer material and construction**  
Oak Veneered Frame with Veneered Centre Panel

**Recommended cabinet colour**  
Blonde Oak

**Glazed door style**  
Clear Glass



**Handle drilling information**  
Undrilled

**Recommended handle**



HPK630

**Recommended worktop**

40mm	Premium	22mm
Marble Siroco	Liberty Rock	Brazilia

**Curved units available**  
Yes – Convex only

**EKO timber drawer box available**  
Yes

## WEXFORD PAINT TO ORDER\*



**Door colour options**


Anthracite	Cashmere	Chalk White	Clay	Cobble Grey
Cooks Blue	Dove Grey	Duck Egg Blue	Indigo	Ivory
Platinum	Pumice	Sage	Skylon Grey	Stone

**Door/drawer front thickness**  
20mm

**Door/drawer material and construction**  
Ash Veneered Frame with Veneered Centre Panel

**Recommended cabinet colour**  
Ivory or White

**Glazed door style**  
Clear Glass



**Handle drilling information**  
Undrilled

**Recommended handle**



HPK637



HPK464


**Recommended worktop**

	40mm	Premium	22mm
All Colours			N/A
	Oak Block	Chalet Oak	

**Curved units available**  
Yes – Convex only

**EKO timber drawer box available**  
Yes

# RANGE OVERVIEW – INLINE FORM



**Door/drawer front thickness**  
18mm

**Door/drawer material and construction**  
Textured MFC door with matching PVC edging

**Replacement end colour**  
Avola Grey

**Cabinet exterior**  
White

**Recommended worktop**

40mm	Premium	22mm
 Alaska	 Woodstone	 Designer White






**Door/drawer front thickness**  
18mm


**Door/drawer material and construction**  
MFC door with matching PVC edging

**Replacement end colour**  
Blonde Oak

**Cabinet exterior**  
Blonde Oak

**Recommended worktop**

40mm	Premium	22mm
 Alaska	 Woodstone	 Designer White






**Door/drawer front thickness**  
18mm

**Door/drawer material and construction**  
MFC textured panel door with flat matching PVC edging

**Replacement end colour**  
Textured Cashmere

**Cabinet exterior**  
White

**Recommended worktop**

40mm	Premium	22mm
 Copper Slate	 Platinum Metallic	 Mystic Pine



**Door/drawer front thickness**  
18mm

**Door/drawer material and construction**  
MFC textured panel door with flat matching PVC edging

**Replacement end colour**  
Textured Cobble Grey

**Cabinet exterior**  
White

**Recommended worktop**

40mm	Premium	22mm
 Marble Siroco	 Woodstone	 Rustic Oak




**Door/drawer front thickness**  
18mm


**Door/drawer material and construction**  
MFC textured panel door with flat matching PVC edging

**Replacement end colour**  
Textured Mussel

**Cabinet exterior**  
Ivory

**Recommended worktop**

40mm	Premium	22mm
 Brazilian Walnut	 Cinnamon	 Mystic Pine




**Door/drawer front thickness**  
18mm

**Door/drawer material and construction**  
MFC textured panel door with flat matching PVC edging

**Replacement end colour**  
Textured Porcelain

**Cabinet exterior**  
White

**Recommended worktop**

40mm	Premium	22mm
 Tectonica	 Liberty Rock	 Mystic Pine




**Door/drawer front thickness**  
18mm

**Door/drawer material and construction**  
MFC textured panel door with flat matching PVC edging

**Replacement end colour**  
Textured Stone

**Cabinet exterior**  
White

**Recommended worktop**

40mm	Premium	22mm
 Alaska	 Platinum Metallic	 Mystic Pine



# RANGE OVERVIEW – INLINE TREND

<div><div>GLOSS ICE ANTHRACITE</div><div></div></div>	<div>Door/drawer front thickness 18mm</div> <div>Door/drawer material and construction Gloss painted MFC door</div>	<div>Replacement end colour Gloss Anthracite</div> <div>Cabinet exterior White</div>	<div>Recommended worktop</div> <table><tr><td>40mm</td><td>Premium</td><td>22mm</td></tr><tr><td><div><div></div><div>Marble Siroco</div></div></td><td><div><div></div><div>Cloudy Cement</div></div></td><td><div><div></div><div>Rustic Oak</div></div></td></tr></table>	40mm	Premium	22mm	<div><div></div><div>Marble Siroco</div></div>	<div><div></div><div>Cloudy Cement</div></div>	<div><div></div><div>Rustic Oak</div></div>
40mm	Premium	22mm							
<div><div></div><div>Marble Siroco</div></div>	<div><div></div><div>Cloudy Cement</div></div>	<div><div></div><div>Rustic Oak</div></div>							
<div><div>GLOSS ICE CASHMERE</div><div></div></div>	<div>Door/drawer front thickness 18mm</div> <div>Door/drawer material and construction Gloss painted MFC door</div>	<div>Replacement end colour Gloss Cashmere</div> <div>Cabinet exterior White</div>	<div>Recommended worktop</div> <table><tr><td>40mm</td><td>Premium</td><td>22mm</td></tr><tr><td><div><div></div><div>Copper Slate</div></div></td><td><div><div></div><div>Volcanic Ash</div></div></td><td><div><div></div><div>Mystic Pine</div></div></td></tr></table>	40mm	Premium	22mm	<div><div></div><div>Copper Slate</div></div>	<div><div></div><div>Volcanic Ash</div></div>	<div><div></div><div>Mystic Pine</div></div>
40mm	Premium	22mm							
<div><div></div><div>Copper Slate</div></div>	<div><div></div><div>Volcanic Ash</div></div>	<div><div></div><div>Mystic Pine</div></div>							
<div><div>GLOSS ICE IVORY</div><div></div></div>	<div>Door/drawer front thickness 18mm</div> <div>Door/drawer material and construction Gloss painted MFC door</div>	<div>Replacement end colour Gloss Ivory</div> <div>Cabinet exterior Ivory</div>	<div>Recommended worktop</div> <table><tr><td>40mm</td><td>Premium</td><td>22mm</td></tr><tr><td><div><div></div><div>Brazilian Walnut</div></div></td><td><div><div></div><div>Cinnamon</div></div></td><td><div><div></div><div>Dark Oak</div></div></td></tr></table>	40mm	Premium	22mm	<div><div></div><div>Brazilian Walnut</div></div>	<div><div></div><div>Cinnamon</div></div>	<div><div></div><div>Dark Oak</div></div>
40mm	Premium	22mm							
<div><div></div><div>Brazilian Walnut</div></div>	<div><div></div><div>Cinnamon</div></div>	<div><div></div><div>Dark Oak</div></div>							
<div><div>GLOSS ICE PLATINUM</div><div></div></div>	<div>Door/drawer front thickness 18mm</div> <div>Door/drawer material and construction Gloss painted MFC door</div>	<div>Replacement end colour Gloss Platinum</div> <div>Cabinet exterior White</div>	<div>Recommended worktop</div> <table><tr><td>40mm</td><td>Premium</td><td>22mm</td></tr><tr><td><div><div></div><div>Brazilian Walnut</div></div></td><td><div><div></div><div>Volcanic Ash</div></div></td><td><div><div></div><div>Mystic Pine</div></div></td></tr></table>	40mm	Premium	22mm	<div><div></div><div>Brazilian Walnut</div></div>	<div><div></div><div>Volcanic Ash</div></div>	<div><div></div><div>Mystic Pine</div></div>
40mm	Premium	22mm							
<div><div></div><div>Brazilian Walnut</div></div>	<div><div></div><div>Volcanic Ash</div></div>	<div><div></div><div>Mystic Pine</div></div>							
<div><div>GLOSS ICE WHITE</div><div></div></div>	<div>Door/drawer front thickness 18mm</div> <div>Door/drawer material and construction Gloss painted MFC door</div>	<div>Replacement end colour Gloss White</div> <div>Cabinet exterior White</div>	<div>Recommended worktop</div> <table><tr><td>40mm</td><td>Premium</td><td>22mm</td></tr><tr><td><div><div></div><div>Brazilian Walnut</div></div></td><td><div><div></div><div>Liberty Rock</div></div></td><td><div><div></div><div>Brazilia</div></div></td></tr></table>	40mm	Premium	22mm	<div><div></div><div>Brazilian Walnut</div></div>	<div><div></div><div>Liberty Rock</div></div>	<div><div></div><div>Brazilia</div></div>
40mm	Premium	22mm							
<div><div></div><div>Brazilian Walnut</div></div>	<div><div></div><div>Liberty Rock</div></div>	<div><div></div><div>Brazilia</div></div>							

# RANGE OVERVIEW – INLINE SELECT

<div><div>GLOSS DUSK GREY</div><div></div></div>	<div><div>Door/drawer front thickness</div><div>18mm</div></div> <div><div>Door/drawer material and construction</div><div>Gloss painted and lacquered MDF door</div></div>	<div><div>Replacement end colour</div><div>Gloss Dusk Grey</div></div> <div><div>Cabinet exterior</div><div>White</div></div>	<div><div>Recommended worktop</div><table><tr><th>40mm</th><th>Premium</th><th>22mm</th></tr><tr><td><div><div></div><div>Brazilian Walnut</div></div></td><td><div><div></div><div>Woodstone</div></div></td><td><div><div></div><div>Rustic Oak</div></div></td></tr></table></div>	40mm	Premium	22mm	<div><div></div><div>Brazilian Walnut</div></div>	<div><div></div><div>Woodstone</div></div>	<div><div></div><div>Rustic Oak</div></div>
40mm	Premium	22mm							
<div><div></div><div>Brazilian Walnut</div></div>	<div><div></div><div>Woodstone</div></div>	<div><div></div><div>Rustic Oak</div></div>							
<div><div>GLOSS MUSSEL</div><div></div></div>	<div><div>Door/drawer front thickness</div><div>18mm</div></div> <div><div>Door/drawer material and construction</div><div>Gloss painted and lacquered MDF door</div></div>	<div><div>Replacement end colour</div><div>Gloss Mussel</div></div> <div><div>Cabinet exterior</div><div>Ivory</div></div>	<div><div>Recommended worktop</div><table><tr><th>40mm</th><th>Premium</th><th>22mm</th></tr><tr><td><div><div></div><div>Copper Slate</div></div></td><td><div><div></div><div>Volcanic Ash</div></div></td><td><div><div></div><div>Mystic Pine</div></div></td></tr></table></div>	40mm	Premium	22mm	<div><div></div><div>Copper Slate</div></div>	<div><div></div><div>Volcanic Ash</div></div>	<div><div></div><div>Mystic Pine</div></div>
40mm	Premium	22mm							
<div><div></div><div>Copper Slate</div></div>	<div><div></div><div>Volcanic Ash</div></div>	<div><div></div><div>Mystic Pine</div></div>							
<div><div>GLOSS PEARL GREY</div><div></div></div>	<div><div>Door/drawer front thickness</div><div>18mm</div></div> <div><div>Door/drawer material and construction</div><div>Gloss painted and lacquered MDF door</div></div>	<div><div>Replacement end colour</div><div>Gloss Pearl Grey</div></div> <div><div>Cabinet exterior</div><div>White</div></div>	<div><div>Recommended worktop</div><table><tr><th>40mm</th><th>Premium</th><th>22mm</th></tr><tr><td><div><div></div><div>Brazilian Walnut</div></div></td><td><div><div></div><div>Liberty Rock</div></div></td><td><div><div></div><div>Mystic Pine</div></div></td></tr></table></div>	40mm	Premium	22mm	<div><div></div><div>Brazilian Walnut</div></div>	<div><div></div><div>Liberty Rock</div></div>	<div><div></div><div>Mystic Pine</div></div>
40mm	Premium	22mm							
<div><div></div><div>Brazilian Walnut</div></div>	<div><div></div><div>Liberty Rock</div></div>	<div><div></div><div>Mystic Pine</div></div>							
<div><div>GLOSS PURE WHITE</div><div></div></div>	<div><div>Door/drawer front thickness</div><div>18mm</div></div> <div><div>Door/drawer material and construction</div><div>Gloss painted and lacquered MDF door</div></div>	<div><div>Replacement end colour</div><div>Gloss Pure White</div></div> <div><div>Cabinet exterior</div><div>White</div></div>	<div><div>Recommended worktop</div><table><tr><th>40mm</th><th>Premium</th><th>22mm</th></tr><tr><td><div><div></div><div>Brazilian Walnut</div></div></td><td><div><div></div><div>Liberty Rock</div></div></td><td><div><div></div><div>Brazilia</div></div></td></tr></table></div>	40mm	Premium	22mm	<div><div></div><div>Brazilian Walnut</div></div>	<div><div></div><div>Liberty Rock</div></div>	<div><div></div><div>Brazilia</div></div>
40mm	Premium	22mm							
<div><div></div><div>Brazilian Walnut</div></div>	<div><div></div><div>Liberty Rock</div></div>	<div><div></div><div>Brazilia</div></div>							
<div><div>MATT ANTHRACITE</div><div></div></div>	<div><div>Door/drawer front thickness</div><div>18mm</div></div> <div><div>Door/drawer material and construction</div><div>Matt painted MDF door</div></div>	<div><div>Replacement end colour</div><div>Matt Anthracite</div></div> <div><div>Cabinet exterior</div><div>White</div></div>	<div><div>Recommended worktop</div><table><tr><th>40mm</th><th>Premium</th><th>22mm</th></tr><tr><td><div><div></div><div>Marble Siroco</div></div></td><td><div><div></div><div>Cloudy Cement</div></div></td><td><div><div></div><div>Rustic Oak</div></div></td></tr></table></div>	40mm	Premium	22mm	<div><div></div><div>Marble Siroco</div></div>	<div><div></div><div>Cloudy Cement</div></div>	<div><div></div><div>Rustic Oak</div></div>
40mm	Premium	22mm							
<div><div></div><div>Marble Siroco</div></div>	<div><div></div><div>Cloudy Cement</div></div>	<div><div></div><div>Rustic Oak</div></div>							
<div><div>MATT DARK WALNUT</div><div></div></div>	<div><div>Door/drawer front thickness</div><div>18mm</div></div> <div><div>Door/drawer material and construction</div><div>Timber effect MDF door with 1mm PVC-edging</div></div>	<div><div>Replacement end colour</div><div>Dark Walnut</div></div> <div><div>Cabinet exterior</div><div>White</div></div>	<div><div>Recommended worktop</div><table><tr><th>40mm</th><th>Premium</th><th>22mm</th></tr><tr><td><div><div></div><div>Marble Siroco</div></div></td><td><div><div></div><div>Cloudy Cement</div></div></td><td><div><div></div><div>Designer White</div></div></td></tr></table></div>	40mm	Premium	22mm	<div><div></div><div>Marble Siroco</div></div>	<div><div></div><div>Cloudy Cement</div></div>	<div><div></div><div>Designer White</div></div>
40mm	Premium	22mm							
<div><div></div><div>Marble Siroco</div></div>	<div><div></div><div>Cloudy Cement</div></div>	<div><div></div><div>Designer White</div></div>							
<div><div>MATT PURE WHITE</div><div></div></div>	<div><div>Door/drawer front thickness</div><div>18mm</div></div> <div><div>Door/drawer material and construction</div><div>Matt painted MDF door</div></div>	<div><div>Replacement end colour</div><div>Matt Pure White</div></div> <div><div>Cabinet exterior</div><div>White</div></div>	<div><div>Recommended worktop</div><table><tr><th>40mm</th><th>Premium</th><th>22mm</th></tr><tr><td><div><div></div><div>Brazilian Walnut</div></div></td><td><div><div></div><div>Liberty Rock</div></div></td><td><div><div></div><div>Brazilia</div></div></td></tr></table></div>	40mm	Premium	22mm	<div><div></div><div>Brazilian Walnut</div></div>	<div><div></div><div>Liberty Rock</div></div>	<div><div></div><div>Brazilia</div></div>
40mm	Premium	22mm							
<div><div></div><div>Brazilian Walnut</div></div>	<div><div></div><div>Liberty Rock</div></div>	<div><div></div><div>Brazilia</div></div>							
<div><div>MATT RUSTIC OAK</div><div></div></div>	<div><div>Door/drawer front thickness</div><div>18mm</div></div> <div><div>Door/drawer material and construction</div><div>Timber effect MDF door with 1mm PVC-edging</div></div>	<div><div>Replacement end colour</div><div>Rustic Oak</div></div> <div><div>Cabinet exterior</div><div>White</div></div>	<div><div>Recommended worktop</div><table><tr><th>40mm</th><th>Premium</th><th>22mm</th></tr><tr><td><div><div></div><div>Dark Ash</div></div></td><td><div><div></div><div>Liberty Rock</div></div></td><td><div><div></div><div>Rustic Oak</div></div></td></tr></table></div>	40mm	Premium	22mm	<div><div></div><div>Dark Ash</div></div>	<div><div></div><div>Liberty Rock</div></div>	<div><div></div><div>Rustic Oak</div></div>
40mm	Premium	22mm							
<div><div></div><div>Dark Ash</div></div>	<div><div></div><div>Liberty Rock</div></div>	<div><div></div><div>Rustic Oak</div></div>							

# RANGE OVERVIEW



Aluminium Inline Handle




Black Inline Handle



Chrome Wave Inline Handle

## INSET HANDLE WALL UNITS

The inset handle can be added to all wall units, bifolds and bridging cupboards and is to be designed with standard handles on base units to create a subtle, more streamlined design option for the modern kitchen.



### Inset Handle Range Availability

Alta Gloss

Alta Matt

Inline Form

Inline Select

Inline Trend

Minnesota

Plaza

Virginia

Woodbury

# WORKTOPS

Creativity doesn't have to stop with your furniture but can extend to your worktop. Durable with easy-clean technology, our range of work surfaces offer individuality in your kitchen.

## 22mm LAMINATED PVC SQUARE EDGED WORKTOPS

These stunning 22mm worktops feature subtle textured surfaces and are the cutting edge of laminate worktop design.



Brazillia



Dark Oak



Designer White




Mystic Pine




Rustic Oak

## 40mm POSTFORMED & PVC SQUARE EDGED WORKTOPS

Our 40mm worktops are supplied in a bullnose or PVC edged specification and are available with co-ordinating upstands and splashbacks.



Alaska



Alpine White



Brazilian Walnut



Copper Slate




Dark Ash



Everest Black




Marble Siroco



Natural Ash



Oak Block



Pastel Oak



Riverside Beige



Riverside Grey



Stella Mare



Tectonica

# WORKTOPS

## 40mm PREMIUM POSTFORMED WORKTOPS


Our range of premium worktops have been developed to have a tighter radius of 3mm for a more contemporary look and feel.



Chalet Oak



Cinnamon



Cloudy Cement



Colmar Oak



Liberty Rock



Platinum Metallic




Roman Oak  
(Available July 2019)



Venice Marble  
(Available July 2019)



Volcanic Ash



Woodstone

# WORKTOPS

## GRANITE WORKTOPS

There's nothing quite like a genuine granite work surface. Extremely durable, 30mm thick, easy to clean, heat resistant and of course, stunningly beautiful. No two pieces of granite are identical, so each kitchen is totally unique.



Azul Platino




Baltic Brown



Bengal Black



Brazil Gold



Brown Silk



Colonial Persa



Fox Brown



Penalva



Star Galaxy



Steel Grey



Tan Brown



Verde Ubatuba

## SILESTONE WORKTOPS

Available in 20mm our scratch resistant Silestone Quartz has radiant clarity and exceptional strength. Silestone is available in a range of creative colours.



Arden Blue



Blanco City



Blanco Norte



Cemento Spa



Gris Expo



Marengo



Nero Tebas



Noka



Nymbus



Rougui



Royal Reef




White Storm

# GLASS UPSTANDS & SPLASHBACKS

A range of contemporary and subtle colours to suit any style of kitchen and complement our worktop selection. Our standard range are available off the shelf, whilst our special order finishes are made to order in a variety of eye catching colours. A full template and fit upgrade option is available on the special order finishes.

## STANDARD

This collection features the four core splashback colours.



Bride



Chalk White



Ebony




Pewter



## GLOSS COLLECTION


Our Gloss Collection feature a diverse palette of colours that match and complement a variety of the kitchen finishes, accent open display units and include three metallic effect styles.




Anthracite



Blue



Bronze




Cashmere




Dark Stone



Gold




Lava



Light Stone



Midnight Stardust



Platinum



Sage



Stone



White Sparkle



Yellow



# REPLACEMENT CABINET ENDS

To enhance the finish of a selection of our kitchens, replacement cabinet end panels are available to order.

The replacement end panels are designed to be fitted to the exposed ends of a unit run only. On base and tall units (for example larger units and tall appliance housings) the replacement cabinet end panel is a full length panel extending to the floor and therefore additional blender panels will not be required.

**Please note: Belfast sink units, worktop dressers, over appliance units, 45° units, diagonal wall units and reduced depth base cabinets are not available with replacement cabinet ends.**

RANGE	DOOR COLOUR	RECOMMENDED CABINET	REPLACEMENT END EXTERNAL COLOUR	REPLACEMENT END INTERNAL COLOUR	REPLACEMENT END GRAIN DIRECTION
Alta	Matt Anthracite	White	Matt Anthracite	Matt Anthracite	N/A
Alta	Matt Dark Walnut	White	Matt Dark Walnut	Matt Dark Walnut	Vertical
Alta	Matt Pure White	White	Matt Pure White	Matt Pure White	N/A
Alta	Matt Rustic Oak	White	Matt Rustic Oak	Matt Rustic Oak	Vertical
Alta	Gloss Dusk Grey	White	Gloss Dusk Grey	Matt Dusk Grey	N/A
Alta	Gloss Mussel	Ivory	Gloss Mussel	Matt Mussel	N/A
Alta	Gloss Pearl Grey	White	Gloss Pearl Grey	Matt Pearl Grey	N/A
Alta	Gloss Pure White	White	Gloss Pure White	Matt Pure White	N/A
Cranbrook	Cobble Grey	White	Cobble Grey	Cobble Grey	N/A
Cranbrook	Ivory	Ivory	Ivory	Ivory	N/A
Cranbrook	Platinum	White	Platinum	Platinum	N/A
Cranbrook	Sage	Ivory	Sage	Sage	N/A
Cranbrook	Stone	Ivory	Stone	Stone	N/A
Minnesota	Avola Grey	White	Avola Grey	Avola Grey	Vertical
New York	Gloss Cashmere	White	Gloss Cashmere	Matt Cashmere	N/A
New York	Gloss Dusk Grey	White	Gloss Dusk Grey	Matt Dusk Grey	N/A
New York	Gloss Ivory	Ivory	Gloss Ivory	Matt Ivory	N/A
New York	Gloss Pearl Grey	White	Gloss Pearl Grey	Matt Pearl Grey	N/A
New York	Gloss White	White	Gloss White	Matt White	N/A
New York	Matt Anthracite	White	Matt Anthracite	Matt Anthracite	N/A
Plaza	Cashmere	White	Textured Cashmere	Matt Cashmere	Vertical
Plaza	Cobble Grey	White	Textured Cobble Grey	Matt Cobble Grey	Vertical
Plaza	Mussel	Ivory	Textured Mussel	Matt Mussel	Vertical
Plaza	Porcelain	White	Textured Porcelain	Matt Porcelain	Vertical
Plaza	Stone	Ivory	Textured Stone	Matt Stone	Vertical
Quadra	Cobble Grey	White	Cobble Grey	Cobble Grey	N/A
Quadra	White	White	White	White	N/A
Woodbury	Gloss Anthracite	White	Gloss Anthracite	Matt Charcoal	N/A
Woodbury	Gloss Cashmere	White	Gloss Cashmere	Matt Cashmere	N/A
Woodbury	Gloss Ivory	Ivory	Gloss Ivory	Matt Ivory	N/A
Woodbury	Gloss Platinum	White	Gloss Platinum	Matt Platinum	N/A
Woodbury	Gloss White	White	Gloss White	Matt White	N/A

# REPLACEMENT CABINET ENDS AND BLENDER PANELS

Cabinets are available in white, ivory, and blonde oak. Depending on the door and colour chosen, you may prefer to colour match the outside of the cabinets using **blender panels** or **replacement ends**.

This kitchen, in Woodbury Anthracite on a white cabinet, demonstrates the strong contrast achieved by leaving the cabinet sides exposed.



In this example, the sides of the cabinets have been covered using frontal matched blender panels, which are available in the majority of ranges. Frontal matching plinth has also been used.



Alternatively, 'replacement end' cabinets are available in selected ranges:

- All gloss finishes
- Matt contemporary finishes (with the exception of Paint to Order ranges)
- Quadra
- Cranbrook



Replacement ends are factory-fitted, in place of the cabinet side. On base and tall units, it is a 'gable end' which reaches the floor, avoiding the need for a plinth return along the side of the cabinet. On wall cabinets, the replacement end is the same size as a standard side panel.

Refer to the 'cabinet codes' page for details of how to order.  
Refer to page 26 for available colours.

Please note that the grain on a replacement end may run in the opposite direction to the door. Refer to the Range Overview for details.

# MIX AND MATCH

The complementary tones of two contrasting ranges in the same kitchen creates the luxury modern kitchen environment. Mix and match is available with Contemporary ranges on 18mm cabinets and can be completed with a selection of framing effects, handle options and worktop finishes.

## MIX & MATCH STYLES

Eight design styles are available based on the group of units where the accent range is located.














Image shows Style 2 - Accent Wall Units









# UNIT CONTENT

FULL HEIGHT DOOR BASE CABINETS		WIDTH	CODE
	Reduced Depth Single Base Cabinets H: 870mm D: 285mm Hand by hinge (BU1503F and BU253F have Joined Frame and door in New England) Single adjustable shelf	150mm	<b>BU1503F</b>
		255mm	<b>BU253F</b>
		300mm	<b>BU33F</b>
		400mm	<b>BU43F</b>
		450mm	<b>BU453F</b>
		500mm	<b>BU53F</b>
		600mm	<b>BU63F</b>
	Reduced Depth Double Base Cabinet H: 870mm D: 285mm Single adjustable shelf	800mm	<b>BU83F</b>
		900mm	<b>BU93F</b>
		1000mm	<b>BU103F</b>
	Single Base Cabinets H: 870mm D: 570mm Hand by hinge (BU1506F and BU256F have Joined Frame and door in New England) Single adjustable shelf	150mm	<b>BU1506F</b>
		255mm	<b>BU256F</b>
		300mm	<b>BU36F</b>
		400mm	<b>BU46F</b>
		450mm	<b>BU456F</b>
		500mm	<b>BU56F</b>
		600mm	<b>BU66F</b>
	Single Base Cabinets with Kesseböhmer Storage H: 870mm D: 570mm (Joined Frame and door in New England)	150mm with Basket	<b>BU1506BAFAR</b>
		150mm with Basket/Towel	<b>BU1506TOFAR</b>
		300mm with Basket	<b>BU36BAFAR</b>
	Single Base Cabinets with Pull Out Waste Disposal (Bins not fitted) H: 870mm D: 570mm Frontal supplied loose Not available in New England	500mm with Premium Waste Bin	<b>BU56PBIF</b>
		600mm with Premium Waste Bin	<b>BU66PBIF</b>
		600mm with 60L Recycle Bin	<b>BU66BIF</b>
	Double Base Cabinets H: 870mm D: 570mm Single adjustable shelf	800mm	<b>BU86F</b>
		900mm	<b>BU96F</b>
		1000mm	<b>BU106F</b>
		1200mm	<b>BU126F</b>
	Corner Base Cabinets H: 870mm D: 570mm Handing required for all specifications Hand by blank, i.e for left hand door/wirework order RHB and vice versa for right hand, right hand blank shown (Joined Frame and door on New England) Single adjustable shelf	800mm with 300 Door	<b>CB86FB</b>
		800mm with 400 Door	<b>CB86FA</b>
		800mm with 500 Door	<b>CB86FC</b>
		900mm with 450 Door	<b>CB96FA</b>
		1000mm with 400 Door	<b>CB106FB</b>
		1000mm with 500 Door	<b>CB106FA</b>
		1000mm with 600 Door	<b>CB106FC</b>
		1200mm with 600 Door	<b>CB126FA</b>
	Corner Base Cabinets with Flexible Corner Post H: 870mm D: 570mm Handing required, hand by the blank. Order RHB for left hand door and vice versa for LHB, right hand blank shown Single adjustable shelf	800mm with 300 Door	<b>CB86FBFP</b>
		800mm with 400 Door	<b>CB86FAFP</b>
		800mm with 500 Door	<b>CB86FCFP</b>
		900mm with 450 Door	<b>CB96FAFP</b>
		1000mm with 400 Door	<b>CB106FBFP</b>
		1000mm with 500 Door	<b>CB106FAFP</b>
		1000mm with 600 Door	<b>CB106FCFP</b>
		1200mm with 600 Door	<b>CB126FAFP</b>
	Corner Base Cabinets with Kesseböhmer Storage H: 870mm D: 570mm Handing required for all specifications Hand by blank, i.e for left hand door/wirework order RHB and vice versa for right hand, right hand blank shown (Joined Frame and door on New England)	800mm with 400 Door/Le Mans	<b>CB86LMFAAR</b>
		900mm with 450 Door/Le Mans	<b>CB96LMFAAR</b>
		1000mm with 400 Door/Le Mans	<b>CB106LMFBAR</b>
		1000mm with 500 Door/Le Mans	<b>CB106LMFAAR</b>
		1000mm with 600 Door/Le Mans	<b>CB106LMFCAR</b>
		1200mm with 600 Door/Le Mans	<b>CB126LMFAAR</b>









# UNIT CONTENT

FULL HEIGHT DOOR BASE CABINETS		WIDTH	CODE
	Corner Cabinet H: 870mm D: 570mm Single adjustable shelf Hand by blank, right hand blank shown 110° hinges Add 'FP' suffix for a frontal matched flexible corner post Add 'BO' suffix for no corner post	1200mm Two 400 Doors	<b>CB126FE</b>
		1200mm 300 Door and 400 Doors	<b>CB126FF</b>
	Corner Cabinet H: 870mm D: 570mm Single adjustable shelf Hand by blank, right hand blank shown 110° hinges Add 'FP' suffix for a frontal matched flexible corner post Add 'BO' suffix for no corner post	1200mm 600 Door	<b>CB126FA</b>
	1 Piece 'L' Shape Corner Base Cabinet H: 870mm D: 570mm Single adjustable shelf Supplied Ready for Assembly (Joined Frame and door on New England)	930x930mm	<b>LSB991PCF</b>
		1030x1030mm	<b>LSB101PCF</b>
	1 Piece 'L' Shape Corner Base Cabinet with Kesseböhmer Storage H: 870mm D: 570mm Supplied Ready for Assembly (Joined Frame and door on New England)	930x930mm with 3/4 Carousel	<b>LCB991PCFAR</b>
	Convex Curved Island Base Cabinet H: 870mm D: 285mm See pages 08-17 for range availability Single adjustable shelf Supplied Ready for Assembly Front cabinet edges are 0.6mm PVC edging. (includes curved frontal matched plinth) Hand by hinge	300mm	<b>BISL372CU</b>
	Convex Curved Base Cabinet H: 870mm D: 570mm See pages 08-17 for range availability Single adjustable shelf Supplied Ready for Assembly Front cabinet edges are 0.6mm PVC edging. (includes curved frontal matched plinth) Hand by hinge	300mm	<b>BWE372CU</b>
	Concave Corner Base Cabinet H: 870mm D: 570mm See pages 08-17 for range availability Supplied Ready for Assembly with a 15mm solid back and 0.6mm PVC edging to front of cabinet and shelf (includes concave frontal matched plinth) Single adjustable shelf Only suitable for use with solid surface worktops Hand by hinge	930x930mm	<b>COB991PCF</b>
FLAP DOWN BASE CABINETS		WIDTH	CODE
	Flap Down Base Cabinets H: 362mm D: 300mm Available with Contemporary and Inline ranges only To be wall hung (no legs supplied)	500mm	<b>OCH536D</b>
		600mm	<b>OCH636D</b>
		800mm	<b>OCH836D</b>
		900mm	<b>OCH936D</b>
		1000mm	<b>OCH1036D</b>

# UNIT CONTENT












DRAWER LINE BASE CABINETS		WIDTH	CODE
	Reduced Depth	300mm	<b>BU33D</b>
	Single Base Cabinets	400mm	<b>BU43D</b>
	H: 870mm D: 285mm	450mm	<b>BU453D</b>
	Hand by hinge	500mm	<b>BU53D</b>
	Dummy Drawer	600mm	<b>BU63D</b>
	Single adjustable shelf		
	Not available in Inline		
	Double Reduced Depth Base Unit	800mm	<b>BU83D</b>
	H: 870mm D: 285mm	900mm	<b>BU93D</b>
	Two dummy drawers	1000mm	<b>BU103D</b>
	Single Base Cabinets	300mm	<b>BU36D</b>
	H: 870mm D: 570mm	400mm	<b>BU46D</b>
	Hand by hinge	450mm	<b>BU456D</b>
	Single adjustable shelf	500mm	<b>BU56D</b>
	Not available in Inline	600mm	<b>BU66D</b>
	Double Base Cabinets	800mm	<b>BU86D</b>
	H: 870mm D: 570mm	900mm	<b>BU96D</b>
	Single adjustable shelf	1000mm	<b>BU106D</b>
	Not available in Inline	1200mm	<b>BU126D</b>
	Corner Base Cabinets	800mm with 300 Door	<b>CB86DB</b>
	H: 870mm D: 570mm	800mm with 400 Door	<b>CB86DA</b>
	Handing required, hand by the blank. Order RHB for left hand door and vice versa for LHB, right hand blank shown	800mm with 500 Door	<b>CB86DC</b>
	Single adjustable shelf	900mm with 450 Door	<b>CB96DA</b>
	Not available in Inline	1000mm with 400 Door	<b>CB106DB</b>
		1000mm with 400 Door	<b>CB106DA</b>
		1000mm with 600 Door	<b>CB106DC</b>
		1200mm with 600 Door	<b>CB126DA</b>
	Corner Base Cabinets with Flexible Corner Post	800mm with 300 Door	<b>CB86DBFP</b>
	H: 870mm D: 570mm	800mm with 400 Door	<b>CB86DAFP</b>
	Handing required, hand by the blank. Order RHB for left hand door and vice versa for LHB, right hand blank shown	800mm with 500 Door	<b>CB86DCFP</b>
	Single adjustable shelf	900mm with 450 Door	<b>CB96DAFP</b>
	Not available in Inline	1000mm with 400 Door	<b>CB106DBFP</b>
		1000mm with 500 Door	<b>CB106DAFP</b>
		1000mm with 600 Door	<b>CB106DCFP</b>
		1200mm with 600 Door	<b>CB126DAFP</b>
	Corner Base Cabinets with Kesseböhmer Storage	800mm with 400 Door/Le Mans	<b>CB86LMDAAR</b>
	H: 870mm D: 570mm	900mm with 450 Door/Le Mans	<b>CB96LMDAAR</b>
	Dummy Drawer	1000mm with 400 Door/Le Mans	<b>CB106LMDBAR</b>
	Handing required, hand by the blank. Order RHB for left hand door/wirework and vice versa for LHB, right hand blank shown	1000mm with 500 Door/Le Mans	<b>CB106LMDAAR</b>
	(Joined Frame and door in New England)	1000mm with 600 Door/Le Mans	<b>CB106LMDCAR</b>
	Single adjustable shelf	1200mm with 600 Door/Le Mans	<b>CB126LMDAAR</b>
	Not available in Inline		
	Corner Cabinet	1200mm 300 and 400 Doors	<b>CB126DF</b>
	H: 870mm D: 570mm	1200mm Two 400 Doors	<b>CB126DE</b>
	Two drawers		
Single adjustable shelf			
Hand by blank, right hand blank shown			
110° hinges			
Add 'FP' suffix for a frontal matched flexible corner post			
Add 'BO' suffix for no corner post			
Not available in Inline			

# UNIT CONTENT











DRAWER LINE BASE CABINETS		WIDTH	CODE
	1 Piece 'L' Shape Corner Base Cabinet H: 870mm D: 570mm Single adjustable shelf Dummy Drawers Supplied Ready for Assembly (Joined Frame and door in New England) Not available in Inline	930x930mm	<b>LSB991PCD</b>
		1030x1030mm	<b>LSB101PCD</b>
	1 Piece 'L' Shape Corner Base Cabinet with Kesseböhmer Storage H: 870mm D: 570mm Dummy Drawers Supplied Ready for Assembly (Joined Frame and door on New England) Not available in Inline	930x930mm with 3/4 Carousel	<b>LCB991PCDAR</b>
SINK BASE CABINETS		WIDTH	CODE
	Full Height Single Sink Cabinets H: 870mm D: 570mm Hand by hinge Single adjustable shelf Includes sink liner	500mm	<b>SU56SLF</b>
		600mm	<b>SU66SLF</b>
	Drawer Line Single Sink Cabinets H: 870mm D: 570mm Hand by hinge Dummy Drawer Includes sink liner Single adjustable shelf Not available in Inline	500mm	<b>SU56SLD</b>
		600mm	<b>SU66SLD</b>
	Full Height Double Sink Cabinets H: 870mm D: 570mm Single adjustable shelf Includes sink liner	800mm	<b>SU86SLF</b>
		900mm	<b>SU96SLF</b>
		1000mm	<b>SU106SLF</b>
		1200mm	<b>SU126SLF</b>
	Drawer Line Sink Cabinets H: 870mm D: 570mm x1 Dummy Drawer, x1 Working Drawer Hand by drainer i.e left hand (LHD) supplied with right hand dummy drawer Includes sink liner Single adjustable shelf Not available in Inline	800mm	<b>SU86SLD</b>
		900mm	<b>SU96SLD</b>
		1000mm	<b>SU106SLD</b>
		1200mm	<b>SU126SLD</b>
	Drawer Line Double Sink Cabinets H: 870mm D: 570mm x2 Dummy Drawers Includes sink liner Single adjustable shelf Not available in Inline	800mm	<b>SU86SLDAI</b>
		900mm	<b>SU96SLDAI</b>
		1000mm	<b>SU106SLDAI</b>
		1200mm	<b>SU126SLDAI</b>
	3 Drawer Sink Cabinet H: 870mm D: 570mm Dummy top drawer, middle and bottom cut away drawers	800mm	<b>PD86D3SU3</b>
		900mm	<b>PD96D3SU3</b>
		1000mm	<b>PD106D3SU3</b>













# UNIT CONTENT

SINK BASE CABINETS		WIDTH	CODE
	2 Drawer Sink Cabinet H: 870mm D: 570mm Top and bottom cut away drawers	800mm	PD86D2SU2
		900mm	PD96D2SU2
	Single Belfast Sink Cabinet H: 600mm D: 570mm Hand by hinge 450 high door Includes sink liner Available in Classic ranges only (Not compatible with laminate worktops)	600mm	BSU66SLF
	Double Belfast Sink Cabinet H: 600mm D: 570mm x2 450x450mm doors Includes sink liner Available in Classic ranges only (Not compatible with laminate worktops)	900mm	BSU96SLF
DRAWER BASE CABINETS		WIDTH	CODE
	Four Drawer Base Cabinet with x4 Shallow Drawers H: 870mm D: 570mm Not available in Inline	400mm	DU46D
		500mm	DU56D
		600mm	DU66D
	Full Height Base Cabinet with x4 Shallow Internal Drawers H: 870mm D: 570mm Hand by hinge (Joined Frame and door on New England)	300mm	BU36F4ID
		400mm	BU46F4ID
		450mm	BU456F4ID
		500mm	BU56F4ID
		600mm	BU66F4ID
	Full Height Base Cabinet with x3 Internal Deep Drawers H: 870mm D: 570mm Hand by hinge (Joined Frame and door on New England)	300mm	BU36F3ID
		400mm	BU46F3ID
		450mm	BU456F3ID
		500mm	BU56F3ID
		600mm	BU66F3ID
	Full Height Base Cabinet with x1 Shallow Internal Drawer & x2 Internal Deep Drawers H: 870mm D: 570mm Hand by hinge (Joined Frame and door on New England)	300mm	BU36F3IDC
		400mm	BU46F3IDC
		450mm	BU456F3IDC
		500mm	BU56F3IDC
		600mm	BU66F3IDC
	Full Height Base Cabinet with x1 Pull Out Deep Drawer (attached to door), x1 Internal Deep Drawer & x1 Internal Shallow Drawer H: 870mm D: 570mm (Joined Frame and door on New England)	600mm	BU66F2ID
	Three Drawer Cabinet with x1 Shallow Drawer & 2 Deep Pan Drawers H: 870mm D: 570mm	500mm	PD56D3
		600mm	PD66D3
		800mm	PD86D3
		900mm	PD96D3
		1000mm	PD106D3
	Two Drawer Cabinet with x2 Deep Pan Drawers H: 870mm D: 570mm	500mm	PD56D2
		600mm	PD66D2
		800mm	PD86D2
		900mm	PD96D2
	Two Drawer Cabinet with x2 Deep Pan Drawers & 1 Internal Shallow Drawer H: 870mm D: 570mm	500mm	PD56D2IDT
		600mm	PD66D2IDT
		800mm	PD86D2IDT
		900mm	PD96D2IDT










# UNIT CONTENT

FEATURE BASE CABINETS		WIDTH	CODE
	<p>Wicker Basket Cabinet H: 870mm D: 570mm Available in Classic ranges only PTO cabinets are a flat finish, except for Premium Specification cabinets in Classic PTO ranges, which are veneered</p>	500mm (Melamine; Ivory, Blonde Oak and White)	<b>WBU56D</b>
		500mm (Paint to Order)	<b>WBU56DPTO</b>
	<p>Tea Tray Cabinet H: 870mm D: 570mm Available in Classic ranges only Comes with spice drawer and 2 oak tea trays PTO cabinets are a flat finish, except for Premium Specification cabinets in Classic PTO ranges, which are veneered</p>	150mm (Melamine; Ivory, Blonde Oak and White)	<b>TTU150</b>
		150mm (Paint to Order)	<b>TTU150PTO</b>
	<p>Base Wine Rack Cabinet H: 870mm D: 285mm Four wine racks, holds up to 12 bottles PTO cabinets are a flat finish, except for Premium Specification cabinets in Classic PTO ranges, which are veneered</p>	300mm (Melamine; Ivory, Blonde Oak and White)	<b>BWR3T</b>
		300mm (Paint to Order)	<b>BWR3PTO</b>
	<p>Base Spice/Wine Rack Cabinet H: 870mm D: 285mm Five wine shelves Holds up to 5 bottles PTO cabinets are a flat finish, except for Premium Specification cabinets in Classic PTO ranges, which are veneered</p>	150mm (Melamine; Ivory, Blonde Oak and White)	<b>SPWR15</b>
		150mm (Paint to Order)	<b>SPWR15PTO</b>
	<p>Base Open Display Cabinet H: 870mm D: 285mm Order ODUFRAME separately PTO cabinets are a flat finish, except for Premium Specification cabinets in Classic PTO ranges, which are veneered</p>	500mm (Melamine; Ivory, Blonde Oak and White)	<b>ODB5</b>
		500mm (Paint to Order)	<b>ODB5PTO</b>
	<p>Base Accent Open Display Cabinets H: 870mm D: 285mm Available in MFC colours Blue, Cashmere and Dark Oak</p>	500mm	<b>ODUB572AC</b>
		600mm	<b>ODUB672AC</b>
	<p>Base Open Display Cabinet with Plate Rack H: 870mm D: 285mm Available in Classic ranges only Order ODUFRAME separately PTO cabinets are a flat finish, except for Premium Specification cabinets in Classic PTO ranges, which are veneered</p>	500mm (Melamine; Ivory, Blonde Oak and White)	<b>ODMB85</b>
		500mm (Paint to Order)	<b>ODMB85PTO</b>
	<p>Base Open Display Cabinet with Lattice Wine Rack H: 870mm D: 285mm Available in Classic ranges only Order ODUFRAME separately PTO cabinets are a flat finish, except for Premium Specification cabinets in Classic PTO ranges, which are veneered</p>	500mm (Melamine; Ivory, Blonde Oak and White)	<b>ODMB95</b>
		500mm (Paint to Order)	<b>ODMB95PTO</b>
	<p>Base Open Display Cabinet with Plate &amp; Lattice Wine Rack H: 870mm D: 285mm Available in Classic ranges only Order ODUFRAME separately PTO cabinets are a flat finish, except for Premium Specification cabinets in Classic PTO ranges, which are veneered</p>	500mm (Melamine; Ivory, Blonde Oak and White)	<b>ODMB105</b>
		500mm (Paint to Order)	<b>ODMB105PTO</b>
	<p>Open Display Cabinet Frame H: 724mm</p>	500mm (Melamine; Ivory, Blonde Oak and White)	<b>ODUFRAME</b>
		500mm (Paint to Order)	<b>ODUFRAMEPTO</b>











# UNIT CONTENT

LOW WALL CABINETS		WIDTH	285mm STANDARD DEPTH	330mm PREMIUM DEPTH
	Single Wall Cabinets H: 561mm Hand by hinge Single adjustable shelf Not available in New England	300mm	<b>WU356</b>	<b>WU356P</b>
		400mm	<b>WU456</b>	<b>WU456P</b>
		450mm	<b>WU4556</b>	<b>WU4556P</b>
		500mm	<b>WU556</b>	<b>WU556P</b>
		600mm	<b>WU656</b>	<b>WU656P</b>
	Premium Single Wall Cabinets with LED Illuminated Base Panel (Includes transformer) H: 561mm Hand by hinge Single adjustable shelf Not available in New England	300mm	N/A	<b>WU356PIL</b>
		400mm	N/A	<b>WU456PIL</b>
		450mm	N/A	<b>WU4556PIL</b>
		500mm	N/A	<b>WU556PIL</b>
		600mm	N/A	<b>WU656PIL</b>
	Single Wall Cabinets with Inset Handle H: 561mm Hand by hinge Single adjustable shelf Available in Contemporary and Inline ranges, (excludes Quadra, New York and Paint to Order ranges) only	300mm	<b>WU356IN</b>	<b>WU356PIN</b>
		400mm	<b>WU456IN</b>	<b>WU456PIN</b>
		450mm	<b>WU4556IN</b>	<b>WU4556PIN</b>
		500mm	<b>WU556IN</b>	<b>WU556PIN</b>
		600mm	<b>WU656IN</b>	<b>WU656PIN</b>
	Premium Single Wall Cabinets with LED Illuminated Base Panel and Inset Handle (Includes transformer) H: 561mm Hand by hinge Single adjustable shelf Available in Contemporary and Inline ranges, (excludes New York, Quadra and Paint to Order ranges) only	300mm	N/A	<b>WU356PINIL</b>
		400mm	N/A	<b>WU456PINIL</b>
		450mm	N/A	<b>WU4556PINIL</b>
		500mm	N/A	<b>WU556PINIL</b>
		600mm	N/A	<b>WU656PINIL</b>
	Double Wall Cabinets H: 561mm Single adjustable shelf Not available in New England	800mm	<b>WU856</b>	<b>WU856P</b>
		900mm	<b>WU956</b>	<b>WU956P</b>
		1000mm	<b>WU1056</b>	<b>WU1056P</b>
	Double Wall Cabinets with Inset Handle H: 561mm Single adjustable shelf Available in Contemporary and Inline ranges, (excludes Quadra, New York and Paint to Order ranges) only	800mm	<b>WU856IN</b>	<b>WU856PIN</b>
		900mm	<b>WU956IN</b>	<b>WU956PIN</b>
		1000mm	<b>WU1056IN</b>	<b>WU1056PIN</b>
	Canopy Extractor Wall Cabinet H: 561mm Hand by hinge Includes ducting Available with white cabinet only	600mm	<b>CANWUEX656</b>	<b>CANEXT656D</b>
	Canopy Extractor Wall Cabinet with Inset Handle H: 561mm Hand by hinge Includes ducting Available in Contemporary and Inline ranges, (excludes New York, Quadra and Paint to Order ranges) only Available with white cabinet only	600mm	<b>CANWUEX656IN</b>	<b>CANEXT656IND</b>
	Corner Wall Cabinet H: 561mm Hand by blank, right hand blank shown Single adjustable shelf Available in Contemporary and Inline ranges, (excludes New York, Quadra and Paint to Order ranges) only	600mm 300 Door	<b>CWU656</b>	N/A
		600mm 400 Door	<b>CWU656FB</b>	N/A
		800mm 500 Door	<b>CWU856FA</b>	N/A
		900mm 600 Door	<b>CWU956FC</b>	N/A
	Corner Wall Cabinet with Inset Handle H: 561mm Hand by blank, right hand blank shown Single adjustable shelf Available in Contemporary and Inline ranges, (excludes New York, Quadra and Paint to Order ranges) only	600mm 300 Door	<b>CWU656IN</b>	N/A
		600mm 400 Door	<b>CWU656INFB</b>	N/A
		800mm 500 Door	<b>CWU856INF A</b>	N/A
		900mm 600 Door	<b>CWU956INFC</b>	N/A









# UNIT CONTENT

FEATURE LOW WALL CABINETS		WIDTH	285mm STANDARD DEPTH	330mm PREMIUM DEPTH
	Wall Open Display Cabinet	500mm	ODU556	ODU556P
	H: 561mm Available in Melamine; Ivory, Blonde Oak and White			
	Wall Accent Open Display Cabinet	500mm	ODU556AC	ODU556PAC
	H: 561mm Available in MFC colours Blue, Cashmere and Dark Oak	600mm	ODU656AC	ODU656PAC
STANDARD WALL CABINETS		WIDTH	285mm STANDARD DEPTH	330mm PREMIUM DEPTH
	Single Wall Cabinets H: 724mm Hand by hinge Two adjustable shelves (WU15072 and WU2572 have Joined Frame and door in New England)	150mm	WU15072	WU15072P
		255mm	WU2572	WU2572P
		300mm	WU372	WU372P
		400mm	WU472	WU472P
		450mm	WU4572	WU4572P
		500mm	WU572	WU572P
		600mm	WU672	WU672P
	Premium Single Wall Cabinets with LED Illuminated Base Panel (Includes transformer) H: 724mm Hand by hinge Two adjustable shelves Not available in New England	300mm	N/A	WU372PIL
		400mm	N/A	WU472PIL
		450mm	N/A	WU4572PIL
		500mm	N/A	WU572PIL
		600mm	N/A	WU672PIL
	Single Wall Cabinets with Inset Handle H: 724mm Two adjustable shelves Hand by hinge Available in Contemporary and Inline ranges, (excludes Quadra, New York and Paint to Order ranges) only	150mm	WU15072IN	WU15072PIN
		255mm	WU2572IN	WU2572PIN
		300mm	WU372IN	WU372PIN
		400mm	WU472IN	WU472PIN
		450mm	WU4572IN	WU4572PIN
		500mm	WU572IN	WU572PIN
		600mm	WU672IN	WU672PIN
	Premium Single Wall Cabinets with LED Illuminated Base Panel and Inset Handle (Includes transformer) Hand by hinge H: 724mm Two adjustable shelves Available in Contemporary and Inline ranges, (excludes New York, Quadra and Paint to Order ranges) only	300mm	N/A	WU372PINIL
		400mm	N/A	WU472PINIL
		450mm	N/A	WU4572PINIL
		500mm	N/A	WU572PINIL
		600mm	N/A	WU672PINIL
	Double Wall Cabinets H: 724mm Two adjustable shelves	800mm	WU872	WU872P
		900mm	WU972	WU972P
		1000mm	WU1072	WU1072P
	Double Wall Cabinets with Inset Handle H: 724mm Two adjustable shelves Available in Contemporary and Inline ranges, (excludes Quadra, New York and Paint to Order ranges) only	800mm	WU872IN	WU872PIN
		900mm	WU972IN	WU972PIN
		1000mm	WU1072IN	WU1072PIN
	Bi-Fold Wall Cabinets H: 724mm One adjustable shelf Not available in New England HFWU1072 available in Contemporary ranges only	500mm	HFWU572	HFWU572P
		600mm	HFWU672	HFWU672P
		800mm	HFWU872	HFWU872P
		900mm	HFWU972	HFWU972P
		1000mm	HFWU1072	HFWU1072P









# UNIT CONTENT

STANDARD WALL CABINETS		WIDTH	285mm STANDARD DEPTH	330mm PREMIUM DEPTH
	Premium Bi-Fold Wall Cabinets with LED Illuminated Base Panel (Includes transformer) H: 724mm One adjustable shelf Not available in New England	500mm	N/A	<b>HFUW572PIL</b>
		600mm	N/A	<b>HFUW672PIL</b>
		800mm	N/A	<b>HFUW872PIL</b>
		900mm	N/A	<b>HFUW972PIL</b>
		1000mm	N/A	<b>HFUW1072PIL</b>
	Bi-Fold Wall Cabinets with Inset Handle H: 724mm One adjustable shelf Available in Contemporary and Inline ranges, (excludes Quadra, New York and Paint to Order ranges) only	500mm	<b>HFUW572IN</b>	<b>HFUW572PIN</b>
		600mm	<b>HFUW672IN</b>	<b>HFUW672PIN</b>
		800mm	<b>HFUW872IN</b>	<b>HFUW872PIN</b>
		900mm	<b>HFUW972IN</b>	<b>HFUW972PIN</b>
		1000mm	<b>HFUW1072IN</b>	<b>HFUW1072PIN</b>
	Premium Bi-Fold Wall Cabinets with LED Illuminated Base Panel and Inset Handle (Includes transformer) H: 724mm One adjustable shelf Available in Contemporary and Inline ranges, (excludes New York, Quadra and Paint to Order ranges) only	500mm	N/A	<b>HFUW572PINIL</b>
		600mm	N/A	<b>HFUW672PINIL</b>
		800mm	N/A	<b>HFUW872PINIL</b>
		900mm	N/A	<b>HFUW972PINIL</b>
		1000mm	N/A	<b>HFUW1072PINIL</b>
	Convex Curved Wall Cabinet H: 724mm Hand by hinge Two adjustable shelves See pages 08-17 for range availability Supplied Ready for Assembly 0.6mm PVC edging to front of cabinet and shelf Premium depth supplied with 50mm scribing piece	300mm	<b>WWE372CU</b>	<b>WWE372PCU</b>
	Premium Concave Curved Wall Cabinet H: 724mm Hand by hinge Two adjustable shelves See pages 08-17 for range availability Supplied Ready for Assembly Front cabinet edges are 0.8mm PVC edging	630x630mm	N/A	<b>COCWU672P</b>
	Corner Wall Cabinet H: 724mm Hand by blank, order RHB for left hand door and vice versa for LHB, right hand blank shown Two adjustable shelves	Standard: 630mm with 300 Door Premium: 630mm with 250 Door	<b>CWU672</b>	<b>CWU672P</b>
	Corner Wall Cabinet with Inset Handle H: 724mm Hand by blank, order RHB for left hand door and vice versa for LHB, right hand blank shown Two adjustable shelves Available in Contemporary and Inline ranges, (excludes Quadra, New York and Paint to Order ranges) only	Standard: 630mm with 300 Door Premium: 630mm with 250 Door	<b>CWU672IN</b>	<b>CWU672PIN</b>
	Corner Wall Cabinet with Flexible Corner Post H: 724mm Hand by blank, order RHB for left hand door and vice versa for LHB, right hand blank shown Two adjustable shelves	Standard: 630mm with 300 Door Premium: 630mm with 250 Door	<b>CWU672FP</b>	<b>CWU672PFP</b>
	Corner Wall Cabinet with Flexible Corner Post and Inset Handle H: 724mm Hand by blank, order RHB for left hand door and vice versa for LHB, right hand blank shown Two adjustable shelves Available in Contemporary and Inline ranges, (excludes Quadra, New York and Paint to Order ranges) only	Standard: 630mm with 300 Door Premium: 630mm with 250 Door	<b>CWU672INFP</b>	<b>CWU672PINFP</b>
	'L' Shape Corner Wall Cabinet H: 724mm Two adjustable shelves Supplied with 0.6mm PVC edging (Joined Frame and door in New England) LCWU772 not available in New York Matt	630x630mm	<b>LCWU672</b>	<b>LCWU672P</b>
		730x730mm	<b>LCWU772</b>	<b>LCWU772P</b>











# UNIT CONTENT

STANDARD WALL CABINETS		WIDTH	285mm STANDARD DEPTH	330mm PREMIUM DEPTH
	'L' Shape Corner Wall Cabinet with Inset Handle H: 724mm Two adjustable shelves Supplied with 0.6mm PVC edging Available in Contemporary and Inline ranges, (excludes Quadra, New York and Paint to Order ranges) only	630x630mm	<b>LCWU672IN</b>	<b>LCWU672PIN</b>
		730x730mm	<b>LCWU772IN</b>	<b>LCWU772PIN</b>
	Ranged Glazed Wall Cabinets H: 724mm Hand by hinge Two adjustable glass shelves See pages 08-17 for range availability Not available in Inline	400mm	<b>GDU472</b>	<b>GDU472P</b>
		400mm (Paint to Order cabinet)	<b>GDU472PTO</b>	<b>GDU472PPTO</b>
		500mm	<b>GDU572</b>	<b>GDU572P</b>
		500mm (Paint to Order cabinet)	<b>GDU572PTO</b>	<b>GDU572PPTO</b>
	Ranged Glazed Wall Cabinets with LED Illuminated Base Panel (Includes transformer) Hand by hinge H: 724mm Two adjustable glass shelves See pages 08-17 for range availability Not available in New England or Inline	400mm	N/A	<b>GDU472PIL</b>
		400mm (Paint to Order cabinet)	N/A	<b>GDU472PILPTO</b>
		500mm	N/A	<b>GDU572PIL</b>
		500mm (Paint to Order cabinet)	N/A	<b>GDU572PILPTO</b>
	Integrated Microwave Wall Cabinet H: 724mm Two adjustable glass shelves 296 Door 47 Fascia (scribe required) 358 Aperture Check microwave dimensions before ordering Maximum appliance dimensions 406mm high x 564mm wide Typically 17 litre microwaves suit this cabinet Supplied with Aluminium fascia cap (OHUCAP6) – supplied loose	600mm	N/A	<b>MWU672</b>
	Canopy Extractor Cabinet H: 724mm Hand by hinge Includes ducting Available with white cabinet only	600mm	<b>CANWUEX672</b>	<b>CANEXT672D</b>
	Canopy Extractor Cabinet with Inset Handle H: 724mm Hand by hinge Available in Contemporary and Inline ranges, (excludes Quadra, New York and Paint to Order ranges) only Includes ducting Available with white cabinet only	600mm	<b>CANWUEX672IN</b>	<b>CANEXT672IND</b>
	Double Canopy Extractor Cabinet H: 724mm Includes ducting Available with white cabinet only	900mm	N/A	<b>CANEXT972D</b>
	Double Canopy Extractor Cabinet with Inset Handle H: 724mm Includes ducting Available with white cabinet only	900mm	N/A	<b>CANEXT972IND</b>

# UNIT CONTENT










FEATURE STANDARD WALL CABINETS		WIDTH	285mm STANDARD DEPTH	330mm PREMIUM DEPTH
	Wall Wine Rack Cabinet H: 724mm Four wine racks, holds up to 12 bottles PTO cabinets are a flat finish, except for Premium Specification cabinets in Classic PTO ranges, which are veneered	300mm (Melamine; Ivory, Blonde Oak and White)	<b>WWR372T</b>	<b>WWR372P</b>
		300mm (Paint to Order)	<b>WWR372PTO</b>	<b>WWR372PPTO</b>
	Wall Spice/Wine Rack Cabinet H: 724mm Five wine racks, holds up to 5 bottles PTO cabinets are a flat finish, except for Premium Specification cabinets in Classic PTO ranges, which are veneered	150mm (Melamine; Ivory, Blonde Oak and White)	<b>SPWR15</b>	<b>SPWR15P</b>
		150mm (Paint to Order)	<b>SPWR15PTO</b>	<b>SPWR15PPTO</b>
	Wall Open Display Cabinet H: 724mm Order ODUFRAME separately PTO cabinets are a flat finish, except for Premium Specification cabinets in Classic PTO ranges, which are veneered	300mm (Platinum, Sage and Stone Alta PTO and New York PTO)	<b>ODU372PTO</b>	<b>ODU372PPTO</b>
		500mm (Melamine; Ivory, Blonde Oak and White)	<b>ODU572</b>	<b>ODU572P</b>
		500mm (Paint to Order)	<b>ODU572PTO</b>	<b>ODU572PPTO</b>
	Premium Wall Accent Open Display Cabinets H: 724mm Available in MFC colours Blue, Cashmere and Dark Oak	500mm	N/A	<b>ODU572PAC</b>
		600mm	N/A	<b>ODU672PAC</b>
	Wall Open Display Cabinet with Plate Rack H: 724mm Available in Classic ranges only Order ODUFRAME separately PTO cabinets are a flat finish, except for Premium Specification cabinets in Classic PTO ranges, which are veneered	500mm (Melamine; Ivory, Blonde Oak and White)	<b>ODMW8572</b>	<b>ODMW8572P</b>
		500mm (Paint to Order)	<b>ODMW8572PTO</b>	<b>ODMW8572PPTO</b>
	Wall Open Display Cabinet with Lattice Wine Rack H: 724mm Available in Classic ranges only Order ODUFRAME separately PTO cabinets are a flat finish, except for Premium Specification cabinets in Classic PTO ranges, which are veneered	500mm (Melamine; Ivory, Blonde Oak and White)	<b>ODMW9572</b>	<b>ODMW9572P</b>
		500mm (Paint to Order)	<b>ODMW9572PTO</b>	<b>ODMW9572PPTO</b>
	Wall Open Display Cabinet with Plate & Lattice Wine Rack H: 724mm Available in Classic ranges only Order ODUFRAME separately PTO cabinets are a flat finish, except for Premium Specification cabinets in Classic PTO ranges, which are veneered	500mm (Melamine; Ivory, Blonde Oak and White)	<b>ODMW10572</b>	<b>ODMW10572P</b>
		500mm (Paint to Order)	<b>ODMW10572PTO</b>	<b>ODMW1572PPTO</b>
	Premium Open Display Cabinet Frame H: 724mm	500mm (Melamine; Ivory, Blonde Oak and White)	<b>ODUFRAME</b>	
		500mm (Paint to Order)	<b>ODUFRAMEPTO</b>	

# UNIT CONTENT











TALL WALL CABINETS		WIDTH	285mm STANDARD DEPTH	330mm PREMIUM DEPTH
	Single Wall Cabinets H: 900mm Hand by hinge Two adjustable shelves (WU2590 has Joined Frame and door in New England)	255mm	<b>WU2590</b>	<b>WU2590P</b>
		300mm	<b>WU390</b>	<b>WU390P</b>
		400mm	<b>WU490</b>	<b>WU490P</b>
		450mm	<b>WU4590</b>	<b>WU4590P</b>
		500mm	<b>WU590</b>	<b>WU590P</b>
		600mm	<b>WU690</b>	<b>WU690P</b>
	Premium Single Wall Cabinets with LED Illuminated Base Panel (Includes transformer) H: 900mm Hand by hinge Two adjustable shelves Not available in New England	300mm	N/A	<b>WU390PIL</b>
		400mm	N/A	<b>WU490PIL</b>
		450mm	N/A	<b>WU4590PIL</b>
		500mm	N/A	<b>WU590PIL</b>
		600mm	N/A	<b>WU690PIL</b>
	Single Wall Cabinets with Inset Handle H: 900mm Hand by hinge Two adjustable shelves Available in Contemporary and Inline ranges, (excludes Quadra, New York and Paint to Order ranges) only	255mm	<b>WU2590IN</b>	<b>WU2590PIN</b>
		300mm	<b>WU390IN</b>	<b>WU390PIN</b>
		400mm	<b>WU490IN</b>	<b>WU490PIN</b>
		450mm	<b>WU4590IN</b>	<b>WU4590PIN</b>
		500mm	<b>WU590IN</b>	<b>WU590PIN</b>
		600mm	<b>WU690IN</b>	<b>WU690PIN</b>
	Premium Single Wall Cabinets with LED Illuminated Base Panel and Inset Handle (Includes transformer) H: 900mm Hand by hinge Two adjustable shelves Available in Contemporary and Inline ranges, (excludes New York, Quadra and Paint to Order ranges) only	300mm	N/A	<b>WU390PINIL</b>
		400mm	N/A	<b>WU490PINIL</b>
		450mm	N/A	<b>WU4590PINIL</b>
		500mm	N/A	<b>WU590PINIL</b>
		600mm	N/A	<b>WU690PINIL</b>
	Double Wall Cabinets H: 900mm Two adjustable shelves	800mm	<b>WU890</b>	<b>WU890P</b>
		900mm	<b>WU990</b>	<b>WU990P</b>
		1000mm	<b>WU1090</b>	<b>WU1090P</b>
	Double Wall Cabinets with Inset Handle H: 900mm Two adjustable shelves Available in Contemporary and Inline ranges, (excludes Quadra, New York and Paint to Order ranges) only	800mm	<b>WU890IN</b>	<b>WU890PIN</b>
		900mm	<b>WU990IN</b>	<b>WU990PIN</b>
		1000mm	<b>WU1090IN</b>	<b>WU1090PIN</b>
	Corner Wall Cabinet H: 900mm Hand by blank, order RHB for left hand door and vice versa for LHB, right hand blank shown Two adjustable shelves	Standard: 630mm with 300 Door Premium: 630mm with 250 Door	<b>CWU690</b>	<b>CWU690P</b>
	Corner Wall Cabinet with Inset Handle H: 900mm Hand by blank, order RHB for left hand door and vice versa for LHB, right hand blank shown Two adjustable shelves Available in Contemporary and Inline ranges, (excludes Quadra, New York and Paint to Order ranges) only	Standard: 630mm with 300 Door Premium: 630mm with 250 Door	<b>CWU690IN</b>	<b>CWU690PIN</b>
	'L' Shape Corner Wall Cabinet H: 900mm Two adjustable shelves Supplied with 0.6mm PVC edging (Joined Frame and door in New England)	630x630mm	<b>LCWU690</b>	<b>LCWU690P</b>
	'L' Shape Corner Wall Cabinet with Inset Handle H: 900mm Two adjustable shelves Supplied with 0.6mm PVC edging Available in Contemporary and Inline ranges, (excludes Quadra, New York and Paint to Order ranges) only	630x630mm	<b>LCWU690IN</b>	<b>LCWU690PIN</b>











# UNIT CONTENT

TALL WALL CABINETS		WIDTH	285mm STANDARD DEPTH	330mm PREMIUM DEPTH
	Ranged Glazed Wall Cabinet H: 900mm Hand by hinge Two adjustable glass shelves See pages 08-17 for range availability Not available in Inline	500mm	<b>GDU590</b>	<b>GDU590P</b>
		500mm (Paint to Order cabinet)	<b>GDU590PTO</b>	<b>GDU590PPTO</b>
	Ranged Glazed Wall Cabinet with Illuminated Base Panel (Includes transformer) H: 900mm Hand by hinge Two adjustable glass shelves See pages 08-17 for range availability Not available in New England or Inline	500mm	N/A	<b>GDU590PIL</b>
		500mm (Paint to Order cabinet)	N/A	<b>GDU590PILPTO</b>
	Integrated Microwave Wall Cabinet H: 900mm 450mm door 72mm fascia (scribe required) 358mm aperture Check microwave dimensions before ordering Maximum appliance dimensions 406mm high x 564mm wide Typically 17 litre microwaves suit the cabinet Supplied with Aluminium fascia cap (OHUCAP6) – supplied loose	600mm	N/A	<b>MWU690</b>
	Canopy Extractor Cabinet H: 900mm Includes ducting Available with white cabinet only Hand by hinge	600mm	N/A	<b>CANEXT690D</b>
	Canopy Extractor Cabinet with Inset Handle H: 900mm Includes ducting Available in Contemporary and Inline ranges, (excludes Quadra, New York and Paint to Order ranges) only Available with white cabinet only Hand by hinge	600mm	N/A	<b>CANEXT690IND</b>
FEATURE TALL WALL CABINETS		WIDTH	285mm STANDARD DEPTH	330mm PREMIUM DEPTH
	Wall Spice/Wine Rack Cabinet H: 900mm Five wine racks, holds up to 15 bottles PTO cabinets are a flat finish, except for Premium Specification cabinets in Classic PTO ranges, which are veneered	300mm (Melamine; Ivory, Blonde Oak and White)	<b>WWR390T</b>	<b>WWR390P</b>
		300mm (Paint to Order)	<b>WWR390TPTO</b>	<b>WWR390PPTO</b>
	Wall Open Display Cabinets H: 900mm Order ODUFRAME90 separately PTO cabinets are a flat finish, except for Premium Specification cabinets in Classic PTO ranges, which are veneered	500mm (Melamine; Ivory, Blonde Oak and White)	<b>ODU590</b>	<b>ODU590P</b>
		500mm (Paint to Order)	<b>ODU590PTO</b>	<b>ODU590PPTO</b>
	Wall Open Display Cabinet with Three Spice Drawers H: 900mm Available in Classic ranges only Order ODUFRAME90 separately PTO cabinets are a flat finish, except for Premium Specification cabinets in Classic PTO ranges, which are veneered	500mm (Melamine; Ivory, Blonde Oak and White)	<b>ODMW3590</b>	<b>ODMW3590P</b>
		500mm (Paint to Order)	<b>ODMU3590PTO</b>	<b>ODMW3590PPTO</b>
	Open Display Cabinet Frame H: 900mm	500mm (Melamine; Ivory, Blonde Oak and White)	<b>ODUFRAME90</b>	
		500mm (Paint to Order)	<b>ODUFRAME9PTO</b>	








# UNIT CONTENT

BRIDGING CABINETS		WIDTH	285mm STANDARD DEPTH	330mm PREMIUM DEPTH
	Bridging Cabinets H: 362mm OCH1036 available in Contemporary and Inline ranges only Lines through with bi-fold wall cabinets	500mm	OCH536	OCH536P
		600mm	OCH636	OCH636P
		800mm	OCH836	OCH836P
		900mm	OCH936	OCH936P
		1000mm	OCH1036	OCH1036P
	Bridging Cabinets with Illuminated Base Panel (Includes transformer) H: 362mm Not available in New England Top lift door cabinets line through with bi-fold units	500mm	N/A	OCH536PIL
		600mm	N/A	OCH636PIL
		800mm	N/A	OCH836PIL
		900mm	N/A	OCH936PIL
		1000mm	N/A	OCH1036PIL
	Bridging Cabinets with Inset Handle H: 362mm Available in Contemporary and Inline ranges, (excludes Quadra, New York and Paint to Order ranges) only Lines through with bi-fold wall cabinets	500mm	OCH536IN	OCH536PIN
		600mm	OCH636IN	OCH636PIN
		800mm	OCH836IN	OCH836PIN
		900mm	OCH936IN	OCH936PIN
		1000mm	OCH1036IN	OCH1036PIN
	Bridging Cabinets with Illuminated Base Panel and Inset Handle (Includes transformer) H: 362mm Available in Contemporary and Inline ranges, (excludes New York, Quadra and Paint to Order ranges) only	500mm	N/A	OCH536PINIL
		600mm	N/A	OCH636PINIL
		800mm	N/A	OCH836PINIL
		900mm	N/A	OCH936PINIL
		1000mm	N/A	OCH1036PINIL
	Over Appliance Cabinets (OCH1028 has Joined Frame and door in New England)	600mm (H: 300mm)	OCH63	OCH63P
		1000mm (H: 280mm)	OCH1028	OCH1028P
	Over Appliance Cabinets with Inset Handle Available in Contemporary and Inline ranges, (excludes Quadra, New York and Paint to Order ranges) only	600mm (H: 300mm)	OCH63IN	OCH63PIN
		1000mm (H: 280mm)	OCH1028IN	OCH1028PIN
FEATURE BRIDGING CABINETS		WIDTH	285mm STANDARD DEPTH	330mm PREMIUM DEPTH
	Bridging Open Display Cabinet H: 362mm	600mm (Paint to Order flat cabinet)	ODU636PTO	ODU636PPTO
	Bridging Accent Open Display Cabinets H: 362mm Available in MFC colours Blue, Cashmere and Dark Oak	500mm	ODU536AC	ODU536PAC
		600mm	ODU636AC	ODU636PAC
		900mm	ODU936AC	ODU936PAC
WORKTOP DRESSER CABINETS		WIDTH	285mm STANDARD DEPTH	330mm PREMIUM DEPTH
	Ranged Glazed Worktop Dresser Cabinet with Three Spice Drawers H: 1190mm Hand by hinge Two adjustable glass shelves Not available with replacement ends See pages 08-17 for range availability (excludes Alta & New York)	500mm	WDU512	WDU512P
		500mm (Paint to Order cabinet)	N/A	WDU512PAPTO
	Ranged Glazed Worktop Dresser Cabinet with Single Spice Drawer H: 1190mm Hand by hinge Two adjustable glass shelves Not available with replacement ends See pages 08-17 for range availability (excludes Alta & New York)	500mm	WDU512B	WDU512PB
		500mm (Paint to Order cabinet)	N/A	WDU512PBPTO

# UNIT CONTENT

WORKTOP DRESSER CABINETS		WIDTH	285mm STANDARD DEPTH	330mm PREMIUM DEPTH
	Ranged Glazed Dresser Cabinet without Spice Drawers H: 1190mm Hand by hinge Two adjustable glass shelves Available in New England only	500mm	<b>WDU512D</b>	<b>WDU512PD</b>
		500mm (Paint to Order cabinet)	N/A	<b>WDU512PDPTO</b>
TALL WORKTOP DRESSER CABINETS		WIDTH	285mm STANDARD DEPTH	330mm PREMIUM DEPTH
	Ranged Glazed Worktop Dresser Cabinet with Three Spice Drawers H: 1366mm Hand by hinge Two adjustable glass shelves Not available with replacement ends See pages 08-17 for range availability (excludes Alta & New York)	500mm	<b>WDU513A</b>	<b>WDU513PA</b>
		500mm (Paint to Order cabinet)	N/A	<b>WDU513PAPTO</b>
	Ranged Glazed Worktop Dresser Cabinet with Single Spice Drawer H: 1366mm Hand by hinge Two adjustable glass shelves Not available with replacement ends See pages 08-17 for range availability (excludes Alta & New York)	500mm	<b>WDU513B</b>	<b>WDU513PB</b>
		500mm (Paint to Order cabinet)	N/A	<b>WDU513PBPTO</b>
	Glazed Dresser Cabinet without Spice Drawers H: 1366mm Hand by hinge Two adjustable glass shelves Available in New England only	500mm	<b>WDU513D</b>	<b>WDU513PD</b>
		500mm (Paint to Order cabinet)	N/A	<b>WDU513PDPTO</b>
BOILER HOUSING CABINETS		WIDTH	CODE	
	Boiler Housing Wall Cabinet H: 724mm D: 400mm Hand by hinge Supplied on a 15mm Ready For Assembly cabinet with White internal only Does not have soft close hinges (Joined Frame and door in New England)	500mm	<b>BH572</b>	
		600mm	<b>BH672</b>	
	Wall Boiler Cabinet with Inset Handle H: 724mm D: 400mm Supplied on a 15mm Ready For Assembly cabinet with White internal only Hand by hinge Does not have soft close hinges Available in Selected Inline and Contemporary ranges only	500mm	<b>BH572IN</b>	
		600mm	<b>BH672IN</b>	
	Boiler Housing Wall Cabinet H: 900mm D: 400mm Hand by hinge Supplied on a 15mm Ready For Assembly cabinet with White internal only Does not have soft close hinges (Joined Frame and door in New England)	500mm	<b>BH590</b>	
		600mm	<b>BH690</b>	
	Wall Boiler Cabinet with Inset Handle H: 900mm D: 400mm Supplied on a 15mm Ready For Assembly cabinet with White internal only Hand by hinge Does not have soft close hinges Available in Selected Inline and Contemporary ranges only	500mm	<b>BH590IN</b>	
		600mm	<b>BH690IN</b>	






# UNIT CONTENT

BOILER HOUSING CABINETS		WIDTH	CODE
	Boiler Housing Dresser Cabinet H: 1190mm D: 400mm 900 door 276 dummy drawer Does not have soft close hinges Not available with replacement ends Hand by hinge Not available in New England	600mm	<b>BH612</b>
	Dresser Boiler Cabinet H: 1366mm D: 400mm 1228 door 120 fascia Does not have soft close hinges Not available with replacement ends Hand by hinge Supplied Ready For Assembly	600mm	<b>BH613</b>
	Dresser Boiler Cabinet H: 1560mm D: 400mm 1228 door 47 fascia 276 dummy drawer Does not have soft close hinges Not available with replacement ends Hand by hinge Supplied Ready For Assembly	600mm	<b>BH615</b>
2100MM HIGH UNITS – 50/50 SPECIFICATION (ALIGNS 930MM HIGH BASE DOORS)			
LARDER CABINETS		WIDTH	CODE
	50/50 Larder Cabinet H: 2100mm D: 570mm 1018 door 930 door Hand by hinge Five adjustable shelves (Joined Frame and door in New England)	600mm	<b>LU66A</b>
	50/50 Larder Cabinet with Internal Drawers H: 2100mm D: 570mm 1018 door 930 door Hand by hinge Five internal deep drawers Drawers supplied separately (Joined Frame and door in New England)	600mm	<b>LU66AID</b>
	50/50 Corner Larder Cabinet H: 2100mm D: 570mm 1018 door 930 door Hand by blank Two doors, five additional shelves Supplied with frontal matched blanking panel (750x2400mm) for the blanking panel and corner post to be created on site Supplied RFA (Joined Frame and door in New England)	1000mm with 600mm doors	<b>CNLU106A</b>
	50/50 Corner Larder Cabinet with Kesseböhmer Storage (Wirework not fitted) H: 2100mm D: 600mm 1018mm door 930mm door Includes blanking panel (750x2400mm), x2 Le Mans pull-out units (4 trays) and a 1265mm centre pole Hand by blank, order RHB for left hand door and vice versa for LHB, right hand blank shown Supplied Ready for Assembly only (Joined Frame and door in New England)	1000mm with 600 Door/Le Mans	<b>CNLLM106A</b>

**Important:** Please check the appliance manufacturer's instructions as to the venting requirements for any particular appliance. All appliances must be fitted strictly in accordance with the manufacturer's instructions. Check appliance dimensions fit the appliance housing before ordering. Fascia panels can be cut to suit. Edging tape or the OHUCAP6 are available for re-edging the fascia after cutting.

**UPGRADE:** EKO timber drawer boxes are available as an optional upgrade with all Classic ranges.

# UNIT CONTENT


FRIDGE/FREEZER HOUSINGS		WIDTH	CODE
	50/50 Integrated Housing	600mm (slider fixing appliances)	<b>IF66A</b>
	H: 2100mm D: 570mm	600mm (door-on-door appliances)	
	1018 door	Cabinet without appliance doors	<b>IF66AND</b>
	930 door	1018 appliance door	<b>DRIFTOP1UD</b>
	Hand by hinge	930 appliance door	<b>DRIFBOT1UD</b>
One appliance behind top and bottom door			
Check fridge freezer specification			
Frontals are hinged to cabinets designed for slider fixing appliances			
Appliance frontals are supplied separately to the cabinet for door-on-door appliances			
OVEN HOUSINGS		WIDTH	CODE
	Single Oven Housing – Door	600mm	<b>OH6616A</b>
	H: 2100mm D: 570mm		
	358 flap		
	120 fascia (scribe required)		
	595 aperture		
	930 door		
	Hand by hinge		
	Single adjustable shelf		
	Supplied with Aluminium fascia cap (OHUCAP6) – supplied loose		
	Single Oven and Integrated Fridge Housing – Door	600mm (slider fixing appliances)	<b>OFH66A</b>
	H: 2100mm D: 570mm	600mm (door-on-door appliances)	
	358 flap	Cabinet without appliance doors	<b>OFH66AND</b>
	72 fascia	930 appliance door	<b>DRIFBOT1UD</b>
	595 aperture		
	930 door		
	Hand by hinge		
	Suitable for 880mm high integrated fridge/freezers only		
	Check fridge freezer specification		
	Frontals are hinged to cabinets designed for slider fixing appliances		
	Appliance frontals are supplied separately to the cabinet for door-on-door appliances		
	Microwave/Compact Oven Housing – Door	600mm	<b>OH6616B</b>
	H: 2100mm D: 570mm		
	557 door		
	455 aperture		
	930 door		
	Hand by hinge		
	Single adjustable shelf		
	Microwave/Compact Oven and Integrated Fridge Housing – Door	600mm (slider fixing appliances)	<b>OFH66B</b>
	H: 2100mm D: 570mm	600mm (door-on-door appliances)	
	557 door	Cabinet without appliance doors	<b>OFH66BND</b>
	455 aperture	930 appliance door	<b>DRIFBOT1UD</b>
	930 door		
	Hand by hinge		
	Suitable for 880mm high integrated fridge/freezers only		
	Check fridge freezer specification		
	Frontals are hinged to cabinets designed for slider fixing appliances		
	Appliance frontals are supplied separately to the cabinet for door-on-door appliances		






**Important:** Please check the appliance manufacturer's instructions as to the venting requirements for any particular appliance. All appliances must be fitted strictly in accordance with the manufacturer's instructions. Check appliance dimensions fit the appliance housing before ordering. Fascia panels can be cut to suit. Edging tape or the OHUCAP6 are available for re-edging the fascia after cutting.

**UPGRADE:** EKO timber drawer boxes are available as an optional upgrade with all Classic ranges.

# UNIT CONTENT

## 2100MM HIGH UNITS – 70/30 SPECIFICATION (ALIGNS 720MM HIGH BASE DOORS)






REDUCED DEPTH LARDER CABINETS		285mm STANDARD DEPTH	330mm PREMIUM DEPTH
	WIDTH		
	70/30 Reduced Depth Larder Cabinet	<b>LU33</b>	<b>LU33P</b>
	H: 2100mm		
	1228 door	<b>LU53</b>	<b>LU53P</b>
	720 door	<b>LU63</b>	<b>LU63P</b>
Hand by hinge			
One fixed shelf and four additional shelves			
(Joined Frame and door in New England)			

LARDER CABINETS		WIDTH	CODE
	70/30 Larder Cabinet	300mm	<b>LU36</b>
	H: 2100mm D: 570mm	500mm	<b>LU56</b>
	1228 door	600mm	<b>LU66</b>
	720 door		
Hand by hinge			
Five adjustable shelves			
(Joined Frame and door in New England)			
	70/30 Larder Cabinet with Internal Drawers	300mm	<b>LU36ID</b>
	H: 2100mm D: 570mm	500mm	<b>LU56ID</b>
	1228 door	600mm	<b>LU66ID</b>
	720 door		
Hand by hinge			
Five Atira internal deep drawers			
Drawers supplied separately			
(Joined Frame and door in New England)			
	Larder Cabinet - 70/30 with Kesseböhmer Storage	300mm	<b>PL36SO</b>
	(Wirework not fitted)	500mm	<b>PL56SO</b>
	H: 2100mm D: 600mm	500mm (Cranked)	<b>CPL56AR</b>
	1228mm door	600mm (Cranked)	<b>CPL66AR</b>
720mm door			
(Joined Frame and door in New England)			
	70/30 Corner Larder Cabinet	1000mm with 500mm doors	<b>CNLU106</b>
	H: 2100mm D: 570mm	1000mm with 600mm doors	<b>CNLU106C</b>
	1228 door		
	720 door		
Hand by blank			
Two doors, five additional shelves			
Supplied with frontal matched blanking panel (750x2400mm)			
for the blanking panel and corner post to be created on site			
Supplied RFA			
(Joined Frame and door in New England)			
	70/30 Corner Larder Cabinet with Kesseböhmer Storage	1000mm with 500 Door/Le Mans	<b>CNLLM106</b>
	(Wirework not fitted)	1000mm with 600 Door/Le Mans	<b>CNLLM106C</b>
	H: 2100mm D: 600mm		
	1228mm door		
720mm door			
Includes blanking panel (750x2400mm),			
x2 Le Mans pull-out units			
(4 trays) and a 1265mm centre pole			
Hand by blank, order RHB for left hand door and			
vice versa for LHB, right hand blank shown			
Supplied Ready for Assembly only			
(Joined Frame and door in New England)			

**Important:** Please check the appliance manufacturer's instructions as to the venting requirements for any particular appliance. All appliances must be fitted strictly in accordance with the manufacturer's instructions. Check appliance dimensions fit the appliance housing before ordering. Fascia panels can be cut to suit. Edging tape or the OHUCAP6 are available for re-edging the fascia after cutting.

**UPGRADE:** EKO timber drawer boxes are available as an optional upgrade with all Classic ranges.








# UNIT CONTENT

FRIDGE/FREEZER HOUSINGS		WIDTH	CODE
	70/30 Integrated Housing H: 2100mm D: 570mm 1228 door 720 door Hand by hinge One appliance behind top and bottom door Check fridge freezer specification Frontals are hinged to cabinets designed for slider fixing appliances Appliance frontals are supplied separately to the cabinet for door-on-door appliances (Joined Frame and door in New England)	600mm (slider fixing appliances)	<b>IF66D</b>
		600mm (door-on-door appliances) Cabinet without appliance doors 1228 appliance door 720 appliance door	<b>IF66DND DRIFTOP2UD DRIFBOT3UD</b>
	70/30 Integrated Housing H: 2100mm D: 570mm 1228 door 720 door Hand by hinge For use with most NEFF, Bosch and Siemens appliances only (appliance sits higher to allow it to align with doors) One appliance behind top and bottom door Check fridge freezer specification Frontals are hinged to cabinets designed for slider fixing appliances Appliance frontals are supplied separately to the cabinet for door-on-door appliances (Joined Frame and door in New England)	600mm (slider fixing appliances)	<b>IF66G</b>
		600mm (door-on-door appliances) Cabinet without appliance doors 1228 appliance door 720 appliance door	<b>IF66GND DRIFTOP2GUD DRFH6GUD</b>
OVEN HOUSINGS		WIDTH	CODE
	Single Oven Housing – Door H: 2100mm D: 570mm 557 door 72 fascia 595 aperture 720 door Hand by hinge	600mm	<b>OH666A</b>
	Single Oven Housing – Top Drawer H: 2100mm D: 570mm 557 door 72 fascia 595 aperture 159 drawer 557 door Hand by hinge Not available in Inline	600mm	<b>OH664A</b>
	Single Oven Housing – 2 Pan H: 2100mm D: 570mm 557 door 72 fascia 595 aperture 358 drawer 358 drawer Hand by hinge	600mm	<b>OH6610E</b>

**Important:** Please check the appliance manufacturer's instructions as to the venting requirements for any particular appliance. All appliances must be fitted strictly in accordance with the manufacturer's instructions. Check appliance dimensions fit the appliance housing before ordering. Fascia panels can be cut to suit. Edging tape or the OHUCAP6 are available for re-edging the fascia after cutting.

**UPGRADE:** EKO timber drawer boxes are available as an optional upgrade with all Classic ranges.

# UNIT CONTENT








OVEN HOUSINGS		WIDTH	CODE
	Single Oven Housing – 3 Pan H: 2100mm D: 570mm 557 door 72 fascia 595 aperture 159 drawer 276 drawer 276 drawer Hand by hinge	600mm	<b>OH6610A</b>
	Microwave/Compact Appliance Housing – Door H: 2100mm D: 570mm 720 door 47 fascia 455 aperture 720 door Hand by hinge	600mm	<b>OH667A</b>
	Microwave/Compact Appliance Housing – Top Drawer H: 2100mm D: 570mm 720 door 47 fascia 455 aperture 159 drawer 557 door Hand by hinge Not available in Inline	600mm	<b>OH6610I</b>
	Microwave/Compact Appliance Housing – 2 Pan H: 2100mm D: 570mm 720 door 47 fascia 455 aperture 358 drawer 358 drawer Hand by hinge	600mm	<b>OH6610G</b>
	Microwave/Compact Appliance Housing – 3 Pan H: 2100mm D: 570mm 720 door 47 fascia 455 aperture 159 drawer 276 drawer 276 drawer Hand by hinge	600mm	<b>OH6610D</b>
	Twin Compact Appliance Housing – Door H: 2100mm D: 570mm 296 flap 455 aperture 18 shelf (supplied loose) 455 aperture 720 door Hand by hinge	600mm	<b>OH6612A</b>
	Twin Compact Appliance Housing – Top Drawer H: 2100mm D: 570mm 296 flap 455 aperture 18 shelf (supplied loose) 455 aperture 159 drawer 557 door Hand by hinge Not available in Inline	600mm	<b>OH6612B</b>

**Important:** Please check the appliance manufacturer's instructions as to the venting requirements for any particular appliance. All appliances must be fitted strictly in accordance with the manufacturer's instructions. Check appliance dimensions fit the appliance housing before ordering. Fascia panels can be cut to suit. Edging tape or the OHUCAP6 are available for re-edging the fascia after cutting.

**UPGRADE:** EKO timber drawer boxes are available as an optional upgrade with all Classic ranges.








# UNIT CONTENT

OVEN HOUSINGS		WIDTH	CODE
	Twin Compact Appliance Housing – 2 Pan H: 2100mm D: 570mm 296 flap 455 aperture 18 shelf (supplied loose) 455 aperture 358 drawer 358 drawer	600mm	OH6612D
	Twin Compact Appliance Housing – 3 Pan H: 2100mm D: 570mm 296 flap 455 aperture 18 shelf (supplied loose) 455 aperture 159 drawer 276 drawer 276 drawer	600mm	OH6612C
PANTRY UNITS		WIDTH	CODE
	Two Drawer Pantry Cabinet H: 2100mm D: 570mm 1228 door (x1) 358 drawers (x2) Hand by hinge One top door and two deep pan drawers Three adjustable shelves (Joined Frame and door in New England)	600mm	PU6621D2A
	Two Drawer Pantry Cabinet H: 2100mm D: 570mm 1228 doors (x2) 358 drawers (x2) Hand by hinge Two top doors and two deep pan drawers Three adjustable shelves (Joined Frame and door in New England)	600mm	PU6621D2
	Three Drawer Pantry Cabinet H: 2100mm D: 570mm 1228 doors (x1) 159 drawer 276 drawers (x2) Hand by hinge One top door, one shallow drawer and two pan drawers Three adjustable shelves (Joined Frame and door in New England)	600mm	PU6621D3A
	Three Drawer Pantry Cabinet H: 2100mm D: 570mm 1228 doors (x2) 159 drawer 276 drawers (x2) Two top doors, one shallow drawer and two pan drawers Three adjustable shelves (Joined Frame and door in New England)	600mm	PU6621D3
	Four Drawer Pantry Cabinet H: 2100mm D: 570mm 1228 doors (x1) 159 drawer 183 drawers (x3) Hand by hinge One top door and four drawers Three adjustable shelves Not available in Inline (Joined Frame and door in New England)	600mm	PU6621D4A

**Important:** Please check the appliance manufacturer's instructions as to the venting requirements for any particular appliance. All appliances must be fitted strictly in accordance with the manufacturer's instructions. Check appliance dimensions fit the appliance housing before ordering. Fascia panels can be cut to suit. Edging tape or the OHUCAP6 are available for re-edging the fascia after cutting.

**UPGRADE:** EKO timber drawer boxes are available as an optional upgrade with all Classic ranges.

# UNIT CONTENT


PANTRY UNITS		WIDTH	CODE
	Four Drawer Pantry Cabinet H: 2100mm D: 570mm 1228 doors (x2) 159 drawer 183 drawers (x3) Two top doors and four drawers Three adjustable shelves Not available in Inline (Joined Frame and door in New England)	600mm	<b>PU6621D4</b>
	Pantry Cabinet H: 2100mm D: 570mm 1228 doors (x2) 720 doors (x2) Five adjustable shelves Supplied RFA (Joined Frame and door in New England)	1000mm	<b>PU106</b>
	Pantry Cabinet with Internals H: 2100mm D: 600mm x2 1228mm doors x2 720mm doors x3 shelves x1 internal timber cutlery drawer x1 chrome wine rack x1 chrome wine glass insert x2 wicker baskets x6 chrome door storage baskets Supplied on a Ready For Assembly Blonde Oak cabinet only Available in Classic ranges only	1000mm	<b>PU106R1</b>
	Pantry Cabinet with Internals H: 2100mm D: 600mm x2 1228mm doors x2 720mm doors x3 shelves x1 internal timber cutlery drawer x1 chrome wine rack x1 chrome wine glass insert x2 wicker baskets x2 plate racks x6 chrome door storage baskets Supplied on a Ready For Assembly Blonde Oak cabinet only Available in Classic ranges only	1000mm	<b>PU106R2</b>
	Pantry Cabinet with Internals H: 2100mm D: 600mm x2 1228mm doors x2 720mm doors x3 shelves x1 internal timber cutlery drawer x1 chrome wine rack x1 chrome wine glass insert x2 wicker baskets x1 plate rack x6 timber spice boxes x6 chrome door storage baskets Supplied on a Ready For Assembly Blonde Oak cabinet only Available in Classic ranges only	1000mm	<b>PU106R3</b>


**Important:** Please check the appliance manufacturer's instructions as to the venting requirements for any particular appliance. All appliances must be fitted strictly in accordance with the manufacturer's instructions. Check appliance dimensions fit the appliance housing before ordering. Fascia panels can be cut to suit. Edging tape or the OHUCAP6 are available for re-edging the fascia after cutting.


**UPGRADE:** EKO timber drawer boxes are available as an optional upgrade with all Classic ranges.



# UNIT CONTENT

## 2100MM HIGH UNITS – 30/70 SPECIFICATION (ALIGNS 720MM HIGH TOP DOORS)

REDUCED DEPTH LARDER CABINETS		285mm STANDARD DEPTH	330mm PREMIUM DEPTH
	WIDTH		
 <p>30/70 Reduced Depth Larder Cabinet H: 2100mm 720 door 1228 door Hand by hinge One fixed shelf and four additional shelves (Joined Frame and door in New England)</p>	300mm	<b>LU33B</b>	<b>LU33PB</b>
	500mm	<b>LU53B</b>	<b>LU53PB</b>
	600mm	<b>LU63B</b>	<b>LU63PB</b>

LARDER CABINETS		WIDTH	CODE
 <p>30/70 Larder Cabinet H: 2100mm D: 570mm 720 door 1228 door Hand by hinge Five adjustable shelves (Joined Frame and door in New England)</p>	300mm		<b>LU36B</b>
	500mm		<b>LU56B</b>
	600mm		<b>LU66B</b>




FRIDGE/FREEZER HOUSINGS		WIDTH	CODE
 <p>In-Column Integrated Housing H: 2100mm D: 570mm 720 door 1228 door Hand by hinge One appliance behind bottom door Suitable for 1225mm high integrated fridge/freezers only Check fridge freezer specification Frontals are hinged to cabinets designed for slider fixing appliances Appliance frontals are supplied separately to the cabinet for door-on-door appliances (Joined Frame and door in New England)</p>	600mm (slider fixing appliances)		<b>IF66B</b>
	600mm (door-on-door appliances)		
	Cabinet without appliance doors		<b>IF66BND</b>
	1228 appliance door		<b>DRIFBOT2UD</b>

OVEN HOUSINGS		WIDTH	CODE
 <p>Single Oven Housing – Door H: 2100mm D: 570mm 720 door 72 fascia 595 aperture 557 door Hand by hinge</p>	600mm		<b>OH665A</b>
 <p>Microwave/Compact Appliance Housing – Door H: 2100mm D: 570mm 720 door 120 fascia 384 aperture 720 door Hand by hinge</p>	600mm		<b>OH667B</b>

**Important:** Please check the appliance manufacturer's instructions as to the venting requirements for any particular appliance. All appliances must be fitted strictly in accordance with the manufacturer's instructions. Check appliance dimensions fit the appliance housing before ordering. Fascia panels can be cut to suit. Edging tape or the OHUCAP6 are available for re-edging the fascia after cutting.



**UPGRADE:** EKO timber drawer boxes are available as an optional upgrade with all Classic ranges.

# UNIT CONTENT

OVEN HOUSINGS		WIDTH	CODE
	Microwave/Compact Appliance Housing – Top Drawer H: 2100mm D: 570mm 720 door 47 fascia 455 aperture 159 drawer 557 door Hand by hinge Not available in Inline	600mm	<b>OH6610I</b>
	Microwave/Compact Appliance Housing – 2 Pan H: 2100mm D: 570mm 720 door 47 fascia 455 aperture 358 drawer 358 drawer Hand by hinge	600mm	<b>OH6610G</b>
	Microwave/Compact Appliance Housing – 3 Pan H: 2100mm D: 570mm 720 door 47 fascia 455 aperture 159 drawer 276 drawer 276 drawer Hand by hinge	600mm	<b>OH6610D</b>

## 2100MM HIGH UNITS – IN-COLUMN SPECIFICATION (ALIGNS 296MM HIGH TOP FLAPS)






FRIDGE/FREEZER HOUSINGS		WIDTH	CODE
	In-Column Integrated Housing H: 2100mm D: 570mm 296 flap 930 door 720 door Hand by hinge One appliance behind middle door Suitable for 880mm high integrated fridge/freezers only Check fridge freezer specification Frontals are hinged to cabinets designed for slider fixing appliances Appliance frontals are supplied separately to the cabinet for door-on-door appliances (Joined Frame and door in New England)	600mm (slider fixing appliances) 600mm (door-on-door appliances) Cabinet without appliance doors 930 appliance door	<b>IF66C</b>  <b>IF66CND</b> <b>DRIFMIDUD</b>


OVEN HOUSINGS		WIDTH	CODE
	Single Oven and Microwave/Compact Appliance Housing – Door H: 2100mm D: 570mm 296 flap 47 fascia (scribe required) 437 aperture 18 shelf (supplied loose) 590 aperture 557 door Hand by hinge	600mm	<b>OH6614A</b>
	Twin Single Oven Housing – 1 Pan H: 2100mm D: 570mm 296 flap 595 aperture 18 shelf (supplied loose) 595 aperture 450 drawer Internal top drawer	600mm	<b>OH6613A</b>

**Important:** Please check the appliance manufacturer's instructions as to the venting requirements for any particular appliance. All appliances must be fitted strictly in accordance with the manufacturer's instructions. Check appliance dimensions fit the appliance housing before ordering. Fascia panels can be cut to suit. Edging tape or the OHUCAP6 are available for re-edging the fascia after cutting.

**UPGRADE:** EKO timber drawer boxes are available as an optional upgrade with all Classic ranges.

# UNIT CONTENT








OVEN HOUSINGS		WIDTH	CODE
	Double Oven and Microwave/Compact Appliance Housing – 1 Pan H: 2100mm D: 570mm 296 flap 457 aperture 18 shelf (supplied loose) 875 aperture 296 drawer	600mm	<b>OH668C</b>
	Twin Compact Appliance Housing – Door H: 2100mm D: 570mm 296 flap 455 aperture 18 shelf (supplied loose) 455 aperture 720 door Hand by hinge	600mm	<b>OH6612A</b>
	Twin Compact Appliance Housing – Top Drawer H: 2100mm D: 570mm 296 flap 455 aperture 18 shelf (supplied loose) 455 aperture 159 drawer 557 door Hand by hinge Not available in Inline	600mm	<b>OH6612B</b>
	Twin Compact Appliance Housing – 2 Pan H: 2100mm D: 570mm 296 flap 455 aperture 18 shelf (supplied loose) 455 aperture 358 drawer 358 drawer	600mm	<b>OH6612D</b>
	Twin Compact Appliance Housing – 3 Pan H: 2100mm D: 570mm 296 flap 455 aperture 18 shelf (supplied loose) 455 aperture 159 drawer 276 drawer 276 drawer Not available in Inline	600mm	<b>OH6612C</b>

2100MM HIGH UNITS – MISCELLANEOUS			
LARDER CABINETS		WIDTH	CODE
	Diagonal Larder Cabinet H: 2100mm 1228mm door 720mm door Supplied on a Ready For Assembly Blonde Oak cabinet only Not available with replacement ends Not available in Inline	1015x1015mm	<b>DLU1021</b>

**Important:** Please check the appliance manufacturer's instructions as to the venting requirements for any particular appliance. All appliances must be fitted strictly in accordance with the manufacturer's instructions. Check appliance dimensions fit the appliance housing before ordering. Fascia panels can be cut to suit. Edging tape or the OHUCAP6 are available for re-edging the fascia after cutting.

**UPGRADE:** EKO timber drawer boxes are available as an optional upgrade with all Classic ranges.







# UNIT CONTENT

OVEN HOUSINGS		WIDTH	CODE
	Single Oven Housing H: 2100mm D: 570mm 896 door 590 aperture 450 drawer Hand by hinge Drawer contains one wirework basket and one metal sided basket	600mm	OH6613A
	Double Oven Housing H: 2100mm D: 570mm 450 door 47 fascia 890 aperture 557 door Hand by hinge	600mm	OH663A
	Double Oven Housing H: 2100mm D: 570mm 450 door 47 fascia 890 aperture 276 drawer 276 drawer Hand by hinge	600mm	OH6610B
	Single Oven and Microwave/Compact Appliance Housing H: 2100mm D: 570mm 450 door 72 fascia 459 aperture 18 shelf 595 aperture 358 drawer Hand by hinge	600mm	OH661F
	Single Oven and Microwave/Compact Appliance Housing H: 2100mm D: 570mm 450 door 120 fascia (scribe required) 455 aperture 18 shelf (supplied loose) 595 aperture 358 drawer Hand by hinge For use with NEFF seamless appliance arrangements Supplied with Aluminium fascia cap (OHUCAP6) – supplied loose	600mm	OH661H
	Single Oven and Microwave/Compact Appliance Housing H: 2100mm D: 570mm 358 flap 72 fascia 459 aperture 18 shelf (supplied loose) 590 aperture 450 drawer	600mm	OH662N
	Single Oven and Microwave/Compact Appliance Housing H: 2100mm D: 570mm 358 flap 120 fascia (scribe required) 455 aperture 18 shelf (supplied loose) 595 aperture 450 drawer For use with NEFF seamless appliance arrangements Supplied with Aluminium fascia cap (OHUCAP6) – supplied loose Internal top drawer	600mm	OH662R

**Important:** Please check the appliance manufacturer's instructions as to the venting requirements for any particular appliance. All appliances must be fitted strictly in accordance with the manufacturer's instructions. Check appliance dimensions fit the appliance housing before ordering. Fascia panels can be cut to suit. Edging tape or the OHUCAP6 are available for re-edging the fascia after cutting.

**UPGRADE:** EKO timber drawer boxes are available as an optional upgrade with all Classic ranges.





# UNIT CONTENT

OVEN HOUSINGS		WIDTH	CODE
	Single Oven and Microwave/Compact Appliance Housing H: 2100mm D: 570mm 450 door 47 fascia 388 aperture 18 shelf (supplied loose) 595 aperture 450 drawer Hand by hinge	600mm	<b>OH662A</b>
	Double Oven and Microwave/Compact Appliance Housing – 1 Pan H: 2100mm D: 570mm 296 flap 457 aperture 18 shelf (supplied loose) 875 aperture 296 drawer	600mm	<b>OH668C</b>
	Double Oven and Microwave/Compact Appliance Housing H: 2100mm D: 570mm 450 door 72 fascia 455 aperture 18 shelf (supplied loose) 890 aperture 72 fascia Hand by hinge	600mm	<b>OH668D</b>
ACCENT OPEN DISPLAY		WIDTH	CODE
	Accent Open Display End Cabinet H: 2100mm D: 285mm Includes two 724 high and one 561 high accent open wall units Available in 18mm MFC matt colours: Blue, Cashmere and Dark Oak Order framing to suit (includes shelving panels, plinths, legs and fixings)	600mm Cabinet	<b>LUODU21</b>
		Frontal matched framing	<b>LUODUFRMF</b>
		Replacement end matched framing	<b>LUODUFRMR</b>
<b>2276MM HIGH UNITS – 50/50 SPECIFICATION (ALIGNS 1018MM HIGH BASE DOORS)</b>			
LARDER CABINETS		WIDTH	CODE
	50/50 Larder Cabinet H: 2276mm D: 570mm 1106 door 1018 door Hand by hinge Five adjustable shelves (Joined Frame and door in New England)	600mm	<b>LU6623A</b>
	50/50 Larder Cabinet with Internal Drawers H: 2276mm D: 570mm 1106 door 1018 door Hand by hinge Five internal deep drawers Drawers supplied separately (Joined Frame and door in New England)	600mm	<b>LU6623AID</b>

**Important:** Please check the appliance manufacturer's instructions as to the venting requirements for any particular appliance. All appliances must be fitted strictly in accordance with the manufacturer's instructions. Check appliance dimensions fit the appliance housing before ordering. Fascia panels can be cut to suit. Edging tape or the OHUCAP6 are available for re-edging the fascia after cutting.

**UPGRADE:** EKO timber drawer boxes are available as an optional upgrade with all Classic ranges.

# UNIT CONTENT


LARDER CABINETS		WIDTH	CODE
	50/50 Corner Larder Cabinet H: 2276mm D: 570mm 1106x600 door 1018x600 door Hand by blank Two doors, five additional shelves Supplied with frontal matched blanking panel (750x2400mm) Supplied RFA (Joined Frame and door in New England)	1000mm with 600mm doors	<b>CNLU10623A</b>
	Corner Larder Cabinet - 50/50 with Kesseböhmer Storage (Wirework not fitted) H: 2276mm D: 600mm 1106mm door 1018mm door Includes blanking panel (750x2400mm), x2 Le Mans pull-out units (4 trays) and a 1265mm centre pole Hand by blank, order RHB for left hand door and vice versa for LHB, right hand blank shown Supplied Ready for Assembly only (Joined Frame and door in New England)	1000mm with 600 Door/Le Mans	<b>CNLLM10623A</b>
FRIDGE/FREEZER HOUSINGS		WIDTH	CODE
	50/50 Integrated Housing H: 2276mm D: 570mm 1106 door 1018 door Hand by hinge One appliance behind top and bottom door Check fridge freezer specification Frontals are hinged to cabinets designed for slider fixing appliances Appliance frontals are supplied separately to the cabinet for door-on-door appliances (Joined Frame and door in New England)	600mm (slider fixing appliances)	<b>IF6623J</b>
		600mm (door-on-door appliances) Cabinet without appliance doors 1106 appliance door 1018 appliance door	<b>IF6623JND</b> <b>DRIFTOP6UD</b> <b>DRIFBOT4UD</b>
OVEN HOUSINGS		WIDTH	CODE
	Single Oven and Fridge or Freezer Housing – Door H: 2276mm D: 570mm 450 flap 72 fascia (scribe required) 595 aperture 1018 door Hand by hinge Supplied with Aluminium fascia cap (OHUCAP6) – supplied loose Suitable for use with 880mm high integrated fridge/freezers only	600mm	<b>OFH6623A</b>
	Single Oven Housing – Door H: 2276mm D: 570mm 450 door 72 fascia (scribe required) 595 aperture 1018 door Hand by hinge Supplied with Aluminium fascia cap (OHUCAP6) – supplied loose	600mm	<b>OH662316A</b>
	Microwave/Compact Appliance Housing – Door H: 2276mm D: 570mm 557 door 120 fascia (scribe required) 455 aperture 1018 door Hand by hinge Supplied with Aluminium fascia cap (OHUCAP6) – supplied loose	600mm	<b>OH662316B</b>

**Important:** Please check the appliance manufacturer's instructions as to the venting requirements for any particular appliance. All appliances must be fitted strictly in accordance with the manufacturer's instructions. Check appliance dimensions fit the appliance housing before ordering. Fascia panels can be cut to suit. Edging tape or the OHUCAP6 are available for re-edging the fascia after cutting.





**UPGRADE:** EKO timber drawer boxes are available as an optional upgrade with all Classic ranges.



# UNIT CONTENT

OVEN HOUSINGS		WIDTH	CODE
	Microwave/Compact Appliance and Fridge or Freezer Housing – Door	600mm	<b>OFH6623B</b>
	H: 2276mm D: 570mm 557 door 120 fascia (scribe required) 455 aperture 1018 door Hand by hinge Supplied with Aluminium fascia cap (OHUCAP6) – supplied loose Suitable for use with 880mm high integrated fridge/freezers only		






2276MM HIGH UNITS – 70/30 SPECIFICATION (ALIGNS 896MM HIGH BASE DOORS)			
REDUCED DEPTH LARDER CABINETS	WIDTH	285mm STANDARD DEPTH	330mm PREMIUM DEPTH
	70/30 Reduced Depth Larder Cabinet	300mm	<b>LU3323</b>
	H: 2276mm	500mm	<b>LU5323</b>
	1228 door	600mm	<b>LU6323</b>
	896 door		<b>LU6323P</b>
	Hand by hinge One fixed shelf and five additional shelves (Joined Frame and door in New England)		

LARDER CABINETS	WIDTH	CODE
	70/30 Larder Cabinet	<b>LU3623</b>
	H: 2276mm D: 570mm	<b>LU5623</b>
	1228 door	<b>LU6623</b>
	896 door	
	Hand by hinge Five adjustable shelves (Joined Frame and door in New England)	
	70/30 Larder Cabinet with Internal Deep Drawers	<b>LU3623ID</b>
	H: 2276mm D: 570mm	<b>LU5623ID</b>
	1228 door	<b>LU6623ID</b>
	896 door	
	Hand by hinge Five Atira internal deep drawers Drawers supplied separately (Joined Frame and door in New England)	
	Larder Cabinet - 70/30 with Kesseböhmer Storage (Wirework not fitted)	<b>PL3623SO</b>
	H: 2276mm D: 600mm	<b>PL5623SO</b>
	1228mm door	<b>CPL5623AR</b>
	896mm door	<b>CPL6623AR</b>
	(Joined Frame and door in New England)	
	70/30 Corner Larder Cabinet	<b>CNLU10623</b>
	H: 2276mm D: 570mm	<b>CNLU10623C</b>
	1228 door	
	896 door	
	Hand by blank Two doors, five additional shelves Supplied with frontal matched blanking panel (750x2400mm) for the blanking panel and corner post to be created on site Supplied RFA (Joined Frame and door in New England)	

**Important:** Please check the appliance manufacturer's instructions as to the venting requirements for any particular appliance. All appliances must be fitted strictly in accordance with the manufacturer's instructions. Check appliance dimensions fit the appliance housing before ordering. Fascia panels can be cut to suit. Edging tape or the OHUCAP6 are available for re-edging the fascia after cutting.





**UPGRADE:** EKO timber drawer boxes are available as an optional upgrade with all Classic ranges.

# UNIT CONTENT

LARDER CABINETS		WIDTH	CODE
	Corner Larder Cabinet - 70/30 with Kesseböhmer Storage (Wirework not fitted) H: 2276mm D: 600mm 1228mm door 896mm door Includes blanking panel (750x2400mm), x2 Le Mans pull-out units (4 trays) and a 1265mm centre pole Hand by blank, order RHB for left hand door and vice versa for LHB, right hand blank shown Supplied Ready for Assembly only (Joined Frame and door in New England)	1000mm with 500 Door/Le Mans	CNLLM10623
		1000mm with 600 Door/Le Mans	CNLLM10623C
FRIDGE/FREEZER HOUSINGS		WIDTH	CODE
	70/30 Integrated Housing H: 2276mm D: 570mm 1228 door 896 door Hand by hinge One appliance behind top and bottom door Check fridge freezer specification Frontals are hinged to cabinets designed for slider fixing appliances Appliance frontals are supplied separately to the cabinet for door-on-door appliances (Joined Frame and door in New England)	600mm (slider fixing appliances)	IF6623D
		600mm (door-on-door appliances) Cabinet without appliance doors 1228 appliance door 896 appliance door	IF6623DND DRIFTOP2UD DRAHBOT1UD
	70/30 Integrated Housing H: 2276mm D: 570mm 1228 door 896 door Hand by hinge For use with NEFF, Bosch and Siemens appliances only (appliance sits higher to allow it to align with doors) One appliance behind top and bottom door Check fridge freezer specification Frontals are hinged to cabinets designed for slider fixing appliances Appliance frontals are supplied separately to the cabinet for door-on-door appliances (Joined Frame and door in New England)	600mm (slider fixing appliances)	IF6623G
		600mm (door-on-door appliances) Cabinet without appliance doors 1228 appliance door 896 appliance door	IF6623GND DRIFTOP2UD DRAHBOT1UD
OVEN HOUSINGS		WIDTH	CODE
	Single Oven Housing – Door H: 2276mm D: 570mm 557 door 72 fascia 595 aperture 896 door Hand by hinge	600mm	OH66236A
	Microwave/Compact Appliance Housing – Door H: 2276mm D: 570mm 720 door 47 fascia 455 aperture 896 door Hand by hinge	600mm	OH662315A

**Important:** Please check the appliance manufacturer's instructions as to the venting requirements for any particular appliance.  
 All appliances must be fitted strictly in accordance with the manufacturer's instructions. Check appliance dimensions fit the appliance housing before ordering. Fascia panels can be cut to suit. Edging tape or the OHUCAP6 are available for re-edging the fascia after cutting.  
**UPGRADE:** EKO timber drawer boxes are available as an optional upgrade with all Classic ranges.

# UNIT CONTENT







PANTRY CABINETS		WIDTH	CODE
	Pantry Cabinet	1000mm	<b>PU10623</b>
	H: 2276mm D: 570mm		
	1228 doors (x2)		
	896 door (x2)		
	Five adjustable shelves Supplied RFA (Joined Frame and door in New England)		
	Pantry Cabinet with Internals	1000mm	<b>PU10623R1</b>
	H: 2276mm D: 600mm		
	x2 1228mm doors		
	x2 896mm doors		
	x3 shelves x1 internal timber cutlery drawer x2 chrome wine racks x1 chrome wine glass insert x2 wicker baskets x6 chrome door storage baskets Supplied on a Ready For Assembly Blonde Oak cabinet only Available in Classic ranges only		
	Pantry Cabinet with Internals	1000mm	<b>PU10623R2</b>
	H: 2276mm D: 600mm		
	x2 1228mm doors		
	x2 896mm doors		
	x3 shelves x1 internal timber cutlery drawer x2 chrome wine racks x1 chrome wine glass insert x2 wicker baskets x2 plate racks x6 chrome door storage baskets Supplied on a Ready For Assembly Blonde Oak cabinet only Available in Classic ranges only		
	Pantry Cabinet with Internals	1000mm	<b>PU10623R3</b>
	H: 2276mm D: 600mm		
	x2 1228mm doors		
	x2 896mm doors		
	x3 shelves x1 internal timber cutlery drawer x2 chrome wine racks x1 chrome wine glass insert x2 wicker baskets x1 plate rack x6 timber spice boxes x6 chrome door storage baskets Supplied on a Ready For Assembly Blonde Oak cabinet only Available in Classic ranges only		

2276MM HIGH UNITS – 30/70 SPECIFICATION (ALIGNS 896MM HIGH TOP DOORS)			
REDUCED DEPTH LARDER CABINETS	WIDTH	285mm STANDARD DEPTH	330mm PREMIUM DEPTH
	30/70 Reduced Depth Larder Cabinet		
	H: 2276mm	<b>LU3323B</b>	<b>LU3323PB</b>
	896 door	<b>LU5323B</b>	<b>LU5323PB</b>
	1228 door	<b>LU6323B</b>	<b>LU6323PB</b>
	Hand by hinge One fixed shelf and five additional shelves (Joined Frame and door in New England)		

**Important:** Please check the appliance manufacturer's instructions as to the venting requirements for any particular appliance. All appliances must be fitted strictly in accordance with the manufacturer's instructions. Check appliance dimensions fit the appliance housing before ordering. Fascia panels can be cut to suit. Edging tape or the OHUCAP6 are available for re-edging the fascia after cutting.

**UPGRADE:** EKO timber drawer boxes are available as an optional upgrade with all Classic ranges.

# UNIT CONTENT

LARDER CABINETS		WIDTH	CODE
	30/70 Larder Cabinet	300mm	<b>LU3623B</b>
	H: 2276mm D: 570mm	500mm	<b>LU5623B</b>
	896 door	600mm	<b>LU6623B</b>
	1228 door		
	Hand by hinge		
	Five adjustable shelves		
	(Joined Frame and door in New England)		
FRIDGE/FREEZER HOUSINGS		WIDTH	CODE
	In-Column Integrated Housing	600mm (slider fixing appliances)	<b>IF6623B</b>
	H: 2276mm D: 570mm	600mm (door-on-door appliances)	
	896 door	Cabinet without appliance doors	<b>IF6623BND</b>
	1228 door	1228 appliance door	<b>DRIFBOT2UD</b>
	Hand by hinge		
	One appliance behind bottom door		
	Suitable for use with 1225mm high integrated fridge/freezers only		
	Check fridge freezer specification		
	Frontals are hinged to cabinets designed for slider fixing appliances		
	Appliance frontals are supplied separately to the cabinet for door-on-door appliances		
	(Joined Frame and door in New England)		
OVEN HOUSINGS		WIDTH	CODE
	Single Oven Housing – Door	600mm	<b>OH66235A</b>
	H: 2276mm D: 570mm		
	896 door		
	72 fascia		
	595 aperture		
	557 door		
	Hand by hinge		
	Microwave/Compact Appliance Housing – Door	600mm	<b>OH66237A</b>
	H: 2276mm D: 570mm		
	896 door		
	47 fascia		
	457 aperture		
	720 door		
	Hand by hinge		
	Microwave/Compact Appliance Housing – Top Drawer	600mm	<b>OH662310I</b>
	H: 2276mm D: 570mm		
	896 door		
	47 fascia		
	455 aperture		
	159 drawer		
	557 door		
	Hand by hinge		
	Not available in Inline		
	Microwave/Compact Appliance Housing – 2 Pan	600mm	<b>OH662310G</b>
	H: 2276mm D: 570mm		
	896 door		
	47 fascia		
	456 aperture		
	358 drawer		
	358 drawer		
	Hand by hinge		

**Important:** Please check the appliance manufacturer's instructions as to the venting requirements for any particular appliance. All appliances must be fitted strictly in accordance with the manufacturer's instructions. Check appliance dimensions fit the appliance housing before ordering. Fascia panels can be cut to suit. Edging tape or the OHUCAP6 are available for re-edging the fascia after cutting.




**UPGRADE:** EKO timber drawer boxes are available as an optional upgrade with all Classic ranges.

# UNIT CONTENT

OVEN HOUSINGS	WIDTH	CODE
 <p>Microwave/Compact Appliance Housing – 3 Pan  H: 2276mm D: 570mm  896 door  47 fascia  456 aperture  159 drawer  276 drawer  276 drawer  Hand by hinge  Not available in Inline</p>	600mm	<b>OH662310D</b>

## 2276MM HIGH UNITS – ADDITIONAL 70/30 SPECIFICATION (ALIGNS 720MM HIGH BASE DOORS)







FRIDGE/FREEZER HOUSINGS	WIDTH	CODE
 <p>Tall 70/30 Integrated Housing  H: 2276mm D: 570mm  296 flap  1106 door  720 door  Hand by hinge  One appliance behind mid and bottom door  Check fridge freezer specification  Frontals are hinged to cabinets designed for slider fixing appliances  Appliance frontals are supplied separately to the cabinet for door-on-door appliances  (Joined Frame and door in New England)</p>	600mm (slider fixing appliances) 600mm (door-on-door appliances) Cabinet without appliance doors 1106 appliance door 720 appliance door	<b>IF6623K</b>  <b>IF6623KND</b> <b>DRIFTOP6UD</b> <b>DRFH6UD</b>

OVEN HOUSINGS	WIDTH	CODE
 <p>Single Oven Housing – Door  H: 2276mm D: 570mm  720 door  72 fascia  608 aperture  720 door  Hand by hinge</p>	600mm	<b>OH66234C</b>
 <p>Single Oven Housing – Top Drawer  H: 2276mm D: 570mm  720 door  72 fascia  608 aperture  159 drawer  557 door  Hand by hinge  Not available in Inline</p>	600mm	<b>OH66234A</b>
 <p>Single Oven Housing – 2 Pan  H: 2276mm D: 570mm  720 door  72 fascia  607 aperture  358 drawer  358 drawer  Hand by hinge</p>	600mm	<b>OH662310E</b>

**Important:** Please check the appliance manufacturer's instructions as to the venting requirements for any particular appliance. All appliances must be fitted strictly in accordance with the manufacturer's instructions. Check appliance dimensions fit the appliance housing before ordering. Fascia panels can be cut to suit. Edging tape or the OHUCAP6 are available for re-edging the fascia after cutting.

**UPGRADE:** EKO timber drawer boxes are available as an optional upgrade with all Classic ranges.




# UNIT CONTENT

OVEN HOUSINGS		WIDTH	CODE
	Single Oven Housing – 3 Pan H: 2276mm D: 570mm 720 door 72 fascia 607 aperture 159 drawer 276 drawer 276 drawer Hand by hinge Not available in Inline	600mm	OH662310A
	Microwave/Compact Appliance Housing – Door H: 2276mm D: 570mm 896 door 47 fascia 457 aperture 720 door Hand by hinge	600mm	OH66237A
	Microwave/Compact Appliance Housing – Top Drawer H: 2276mm D: 570mm 896 door 47 fascia 455 aperture 159 drawer 557 door Hand by hinge Not available in Inline	600mm	OH662310I
	Microwave/Compact Appliance Housing – 2 Pan H: 2276mm D: 570mm 896 door 47 fascia 456 aperture 358 drawer 358 drawer Hand by hinge	600mm	OH662310G
	Single Oven and Microwave/Compact Appliance Housing – Door H: 2276mm D: 570mm 296 flap 72 fascia (scribe required) 455 aperture 18 shelf (supplied loose) 595 aperture 720 door Hand by hinge Supplied with Aluminium fascia cap (OHUCAP6) – supplied loose	600mm	OH662312A
	Single Oven and Microwave/Compact Appliance Housing – Top Drawer H: 2276mm D: 570mm 296 flap 72 fascia (scribe required) 455 aperture 18 shelf (supplied loose) 595 aperture 159 drawer 557 door Hand by hinge Supplied with Aluminium fascia cap (OHUCAP6) – supplied loose Not available in Inline	600mm	OH662312B


**Important:** Please check the appliance manufacturer's instructions as to the venting requirements for any particular appliance. All appliances must be fitted strictly in accordance with the manufacturer's instructions. Check appliance dimensions fit the appliance housing before ordering. Fascia panels can be cut to suit. Edging tape or the OHUCAP6 are available for re-edging the fascia after cutting.

**UPGRADE:** EKO timber drawer boxes are available as an optional upgrade with all Classic ranges.

# UNIT CONTENT

OVEN HOUSINGS	WIDTH	CODE
 <p>Single Oven and Microwave/Compact Appliance Housing – 2 Pan 600mm  H: 2276mm D: 570mm  296 flap  72 fascia (scribe required)  455 aperture  18 shelf (supplied loose)  595 aperture  358 drawer  358 drawer  Supplied with Aluminium fascia cap (OHUCAP6) – supplied loose</p>		<b>OH662312D</b>
 <p>Single Oven and Microwave/Compact Appliance Housing – 3 Pan 600mm  H: 2276mm D: 570mm  296 flap  72 fascia (scribe required)  455 aperture  18 shelf (supplied loose)  595 aperture  159 drawer  276 drawer  276 drawer  Supplied with Aluminium fascia cap (OHUCAP6) – supplied loose  Not available in Inline</p>		<b>OH662312C</b>
 <p>Twin Microwave/Compact Appliance Housing – 3 Pan  H: 2276mm D: 570mm  557 door  72 fascia  770 aperture  159 drawer  276 drawer  276 drawer  Hand by hinge  Not available in Inline</p>	600mm	<b>OH662310C</b>

## 2276MM HIGH UNITS – IN-COLUMN SPECIFICATION (ALIGNS 296MM HIGH TOP FLAPS)






FRIDGE/FREEZER HOUSINGS	WIDTH	CODE
 <p>In-Column Integrated Housing  H: 2276mm D: 570mm  296 flap  930 door  896 door  Hand by hinge  One appliance behind middle door  Suitable for use with 880mm high integrated fridge/freezers only  Check fridge freezer specification  Frontals are hinged to cabinets designed for slider fixing appliances  Appliance frontals are supplied separately to the cabinet for door-on-door appliances  (Joined Frame and door in New England)</p>	600mm (slider fixing appliances) 600mm (door-on-door appliances) Cabinet without appliance doors 930 appliance door	<b>IF6623C</b> <b>IF6623CND</b> <b>DRIFMIDUD</b>

OVEN HOUSINGS	WIDTH	CODE
 <p>Twin Single Oven Housing – Door  H: 2276mm D: 570mm  296 flap  72 fascia (scribe required)  595 aperture  18 shelf (supplied loose)  595 aperture  557 door  Hand by hinge  Supplied with Aluminium fascia cap (OHUCAP6) – supplied loose</p>	600mm	<b>OH662313A</b>

**Important:** Please check the appliance manufacturer's instructions as to the venting requirements for any particular appliance. All appliances must be fitted strictly in accordance with the manufacturer's instructions. Check appliance dimensions fit the appliance housing before ordering. Fascia panels can be cut to suit. Edging tape or the OHUCAP6 are available for re-edging the fascia after cutting.

**UPGRADE:** EKO timber drawer boxes are available as an optional upgrade with all Classic ranges.

# UNIT CONTENT






OVEN HOUSINGS		WIDTH	CODE
	Single Oven and Microwave/Compact Appliance Housing – Door	600mm	<b>OH662312A</b>
	H: 2276mm D: 570mm 296 flap 72 fascia (scribe required) 455 aperture 18 shelf (supplied loose) 595 aperture 720 door Hand by hinge Supplied with Aluminium fascia cap (OHUCAP6) – supplied loose		
	Single Oven and Microwave/Compact Appliance Housing – Top Drawer	600mm	<b>OH662312B</b>
	H: 2276mm D: 570mm 296 flap 72 fascia (scribe required) 455 aperture 18 shelf (supplied loose) 595 aperture 159 drawer 557 door Hand by hinge Supplied with Aluminium fascia cap (OHUCAP6) – supplied loose Not available in Inline		
	Single Oven and Microwave/Compact Appliance Housing – 2 Pan	600mm	<b>OH662312D</b>
	H: 2276mm D: 570mm 296 flap 72 fascia (scribe required) 455 aperture 18 shelf (supplied loose) 595 aperture 358 drawer 358 drawer Supplied with Aluminium fascia cap (OHUCAP6) – supplied loose		
	Single Oven and Microwave/Compact Appliance Housing – 3 Pan	600mm	<b>OH662312C</b>
	H: 2276mm D: 570mm 296 flap 72 fascia (scribe required) 455 aperture 18 shelf (supplied loose) 595 aperture 159 drawer 276 drawer 276 drawer Supplied with Aluminium fascia cap (OHUCAP6) – supplied loose Not available in Inline		
2276MM HIGH UNITS – MISCELLANEOUS			
LARDER CABINETS		WIDTH	CODE
	Diagonal Larder Cabinet	1015x1015mm	<b>DLU1023</b>
	H: 2276mm 1228mm door 896mm door Supplied on a Ready For Assembly Blonde Oak cabinet only Not available with replacement ends Not available in Inline		

**Important:** Please check the appliance manufacturer's instructions as to the venting requirements for any particular appliance. All appliances must be fitted strictly in accordance with the manufacturer's instructions. Check appliance dimensions fit the appliance housing before ordering. Fascia panels can be cut to suit. Edging tape or the OHUCAP6 are available for re-edging the fascia after cutting.

**UPGRADE:** EKO timber drawer boxes are available as an optional upgrade with all Classic ranges.









# UNIT CONTENT

FRIDGE/FREEZER HOUSINGS		WIDTH	CODE
	Single Oven and Integrated Fridge Housing H: 2276mm D: 570mm 557 door 47 fascia 594 aperture 930 door Hand by hinge Check fridge freezer specification Frontals are hinged to cabinets designed for slider fixing appliances Appliance frontals are supplied separately to the cabinet for door-on-door appliances	600mm (slider fixing appliances) 600mm (door-on-door appliances) Cabinet without appliance doors 930 appliance door	<b>OFH6623C</b>  <b>OFH6623CND</b> <b>DRIFBOT1UD</b>
	Single Oven and Integrated Fridge Housing H: 2276mm D: 570mm 720 door 47 fascia 455 aperture 930 door Hand by hinge Check fridge freezer specification The fascia panel requires cutting to suit the oven on site Frontals are hinged to cabinets designed for slider fixing appliances Appliance frontals are supplied separately to the cabinet for door-on-door appliances	600mm (slider fixing appliances) 600mm (door-on-door appliances) Cabinet without appliance doors 930 appliance door	<b>OFH6623D</b>  <b>OFH6623DND</b> <b>DRIFBOT1UD</b>
OVEN HOUSINGS		WIDTH	CODE
	Twin Single Oven Housing H: 2276mm D: 600mm 557mm door 595mm aperture 18mm shelf (supplied loose) 595mm aperture 358mm drawer Hand by hinge Supplied with Aluminium Fascia Cap (OHUCAP6), supplied loose Not available in New England	600mm	<b>OH662317A</b>
	Single Oven and Microwave/Compact Appliance Housing H: 2276mm D: 570mm For use with NEFF seamless appliance arrangements 720 door 120 fascia (scribe required) 455 aperture 18 shelf (supplied loose) 595 aperture 296 drawer Hand by hinge Supplied with Aluminium fascia cap (OHUCAP6) – supplied loose	600mm	<b>OH66231E</b>
	Single Oven and Microwave/Compact Appliance Housing H: 2276mm D: 570mm 557 door 120 fascia 375 aperture 18 shelf 595 aperture 450 drawer Hand by hinge	600mm	<b>OH66232A</b>
	Single Oven and Microwave/Compact Appliance Housing H: 2276mm D: 570mm 557 door 47 fascia 459 aperture 18 shelf 595 aperture 450 drawer Hand by hinge	600mm	<b>OH66232I</b>

**Important:** Please check the appliance manufacturer's instructions as to the venting requirements for any particular appliance. All appliances must be fitted strictly in accordance with the manufacturer's instructions. Check appliance dimensions fit the appliance housing before ordering. Fascia panels can be cut to suit. Edging tape or the OHUCAP6 are available for re-edging the fascia after cutting.

**UPGRADE:** EKO timber drawer boxes are available as an optional upgrade with all Classic ranges.



# UNIT CONTENT




OVEN HOUSINGS		WIDTH	CODE
	Single Oven and Microwave/Compact Appliance Housing H: 2276mm D: 570mm For use with NEFF seamless appliance arrangements 557 door 120 fascia (scribe required) 455 aperture 18 shelf (supplied loose) 595 aperture 450 drawer Hand by hinge Internal top drawer Supplied with Aluminium fascia cap (OHUCAP6) – supplied loose	600mm	<b>OH66232K</b>
	Double Oven Housing H: 2276mm D: 570mm 557 door 120 fascia 890 aperture 557 door Hand by hinge	600mm	<b>OH66233A</b>
	Double Oven Housing H: 2276mm D: 570mm 557 door 120 fascia 885 aperture 276 drawer 276 drawer Hand by hinge	600mm	<b>OH662310B</b>
	Double Oven and Microwave/Compact Appliance Housing – 1 Pan H: 2276mm D: 570mm 450 door 120 fascia 380 aperture 18 shelf 888 aperture 276 drawer Hand by hinge	600mm	<b>OH66238B</b>
	Double Oven and Microwave/Compact Appliance Housing – 1 Pan H: 2276mm D: 570mm 450 door 47 fascia 453 aperture 18 shelf 888 aperture 276 drawer Hand by hinge	600mm	<b>OH66238A</b>
ACCENT OPEN DISPLAY		WIDTH	CODE
	Accent Open Display End Cabinet H: 2276mm D: 285mm Includes three 724 high accent open wall units Available in 18mm MFC matt colours: Blue, Cashmere and Dark Oak Order framing to suit (includes shelving panels, plinths, legs and fixings)	600mm cabinet	<b>LUODU23</b>
		Frontal matched framing	<b>LUODUFRMF</b>
		Replacement end matched framing	<b>LUODUFRMR</b>





**Important:** Please check the appliance manufacturer's instructions as to the venting requirements for any particular appliance. All appliances must be fitted strictly in accordance with the manufacturer's instructions. Check appliance dimensions fit the appliance housing before ordering. Fascia panels can be cut to suit. Edging tape or the OHUCAP6 are available for re-edging the fascia after cutting.

**UPGRADE:** EKO timber drawer boxes are available as an optional upgrade with all Classic ranges.








# UNIT CONTENT



BASE OVEN HOUSING CABINETS		WIDTH	CODE
	Built Under Oven Housing	600mm	BOH66B
	H: 870mm D: 600mm 72mm fascia 595mm aperture 47mm fascia		
	Built Under Microwave Housing	600mm	MBOH66
	H: 870mm D: 600mm 72mm fascia 495mm aperture 183mm drawer Not available in New England Supplied with Aluminium fascia cap (OHUCAP6) – supplied loose		

INTEGRATED APPLIANCE FRONTALS		WIDTH	CODE
(450mm Frontals are drilled, 600mm frontals are undrilled)			
	Integrated Appliance Frontal	450mm	DRDW45UD
	H: 720mm	600mm	DRFH6UD
	Semi-Integrated Appliance Frontal	600mm	DRDL6UD
	H: 557mm		
	Integrated Appliance Frontal	450mm	IDFD45UD
	H: 720mm includes 557 high door and 159 Drawer front	600mm	IDFD2UD

INTEGRATED COOKER HOOD FRONTALS		WIDTH	CODE
	Integrated Cooker Hood Frontal	600mm	DRICASS
	H: 450mm		
	Integrated Cooker Hood Frontal with Inset Handle	600mm	DRICIN
	H: 450mm Available in Contemporary ranges (excludes Quadra, New York and Paint to Order ranges) only		
	Integrated Cooker Hood Frontal	600mm	DRIC56ASS
	H: 557mm		
	Integrated Cooker Hood Frontal with Inset Handle	600mm	DRIC56IN
	H: 557mm Available in Contemporary ranges (excludes Quadra, New York and Paint to Order ranges) only		

# UNIT CONTENT

MID HEIGHT CABINETS		WIDTH	CODE
	Four Drawer Cabinet H: 1381mm D: 600mm 120mm Fascia x4 276mm Drawers Not available in New England or Inline	600mm	PD66D4
	Single Oven Housing H: 1381mm D: 600mm 72mm Fascia 596mm Aperture 557mm Door Hand by hinge Not available in Inline	600mm	SOH6613
	Single Oven Housing & Microwave Housing H: 1381mm D: 600mm 47mm Fascia 422mm Aperture 595mm Aperture 120mm Fascia Not available in Inline	600mm	SOH6613A
	Double Oven Housing H: 1381mm D: 600mm 47mm Fascia 890mm Aperture 296mm Drawer Not available in Inline	600mm	DOH6613
	Microwave Oven Housing H: 1381mm D: 600mm 47mm Fascia 450mm Aperture 159mm Drawer x2 276mm Drawers Not available in Inline	600mm	MOH6613D3
	Fridge Housing H: 1381mm D: 570mm 930 door 296 drawer Hand by hinge 18mm Excel Cabinets only Not available in Inline Check fridge freezer specification Frontals are hinged to cabinets designed for slider fixing appliances Appliance frontals are supplied separately to the cabinet for door-on-door appliances	600mm (slider fixing appliances)	IF6613
		600mm (door-on-door appliances)	IF6613ND
		Cabinet without appliance doors	DRIFBOT1UD
		930 appliance door	
	Larder Cabinet H: 1381mm D: 600mm 1228mm Door Hand by hinge (Joined Frame and door in New England) Not available in Inline	500mm	LU5613
		600mm	LU6613

APPLIANCE HOUSING ACCESSROIES		HEIGHT	CODE
	Fascia Panels W: 600mm	47mm	KFAAH4
		72mm	KFAAH7
		120mm	KFAAHB
	Oven Housing Fascia Cap To be ordered if not supplied for finishing cut fascia panels on site Supplied with selected appliances as detailed previously		OHUCAP6

# RANGED ACCESSORIES

RECOMMENDED: RANGE PANEL SPECIFICATION			
RANGE	COLOUR	PANEL FINISH – 'R' CODES	PANEL FINISH – 'F' CODES
<b>CONTEMPORARY</b>			
ALTA	GLOSS DUSK GREY	GLOSS PAINTED	GLOSS PAINTED
ALTA	GLOSS MUSSEL	GLOSS PAINTED	GLOSS PAINTED
ALTA	GLOSS PEARL GREY	GLOSS PAINTED	GLOSS PAINTED
ALTA	GLOSS PURE WHITE	GLOSS PAINTED	GLOSS PAINTED
ALTA	MATT ANTHRACITE	MATT PAINTED	MATT PAINTED
ALTA	MATT DARK WALNUT	TEXTURED MDF	TEXTURED MDF
ALTA	MATT PURE WHITE	MATT PAINTED	MATT PAINTED
ALTA	MATT RUSTIC OAK	TEXTURED MDF	TEXTURED MDF
ALTA PTO	PTO	N/A	MATT PAINTED
INLINE SELECT	GLOSS DUSK GREY	GLOSS PAINTED	GLOSS PAINTED
INLINE SELECT	GLOSS MUSSEL	GLOSS PAINTED	GLOSS PAINTED
INLINE SELECT	GLOSS PEARL GREY	GLOSS PAINTED	GLOSS PAINTED
INLINE SELECT	GLOSS PURE WHITE	GLOSS PAINTED	GLOSS PAINTED
INLINE SELECT	MATT ANTHRACITE	MATT PAINTED	MATT PAINTED
INLINE SELECT	MATT DARK WALNUT	TEXTURED MDF	TEXTURED MDF
INLINE SELECT	MATT PURE WHITE	MATT PAINTED	MATT PAINTED
INLINE SELECT	MATT RUSTIC OAK	TEXTURED MDF	TEXTURED MDF
INLINE TREND	GLOSS ICE ANTHRACITE	GLOSS PAINTED	GLOSS PAINTED
INLINE TREND	GLOSS ICE CASHMERE	GLOSS PAINTED	GLOSS PAINTED
INLINE TREND	GLOSS ICE IVORY	GLOSS PAINTED	GLOSS PAINTED
INLINE TREND	GLOSS ICE PLATINUM	GLOSS PAINTED	GLOSS PAINTED
INLINE TREND	GLOSS ICE WHITE	GLOSS PAINTED	GLOSS PAINTED
INLINE FORM	MATT AVOLA GREY TEXTURED	TEXTURED MFC	TEXTURED MFC
INLINE FORM	MATT OAK	FLAT MFC	FLAT MFC
INLINE FORM	MATT TEXTURED CASHMERE	TEXTURED MFC	TEXTURED MFC

RECOMMENDED: RANGE PANEL SPECIFICATION			
RANGE	COLOUR	PANEL FINISH – 'R' CODES	PANEL FINISH – 'F' CODES
INLINE FORM	MATT TEXTURED COBBLE GREY	TEXTURED MFC	TEXTURED MFC
INLINE FORM	MATT TEXTURED MUSSEL	TEXTURED MFC	TEXTURED MFC
INLINE FORM	MATT TEXTURED PORCELAIN	TEXTURED MFC	TEXTURED MFC
INLINE FORM	MATT TEXTURED STONE	TEXTURED MFC	TEXTURED MFC
MINNESOTA	MATT AVOLA GREY	TEXTURED MFC	TEXTURED MFC
NEW YORK	GLOSS CASHMERE	GLOSS PAINTED	GLOSS PAINTED
NEW YORK	GLOSS DUSK GREY	GLOSS PAINTED	GLOSS PAINTED
NEW YORK	GLOSS IVORY	GLOSS PAINTED	GLOSS PAINTED
NEW YORK	GLOSS PEARL GREY	GLOSS PAINTED	GLOSS PAINTED
NEW YORK	GLOSS WHITE	GLOSS PAINTED	GLOSS PAINTED
NEW YORK	MATT ANTHRACITE	MATT PAINTED	MATT PAINTED
NEW YORK PTO	PTO	N/A	MATT PAINTED
PLAZA	MATT CASHMERE	TEXTURED MFC	TEXTURED MFC
PLAZA	MATT COBBLE GREY	TEXTURED MFC	TEXTURED MFC
PLAZA	MATT MUSSEL	TEXTURED MFC	TEXTURED MFC
PLAZA	MATT PORCELAIN	TEXTURED MFC	TEXTURED MFC
PLAZA	MATT STONE	TEXTURED MFC	TEXTURED MFC
QUADRA	COBBLE GREY	MATT PVC	MATT PVC
QUADRA	WHITE	MATT PVC	MATT PVC
VIRGINIA	OAK	CABINET MATCHED MATT MFC	CABINET MATCHED MATT MFC
WOODBURY	GLOSS ANTHRACITE	GLOSS PAINTED	GLOSS PAINTED
WOODBURY	GLOSS CASHMERE	GLOSS PAINTED	GLOSS PAINTED
WOODBURY	GLOSS IVORY	GLOSS PAINTED	GLOSS PAINTED
WOODBURY	GLOSS PLATINUM	GLOSS PAINTED	GLOSS PAINTED
WOODBURY	GLOSS WHITE	GLOSS PAINTED	GLOSS PAINTED

# RANGED ACCESSORIES

## RECOMMENDED: RANGE PANEL SPECIFICATION

RANGE	COLOUR	PANEL FINISH – 'R' CODES	PANEL FINISH – 'F' CODES
<b>CLASSIC</b>			
ASHBOURNE	IVORY	CABINET MATCHED MATT MFC	GRAINED FOIL WRAPPED
ASHBOURNE	PTO	N/A	MATT PAINTED (GRAINED/GRAINED)
AUSTIN	IVORY	CABINET MATCHED MATT MFC	PAINTED (PLANKED/PLAIN)
AUSTIN	PTO	N/A	MATT PAINTED (PLANKED/PLAIN)
CRANBROOK	COBBLE GREY	CABINET MATCHED MATT MFC	FOIL WRAPPED
CRANBROOK	IVORY	CABINET MATCHED MATT MFC	FOIL WRAPPED
CRANBROOK	PLATINUM	CABINET MATCHED MATT MFC	FOIL WRAPPED
CRANBROOK	SAGE	CABINET MATCHED MATT MFC	FOIL WRAPPED
CRANBROOK	STONE	CABINET MATCHED MATT MFC	FOIL WRAPPED
GEORGIA	OAK	CABINET MATCHED MATT MFC	CABINET MATCHED MATT MFC
NEWPORT	IVORY	CABINET MATCHED MATT MFC	PVC PRESSED (PLAIN/PLAIN)
NEW ENGLAND	PTO	N/A	MATT PAINTED (PLANKED/PLAIN)
OAKHAM	OAK	CABINET MATCHED MATT MFC	VENEERED OAK (PLANKED/PLAIN)
WEXFORD	PTO	N/A	MATT PAINTED (PLANKED/PLAIN)

# RECOMMENDED CORNICE AND PELMET


## GENERIC CORNICE AND PELMET CODES

Generic codes are available that will allocate the recommended cornice or pelmet style automatically to each range.


	FRONTAL MATCHED CODE	CABINET MATCHED CODE
Standard Cornice	CORF	CORC
Standard Pelmet	PELF	PELC
Curved Cornice	CORCUF	N/A
Curved Pelmet	PELCUF	N/A




Modern Tangent Cornice  
**CORT30P/CORT30V**  
(Cranbrook, Georgia and Newport only)




Modern Tangent Pelmet  
**UPST30P/UPST30V**  
(Cranbrook, Georgia and Newport only)




Tall Foil Wrapped Cornice  
**CORT30V**  
(Ashbourne only)  
**CORT30PTO**  
(Ashbourne PTO only)




Square Foil Wrapped Pelmet  
**UPST30V**  
(Ashbourne only)  
**UPST30PTO**  
(Ashbourne PTO only)




Tall Cornice  
**CORCT30V**  
(Austin and Oakham, only)  
**CORCT30VPTO**  
(Austin PTO, New England PTO and Wexford PTO only)




Square Pelmet  
**UPSCS30V**  
(Austin and Oakham, only)  
**UPSCS30PTO**  
(Austin PTO, New England PTO and Wexford PTO only)



Universal Cornice and Pelmet  
**CORPEL30/CORPEL30F**  
(Alta PTO, Ashbourne, Cranbrook (except Cobble Grey), Georgia, Newport, New York, Virginia and Woodbury only)



Square Universal Cornice and Pelmet  
**CORPEL30F**  
(Alta Gloss, Alta Matt, Cranbrook Cobble Grey, Minnesota, Plaza, and Quadra only)



# RANGED ACCESSORIES

## RECOMMENDED: BLENDER PANELS, FILLER PANELS & PLINTHS

Three specifications of panels are available. Choose a C, R or F on the end of the code to ensure the panels co-ordinate with either the cabinet, replacement end or frontal throughout the kitchen.

SPEC LEVEL	WALL BLENDER	BASE BLENDER	TALL BLENDER	SHELVING	BREAKFAST BAR PANEL*
Dimensions	352x970x18mm	650x920x18mm	2400x750x18mm	2600x352x18mm	900x920x18mm
STANDARD CABINET	<b>BWU390C</b>	<b>BBU6592C</b>	<b>BLU7523C</b>	<b>SHPANEL24C</b>	<b>N/A</b>
REPLACEMENT ENDS	<b>BWU390R</b>	<b>BBU6592R</b>	<b>BLU7523R</b>	<b>SHPANEL24R</b>	<b>BBBP992R</b>
FRONTAL CO-ORDINATED	<b>BWU390F</b>	<b>BBU6592F</b>	<b>BLU7523F</b>	<b>SHPANEL24F</b>	<b>BBBP992F</b>

SPEC LEVEL	BREAKFAST BAR PANEL	BREAKFAST BAR PANEL	BREAKFAST BAR PANEL†	BOILER HOUSING BLENDER†	PLINTH* (Inc. Seal)
Dimensions	1200x920x18mm	1800x920x18mm	2400x920x18mm	970x400x18	2600x146mm (minimum size)
STANDARD CABINET	<b>N/A</b>	<b>BBBP1892C</b>	<b>N/A</b>	<b>N/A</b>	<b>CONPLINTHC</b>
REPLACEMENT ENDS	<b>BBBP1292R</b>	<b>BBBP1892R</b>	<b>N/A</b>	<b>N/A</b>	<b>CONPLINTHR</b>
FRONTAL CO-ORDINATED	<b>BBBP1292F</b>	<b>BBBP1892F</b>	<b>BBBP2492F</b>	<b>BWU490F</b>	<b>CONPLINTHF</b>

Cabinet colour panels are matt MFC material. Panels that match replacement ends will be a combination of cabinet and frontal co-ordinating panels.

Note: Alta and Inline Select ranges have 350mm deep filler, wall and shelving panels.

New York has 22mm filler panels, wall blenders, base blenders, tall blenders, shelving and breakfast bar panels. Cranbrook, New England and New York have 355mm deep wall blenders and shelving panels.

\* 900mm breakfast bars are available in selected ranges. An 1800mm panel and edging tape will be supplied for any range that has a Cabinet Matched panel specification on pages 69-70 and for Austin, Hacienda, Minnesota, Newport, Oakham, Plaza Mussel and Plaza Stone.

† The 2400mm breakfast bar is available in all Paint to Order ranges only. The boiler housing blender is available in Classic Paint to Order ranges only.

\* Frontal matched plinths are 18mm thick, except Cranbrook and Woodbury finishes, which are 16mm. Cabinet matched plinths are 15mm thick.

## INFILL CODES

General infill panel codes have been set up to make it easier to specify the correct infills across all kitchen ranges. These specify either a frontal or blender to be used as an infill depending on the range (e.g. New York is supplied with a frontal with the integrated handle, whereas Austin is supplied with a blender panel with a flat profile).

BASE FILLER PANEL*	561mm HIGH WALL UNIT FILLER*	724mm HIGH WALL UNIT FILLER*	900mm HIGH WALL UNIT FILLER*
<b>BFF372</b>	<b>WF356</b>	<b>WF372</b>	<b>WF390</b>

\* Dimensions vary by range, but will either be supplied with a 300mm frontal or 352mm wide blender panel.

## DRESSER CABINET BLENDER

1366x352x18mm

AUSTIN PTO	<b>BWU313PTO</b>
AUSTIN IVORY	<b>BWU313</b>
NEW ENGLAND PTO	<b>BWU313PTO</b>
OAKHAM	<b>BWU313</b>
WEXFORD PTO	<b>BWU313PTO</b>

Cabinet colour panels are Matt MFC material. Panels that match replacement ends will be a combination of cabinet and frontal co-ordinating panels.



# RANGED ACCESSORIES

## PILASTERS

RANGE	COLOUR	FINISH	*WALL CHUNKY PILASTER	*TALL CHUNKY PILASTER	*MID-HEIGHT CHUNKY PILASTER
ASHBOURNE	IVORY	FRONTAL MATCHED	N/A	N/A	N/A
ASHBOURNE	PAINT TO ORDER	FRONTAL MATCHED	N/A	N/A	N/A
AUSTIN	IVORY	FRONTAL MATCHED	N/A	N/A	N/A
AUSTIN	PAINT TO ORDER	FRONTAL MATCHED	100x900mm <b>CHPIL1010PTO</b>	100x2276mm <b>CHPIL1023PTO</b>	100x1366mm <b>CHPIL1013PTO</b>
CRANBROOK	ALL COLOURS	FRONTAL MATCHED	N/A	N/A	N/A
NEW ENGLAND	PAINT TO ORDER	FRONTAL MATCHED	100x900mm <b>CHPIL1010PTO</b>	100x2276mm <b>CHPIL1023PTO</b>	100x1366mm <b>CHPIL1013PTO</b>
WEXFORD	PAINT TO ORDER	FRONTAL MATCHED	100x900mm <b>CHPIL1010PTO</b>	100x2276mm <b>CHPIL1023PTO</b>	100x1366mm <b>CHPIL1013PTO</b>
RANGE	COLOUR	FINISH	*BASE CHUNKY PILASTER	*BASE/WALL CURVED PILASTER	*TALL CURVED PILASTER
ASHBOURNE	IVORY	FRONTAL MATCHED	N/A	75x970mm <b>BUCNRE92CU</b>	75x2400mm <b>LUCNRE24CU</b>
ASHBOURNE	PAINT TO ORDER	FRONTAL MATCHED	N/A	75x970mm <b>BUCNR97CUPTO</b>	75x2400mm <b>LUCNR24CUPTO</b>
AUSTIN	IVORY	FRONTAL MATCHED	N/A	75x970mm <b>BUCNRE92CU</b>	75x2400mm <b>LUCNRE24CU</b>
AUSTIN	PAINT TO ORDER	FRONTAL MATCHED	100x870mm <b>CHPIL1087PTO</b>	75x970mm <b>BUCNR97CUPTO</b>	75x2400mm <b>LUCNR24CUPTO</b>
CRANBROOK	ALL COLOURS	FRONTAL MATCHED	N/A	75x970mm <b>BUCNRE92CU</b>	75x2400mm <b>LUCNRE24CU</b>
NEW ENGLAND	PAINT TO ORDER	FRONTAL MATCHED	100x870mm <b>CHPIL1087PTO</b>	75x970mm <b>BUCNR97CUPTO</b>	75x2400mm <b>LUCNR24CUPTO</b>
WEXFORD	PAINT TO ORDER	FRONTAL MATCHED	100x870mm <b>CHPIL1087PTO</b>	75x970mm <b>BUCNR97CUPTO</b>	75x2400mm <b>LUCNR24CUPTO</b>

# RANGED ACCESSORIES












## MANTLE & ACCESSORIES

RANGE	COLOUR	FINISH	MANTEL SHELF*	MANTEL SHELF*	MANTEL SHELF*	MANTEL SHELF*
ASHBOURNE	IVORY	TIMBER ASH VENEERED	1600x109x262 <b>MANTSHELF16</b>	1800x109x262 <b>MANTSHELF18</b>	1900x109x262 <b>MANTSHELF19</b>	2000x109x262 <b>MANTSHELF20</b>
ASHBOURNE	PAINT TO ORDER	PAINT TO ORDER TIMBER ASH VENEERED	1600x109x262 <b>MANTSHF16PTO</b>	1800x109x262 <b>MANTSHF18PTO</b>	1900x109x262 <b>MANTSHF19PTO</b>	2000x109x262 <b>MANTSHF20PTO</b>
AUSTIN	IVORY	FRONTAL MATCHED	1600x109x262 <b>MANTSHELF16</b>	1800x109x262 <b>MANTSHELF18</b>	1900x109x262 <b>MANTSHELF19</b>	2000x109x262 <b>MANTSHELF20</b>
CRANBROOK	ALL COLOURS	PAINT TO ORDER	1600x109x262 <b>MANTSHF16PTO</b>	1800x109x262 <b>MANTSHF18PTO</b>	1900x109x262 <b>MANTSHF19PTO</b>	2000x109x262 <b>MANTSHF20PTO</b>
OAKHAM	BLONDE OAK	FRONTAL MATCHED	1600x109x262 <b>MANTSHELF16</b>	1800x109x262 <b>MANTSHELF18</b>	1900x109x262 <b>MANTSHELF19</b>	2000x109x262 <b>MANTSHELF20</b>
AUSTIN	PAINT TO ORDER	FRONTAL MATCHED	1600x109x262 <b>MANTSHF16PTO</b>	1800x109x262 <b>MANTSHF18PTO</b>	1900x109x262 <b>MANTSHF19PTO</b>	2000x109x262 <b>MANTSHF20PTO</b>
WEXFORD	PAINT TO ORDER	FRONTAL MATCHED	1600x109x262 <b>MANTSHF16PTO</b>	1800x109x262 <b>MANTSHF18PTO</b>	1900x109x262 <b>MANTSHF19PTO</b>	2000x109x262 <b>MANTSHF20PTO</b>
NEW ENGLAND	PAINT TO ORDER	FRONTAL MATCHED	1600x109x262 <b>MANTSHF16PTO</b>	1800x109x262 <b>MANTSHF18PTO</b>	1900x109x262 <b>MANTSHF19PTO</b>	2000x109x262 <b>MANTSHF20PTO</b>



RANGE	COLOUR	FINISH	MANTEL SHELF*	MANTEL PANEL*	CORBEL (pack of 2)	DECORATIVE TABLE POST
ASHBOURNE	IVORY	TIMBER ASH VENEERED	2200x109x262 <b>MANTSHELF22</b>	1400x296 <b>MANTLEPNL14</b>	<b>CORBEL2</b>	100x100x970 <b>TABLEPOST9</b>
ASHBOURNE	PAINT TO ORDER	PAINT TO ORDER TIMBER ASH VENEERED	2200x109x262 <b>MANTSHF22PTO</b>	1400x296 <b>MANTPNL14PTO</b>	<b>CORBEL2PTO</b>	100x100x970 <b>TABLEPST9PTO</b>
AUSTIN	IVORY	FRONTAL MATCHED	2200x109x262 <b>MANTSHELF22</b>	1400x296 <b>MANTLEPNL14</b>	<b>CORBEL2</b>	100x100x970 <b>TABLEPOST9</b>
CRANBROOK	ALL COLOURS	PAINT TO ORDER	N/A	1400x296 <b>MANTPNL14PTO</b>	<b>CORBEL2PTO</b>	N/A
OAKHAM	BLONDE OAK	FRONTAL MATCHED	2200x109x262 <b>MANTSHELF22</b>	1400x296 <b>MANTLEPNL14</b>	<b>CORBEL2</b>	100x100x970 <b>TABLEPOST9</b>
AUSTIN	PAINT TO ORDER	FRONTAL MATCHED	2200x109x262 <b>MANTSHF22PTO</b>	1400x296 <b>MANTPNL14PTO</b>	<b>CORBEL2PTO</b>	100x100x970 <b>TABLEPST9PTO</b>
WEXFORD	PAINT TO ORDER	FRONTAL MATCHED	2200x109x262 <b>MANTSHF22PTO</b>	1400x296 <b>MANTPNL14PTO</b>	<b>CORBEL2PTO</b>	100x100x970 <b>TABLEPST9PTO</b>
NEW ENGLAND	PAINT TO ORDER	FRONTAL MATCHED	2200x109x262 <b>MANTSHF22PTO</b>	1400x296 <b>MANTPNL14PTO</b>	<b>CORBEL2PTO</b>	100x100x970 <b>TABLEPST9PTO</b>




\*Please note that the dimensions of the mantel shelf refers to the top of the shelf. Subtract 80mm to calculate the dimension of the base of the shelf

# RANGED ACCESSORIES















SHELVING, FILLERS & PLINTHS		SPEC	CODE
	MFC Back Panels Available in cabinet colours: Ivory, Blonde Oak and White	18mm Thick 1800x920mm	<b>BBBP1892C</b>
		18mm Thick 900x920mm	<b>BBBP992C</b>
	MFC End Panels Available in cabinet colours: Ivory, Blonde Oak and White	18mm Thick 650x920mm	<b>BBU6592C</b>
	MFC Tray Space Available in cabinet colours: Ivory, Blonde Oak and White Reverse is always White	300mm	<b>TSP3X6P</b>
	MFC Filler Panels Available in cabinet colours: Ivory, Blonde Oak and White	18mm Thick 970x352mm	<b>BWU390C</b>
	MFC Tall Panels Available in cabinet colours: Ivory, Blonde Oak and White	18mm Thick 750x2400mm	<b>BLU7523C</b>
	MFC Shelving Panels Available in cabinet colours: Ivory, Blonde Oak and White	18mm Thick 2600x352mm	<b>SHPANEL2418C</b>
	Arrow Shelf Bracket Adjustable. Max 40mm shelf thickness Use one bracket every 600mm	18mm (W) 180mm (D) 108mm (H)	<b>SHELFBRKSS</b>
	Floating Shelves to compliment Open Accent Cabinets Includes x3 brackets Available in MFC colours: Cashmere, Dark Oak and Stone	38mm Thick 600x300mm	<b>FLSH6PK</b>
		38mm Thick 900x300mm	<b>FLSH9PK</b>
	Deluxe Hanging Rail Available in set sizes can not be cut Hanging rail only, order shelf separately if required	450mm	<b>DXHR45K</b>
		600mm	<b>DXHR6K</b>
		900mm	<b>DXHR9K</b>
	MFC Continuous Plinth Available in cabinet colours: Ivory, Blonde Oak and White	15mm Thick 2600mm (L) 146mm (H)	<b>CONPLINTHC</b>
		15mm Thick 2600mm (L) 200mm (H)	<b>CONPLINTH262</b>
	Mirror and Aluminium Plinth	Mirrored 18mm Thick 3000mm (L) 146mm (H)	<b>DECPL3MIR</b>
		Aluminium Effect 18mm Thick 3000mm (L) 146mm (H)	<b>DECPLINTH3AU</b>
	15mm Continuous Plinth Seal - For use with CONPLINTHC and CONPLINTH262	2600mm (L)	<b>CONPLINTHS</b>
	18mm Continuous Plinth Seal - For use with Frontal Matched, Aluminium and Mirrored Plinths	2600mm (L)	<b>PLINTHS18</b>

# RANGED ACCESSORIES



SHELVING, FILLERS & PLINTHS		SPEC	CODE								
	Plinth Connector (Pack of 2)	146mm (H) (Cabinet Matched)	BRKPLINTH								
		146mm (H) (Mirrored)	BRKPLINTHMR								
		146mm (H) (Metallic)	DECPLINTHPK								
		200mm (H) (Cabinet Matched)	BRKPLINTH200								
	Edging Tape	22mm (W) 1.4 Metres Available in Cranbrook (all colours), and Painted Ivory only	EDGSTRI14								
		22mm (W) 10 Metres Available in Minnesota, Plaza (all colours) and Quadra (all colours) only	EDGSTRI221F								
		22mm (W) 10 Metres Available in Blonde Oak, Matt Ivory and Matt White only	EDGSTRI2210								
		25mm (W) 2.5 Metres Available in Alta (all colours), New York Gloss, and Woodbury	EDGESTRI24								
		25mm (W) 2.4 Metres Available in all Paint to Order ranges (Re-coatable PVC)	PVCEDG24REC								
<table><tr><th>SPEC LEVEL</th><th>GENERIC CODES</th></tr><tr><td>Standard</td><td>EDGESTRI14C</td></tr><tr><td>Replacement End</td><td>EDGESTRI14R</td></tr><tr><td>Frontal Co-ordinated</td><td>EDGESTRI14F</td></tr></table>		SPEC LEVEL	GENERIC CODES	Standard	EDGESTRI14C	Replacement End	EDGESTRI14R	Frontal Co-ordinated	EDGESTRI14F		
SPEC LEVEL	GENERIC CODES										
Standard	EDGESTRI14C										
Replacement End	EDGESTRI14R										
Frontal Co-ordinated	EDGESTRI14F										


FITTINGS		SPEC	CODE
	Paint to Order Touchup Paint Pot For all Paint to Order colours including Painted Ivory	50ml	PAINTPOT125
	Hinges and Hinge Plates	110° Hinge - Pack of 2	HINGE110
		110° Hinge (Concave) - Pack of 2	HINGE110CO
		110° Hinge (Larder) - Pack of 3	HINGE110LU
		Bi-Fold Centre Hinge	HINGEBIFOLD
		170° Hinge (Concealed) - Pack of 2	HINGE170
		45° Hinge - Pack of 2	HINGE45
		95° Hinge - Pack of 2	HINGE95
		In-Frame Hinge - Pack of 1	HINGEIF
	Ventilation Grill Flow rate 200cm²	45x510mm	VENTGRIDGR
	Replacement Knock-In Legs for Cabinets (Pack of 4)	-	LEG15
	Metal Double Towel Rail	-	METALTRAIL
	Frontal Connecting Brackets (Pack of 2)	-	BRKLCB




# WORK SURFACES

WORKTOPS		DEPTH	MIN LENGTH	MAX LENGTH	CODE
	22mm PVC Square Edged Worktop	Max 870mm	300mm	3000mm	<b>PV22</b>
	22mm Double PVC Square Edged Worktops	Max 900mm	300mm	3000mm	<b>DV22</b>
	40mm Postformed Worktops	Max 600mm	300mm	4020mm	<b>PF40</b>
		601-870mm	300mm	3550mm	<b>PF40</b>
	40mm Double Postformed Worktops	655mm	300mm	4020mm	<b>DP40</b>
		900mm	300mm	3550mm	<b>DP40</b>
	40mm Premium Postformed Worktops (3mm Radius Edge)	600mm	300mm	3550mm	<b>PR40</b>
		Max 870mm	300mm	3550mm	<b>PR40</b>
	40mm Double Premium Postformed Worktops (3mm Radius Edge)	665mm	300mm	3550mm	<b>DR40</b>
		900mm	300mm	3550mm	<b>DR40</b>
	40mm PVC Square Edge Worktops	Max 870mm	300mm	4020mm	<b>PV40</b>
	40mm Double PVC Square Edge Worktops	Max 600mm	300mm	4020mm	<b>DV40</b>
		601-870mm	300mm	3550mm	<b>DV40</b>
	40mm PVC Square Edge Worktops - For use with Convex Curved base cabinets (Radius: 200mm curve on both ends, may require cutting and edging on site)	600mm	600mm	3600mm	<b>PV40CU</b>
		650mm	600mm	3550mm	<b>PV4065CU</b>
	40mm PVC Square Edge Worktops - For use with Convex Curved base cabinets (Radius: 200mm curve on one end, handing required)	600mm (Right)	600mm	3600mm	<b>PV40CUR</b>
		600mm (Left)	600mm	3600mm	<b>PV40CUL</b>
		650mm (Right)	600mm	3550mm	<b>PV4065CUR</b>
		650mm (Left)	600mm	3550mm	<b>PV4065CUL</b>
	40mm PVC Square Edge Worktops - For use with Curved Pilasters (Radius 62mm curved on both ends, may require cutting and edging on site)	600mm	300mm	3600mm	<b>PV40CP</b>
		650mm	300mm	3550mm	<b>PV4065CP</b>
	40mm PVC Square Edge Worktops - For use with Curved Pilasters (Radius: 62mm curved on one end, handing required)	600mm (Right)	600mm	3600mm	<b>PV40CPR</b>
		600mm (Left)	600mm	3600mm	<b>PV40CPL</b>
		650mm (Right)	600mm	3550mm	<b>PV4065CPR</b>
		650mm (Left)	600mm	3550mm	<b>PV4065CPL</b>
	40mm PVC Square Edge Worktops - For use with Convex Island base cabinets (2 curves - Radius: 200mm)	665mm	600mm	3600mm	<b>DV40663CU</b>
		900mm	600mm	3600mm	<b>DV40903CU</b>
	40mm PVC Square Edge Worktops - For use with Convex Island base cabinets (4 curves - Radius: 200mm)	900mm	600mm	3600mm	<b>DV40903BBR</b>









# WORK SURFACES

WORKTOPS		DEPTH	MIN LENGTH	MAX LENGTH	CODE
	40mm PVC Square Edge Worktops - For use with Curved Pilasters (2 curves - Radius: 62mm)	665mm	300mm	3550mm	DV40663CP
		900mm	300mm	3600mm	DV40903CP
	40mm PVC Square Edge Worktops - For use with Curved Pilasters (4 curves - Radius: 62mm)	900mm	300mm	3600mm	DV4090BBP

WORKTOP BLENDERS		WIDTH	HEIGHT	CODE
	22mm PVC Edged Square Cut - Laminated 2 sides edged on 4 sides	650mm	920mm	CVB226592
		900mm	900mm	CVB22992
		352mm	970mm	CVB223597
		900mm	1200mm	CVB221292
		900mm	1800mm	CVB221892
		900mm	2400mm	CVB222492
		750mm	2400mm	CVB227524
		352mm	2400mm	CVB222435
		150mm	2400mm	CVB222415

WORKTOP ACCESSORIES		SPEC	CODE
	TopSeal & EasiBolts Pack • x1 14ml (20g) tube TopSeal • x1 applicator/scrapper • x3 hands free EasiBolt • x1 instruction sheet • x1 lint-free dry wipe Colour co-ordinated to worktop colour selected	40mm	TOPSEALBOLT
		22mm	TOPSEALBLT22
	Laminate Worktop Edging Strip - 3 metres	40mm	WTEDG4
	PVC Worktop Edging Strip	40mm (4.5 metres)	EDGSTRI45
		22mm (3 metres)	EDGSTRI30
	Adjustable Angled Breakfast Bar Leg - Light Grey (base 150mm)	820-900mm (height)	LEGBARANGLE
	22mm Worktop Blanco Sink Clips - To replace standard sink clips when using 22mm worktops - Pack of 10		BL453648

# SPLASHBACKS & UPSTANDS

SPLASHBACKS & UPSTANDS		WIDTH	HEIGHT	CODE
	Coloured Glass Etch Splashbacks - Toughened glass - Thickness 6mm See page 25 for colour options	600mm	750mm	<b>GLSPLASH675</b>
		800mm	750mm	<b>GLSPLASH875</b>
		900mm	750mm	<b>GLSPLASH975</b>
	Coloured Glass Upstands - pack of 2 See page 25 for colour options	1000mm	140mm	<b>GLUP1014</b>
	Stainless Steel Splashback - Thickness 1mm - With 6mm back board to align with tiling. (Supplied loose)	600mm	750mm	<b>SBACK675</b>
		700mm	750mm	<b>SBACK775</b>
		900mm	750mm	<b>SBACK975</b>
	Stainless Steel Splashback - Thickness 15mm	600mm	750mm	<b>EFB675X</b>
		900mm	750mm	<b>EFB975X</b>
	Laminate Splashbacks for 22mm Worktops - Thickness 9mm See pages 22-23 for colour options	3000mm	750mm	<b>WT22SB30X75</b>
		600mm	750mm	<b>WT22SB60X75</b>
	Laminate Splashbacks for 40mm Worktops - Thickness 9mm - 3m length is available in 40mm Premium finishes only See pages 22-23 for colour options	3000mm	750mm	<b>WTSB30X75</b>
		600mm	750mm	<b>WTSB60X75</b>
	Laminate Upstands for use with 40mm Postformed, PVC & Premium worktops D: 12mm See pages 22-23 for colour options	3000mm	95mm	<b>PFUP3095</b>
		3000mm	145mm	<b>PFUP30145</b>
	Laminate Upstands - for use with 22mm PVC Edged worktops D: 12mm See pages 22-23 for colour options	3000mm	95mm	<b>PF22UP3095</b>
		3000mm	145mm	<b>PF22UP30145</b>


# WORKTOPS

## MASON MITRE JOINTS

Laminate worktops can be supplied with a factory cut mitred joint and jointing bolts for assembly on site. All mason mitres are available with 40mm standard and 40mm premium worktops. 40mm PVC-edged and 22mm PVC-edged worktops are available with all except RA, 18, 19, 20, 44 and 45 which are not available due to radius ends.


## MASON MITRE PLANNER (600MM DEEP)

Please allow an extra 23mm for male to female connections and an extra 30mm for corner post situations.




## MASON MITRE PLANNER (650MM DEEP)

Please allow an extra 23mm for male to female connections and an extra 30mm for corner post situations. Can be used in conjunction with 600mm deep mitres.



## BULLNOSE WORKTOP RADIUS END DIAGRAM

Current Radius End Variations. Radius end will be edged in flat laminate (not bullnose).





KESSEBÖHMER PREMIUM STORAGE ACCESSORIES		SPEC	CODE
	ARENA 3/4 Carousel - For use with LSB991PCF & LSB991PCD	N/A	<b>CAROBASK34AR</b>
	ARENA LE MANS - For 800mm & 1000mm Corner Base Cabinets with 400 door For corner cabinet with a door on the left and blank on the right order left handing, vice versa for right. Unit door must open 90°, please be aware of possible handle clash on adjoining door	Right Hand	<b>LEMANSKU4ARR</b>
		Left Hand	<b>LEMANSKU4ARL</b>
	ARENA LE MANS - For 900mm Corner Base Cabinets with 450 door For corner cabinet with a door on the left and blank on the right order left handing, vice versa for right. Unit door must open 90°, please be aware of possible handle clash on adjoining door	Right Hand	<b>LEMANSKU45ARR</b>
		Left Hand	<b>LEMANSKU45ARL</b>
	ARENA LE MANS - For 1000mm Corner Base/Larder Cabinets with 500 door For corner cabinet with a door on the left and blank on the right order left handing, vice versa for right. Unit door must open 90°, please be aware of possible handle clash on adjoining door	Right Hand	<b>LEMANSKU5ARR</b>
		Left Hand	<b>LEMANSKU5ARL</b>
	ARENA LE MANS - For 1000 & 1200mm Corner Base and 1000mm Larder Cabinets with 600 door For corner cabinet with a door on the left and blank on the right order left handing, vice versa for right. Unit door must open 90°, please be aware of possible handle clash on adjoining door	Right Hand	<b>LEMANSKU6ARR</b>
		Left Hand	<b>LEMANSKU6ARL</b>
	ARENA LE MANS AXLE H: 1265mm - Centre pole to allow use of Le Mans pull outs in Corner Larder Cabinets (x2 Le Mans units to be ordered separately)	N/A	<b>LEMANSAXLE</b>

# WIREWORK & STORAGE

KESSEBÖHMER PREMIUM STORAGE ACCESSORIES		CABINET WIDTH	CODE
	ARENA Pull Out Larder-5 Baskets Soft Open and Soft Close	300mm	<b>LUBASK5AR</b>
		500mm	<b>PLBASK5AR</b>
	ARENA Cranked Pull Out Larder-5 Baskets	500mm	<b>PLBASK5CRKAR</b>
		600mm	<b>PLBASK6CRKAR</b>
	ARENA Base Pull Out-2 baskets	150mm	<b>PLBUBASK15AR</b>

## KESSEBÖHMER PREMIUM STORAGE ACCESSORIES

CABINET  
WIDTH

CODE



ARENA 150mm Pull Out Basket & Towel Rail

150mm

**PLBUBASKTRAR**



ARENA Base Pull Out-2 baskets

300mm

**PLBUBASK3AR**



iMove Pull Down Baskets  
- Available for use in 724mm & 900mm  
Single Premium 330mm deep Wall Cabinets only  
Not available with bi-fold cabinets

500mm

**IMOVE5**

600mm

**IMOVE6**

# DRAWER ACCESSORIES

Generic codes are available that provide an appropriate cutlery tray depending on the type of unit and desired specification. There are two specifications of codes;

Default specification (CTRAYV\_ codes) = a plastic cutlery tray







Premium specification (CTRAYM\_ codes) = a metal cutlery tray

Please note where the appropriate specification is not available an alternative specification will be supplied.

The table below identifies the appropriate generic cutlery tray code to use for each base unit.

CABINET CODE	CABINET DESCRIPTION	DEFAULT SPECIFICATION	UPGRADE SPECIFICATION
<b>BU46D</b>	Single Drawer Line Base Cabinet	<b>CTRAYVSTD4</b>	<b>CTRAYMSTD4</b>
<b>BU456D</b>	Single Drawer Line Base Cabinet	<b>CTRAYVSTD45</b>	<b>CTRAYMSTD45</b>
<b>BU56D</b>	Single Drawer Line Base Cabinet	<b>CTRAYVSTD5</b>	<b>CTRAYMSTD5</b>
<b>BU66D</b>	Single Drawer Line Base Cabinet	<b>CTRAYVSTD6</b>	<b>CTRAYMSTD6</b>
<b>BU86D</b>	Double Drawer Line Base Cabinet	<b>CTRAYVSTD4</b>	<b>CTRAYMSTD4</b>
<b>BU96D</b>	Double Drawer Line Base Cabinet	<b>CTRAYVSTD45</b>	<b>CTRAYMSTD45</b>
<b>BU106D</b>	Double Drawer Line Base Cabinet	<b>CTRAYVSTD5</b>	<b>CTRAYMSTD5</b>
<b>BU126D</b>	Double Drawer Line Base Cabinet	<b>CTRAYVSTD6</b>	<b>CTRAYMSTD6</b>
<b>DU46D</b>	Four Drawer Cabinet	<b>CTRAYVSTD4</b>	<b>CTRAYMSTD4</b>
<b>DU56D</b>	Four Drawer Cabinet	<b>CTRAYVSTD5</b>	<b>CTRAYMSTD5</b>
<b>DU66D</b>	Four Drawer Cabinet	<b>CTRAYVSTD6</b>	<b>CTRAYMSTD6</b>
<b>PD56D3</b>	Three Pan Drawer Cabinet	<b>CTRAYVSTD5</b>	<b>CTRAYMSTD5</b>
<b>PD66D3</b>	Three Pan Drawer Cabinet	<b>CTRAYVSTD6</b>	<b>CTRAYMSTD6</b>
<b>PD86D3</b>	Three Pan Drawer Cabinet	<b>CTRAYVSTD8</b>	<b>CTRAYMSTD8</b>
<b>PD96D3</b>	Three Pan Drawer Cabinet	<b>CTRAYVSTD9</b>	<b>CTRAYMSTD9</b>
<b>PD106D3</b>	Three Pan Drawer Cabinet	<b>CTRAYVSTD10</b>	<b>CTRAYMSTD10</b>
<b>PD56D2IDT</b>	Two Pan Drawer Cabinet with Internal Top Drawer	<b>CTRAYVINT5</b>	<b>CTRAYMINT5</b>
<b>PD66D2IDT</b>	Two Pan Drawer Cabinet with Internal Top Drawer	<b>CTRAYVINT6</b>	<b>CTRAYMINT6</b>
<b>PD86D2IDT</b>	Two Pan Drawer Cabinet with Internal Top Drawer	<b>CTRAYVINT8</b>	<b>CTRAYMINT8</b>
<b>PD96D2IDT</b>	Two Pan Drawer Cabinet with Internal Top Drawer	<b>CTRAYVINT9</b>	<b>CTRAYMINT9</b>
<b>BU456F4ID</b>	Base Cabinet with 4 Internal Drawers	<b>CTRAYVFH45</b>	<b>CTRAYMFH45</b>
<b>BU56F4ID</b>	Base Cabinet with 4 Internal Drawers	<b>CTRAYVFH5</b>	<b>CTRAYMFH5</b>
<b>BU66F4ID</b>	Base Cabinet with 4 Internal Drawers	<b>CTRAYVFH6</b>	<b>CTRAYMFH6</b>
<b>BU66F2ID</b>	Base Cabinet with 2 Internal Drawers	<b>CTRAYVINT6</b>	<b>CTRAYMINT6</b>
<b>BU56F3IDC</b>	Base Cabinet with 1 Cutlery and 2 Deep Internal Drawers	<b>CTRAYVFH5</b>	<b>CTRAYMFH5</b>
<b>BU66F3IDC</b>	Base Cabinet with 1 Cutlery and 2 Deep Internal Drawers	<b>CTRAYVFH6</b>	<b>CTRAYMFH6</b>


# DRAWER INTERNALS

DRAWER INTERNALS		CABINET SIZE	CODE
	Plastic Cutlery Trays for Atira Drawer Box (Not available in New England or with EKO Timber drawer boxes) <b>For internal drawers behind hinged doors, reduce width by 50mm (25mm for 300 cabinet size)</b>	275mm (For 300mm Internal Drawer)	<b>CTRAYGAL275V</b>
		300mm	<b>CTRAYGALL3V</b>
		350mm	<b>CTRAYGALL35V</b>
		400mm	<b>CTRAYGALL4V</b>
		450mm	<b>CTRAYGALL45V</b>
		500mm	<b>CTRAYGALL5V</b>
		550mm	<b>CTRAYGALL55V</b>
		600mm	<b>CTRAYGALL6V</b>
		800mm	<b>CTRAYGALL8V</b>
		900mm	<b>CTRAYGALL9V</b>
		1000mm	<b>CTRAYGALL10V</b>
	Metal Cutlery Trays for Atira Drawer Box - D: 470mm (Not suitable with EKO Timber drawer box) <b>For internal drawers behind hinged doors, reduce width by 50mm (25mm for 300 cabinet size)</b>	Universal tray width 110mm for all sizes 275, 300, 350, 400mm	<b>CTRAYMIN234</b>
		Universal tray width 310mm for all sizes 450, 500, 550, 600mm	<b>CTRAYMIN456</b>
		2x universal tray width 310mm for all sizes 800, 900, 1000mm	<b>CTRAYMIN810</b>
	Timber Cutlery Trays for Atira Drawer Box (Not suitable with EKO Timber drawer box) <b>For internal drawers behind hinged doors, reduce width by 50mm (25mm for 300 cabinet size)</b>	Universal tray width 110mm for all sizes 275, 300, 350, 400mm	<b>CTRAYTIN234</b>
		Universal tray width 310mm for all sizes 450, 500, 550, 600mm	<b>CTRAYTIN456</b>
		2x universal tray width 310mm for all sizes 800, 900, 1000mm	<b>CTRAYTIN810</b>
	Timber Cutlery Tray for EKO Timber Drawer Box (Not available in New England or with Atira drawer boxes) <b>For internal drawers behind hinged doors, reduce width by 50mm</b>	400mm	<b>CTRAYGALL4T</b>
		450mm	<b>CTRAYGALL45T</b>
		500mm	<b>CTRAYGALL5T</b>
		600mm	<b>CTRAYGALL6T</b>
		800mm	<b>CTRAYGALL8T</b>
		900mm	<b>CTRAYGALL9T</b>
		1000mm	<b>CTRAYGALL10T</b>
	Timber In-frame Cutlery Trays for EKO Timber Drawer Box Available in New England only (Not suitable with Atira drawer box) <b>For internal drawers behind hinged doors, reduce width by 50mm</b>	400mm	<b>CTRAYIF4T</b>
		450mm	<b>CTRAYIF45T</b>
		500mm	<b>CTRAYIF5T</b>
		600mm	<b>CTRAYIF6T</b>
		800mm	<b>CTRAYIF8T</b>
		900mm	<b>CTRAYIF9T</b>
		1000mm	<b>CTRAYIF10T</b>
	Drawer Mats (Not available in New England) <b>For internal drawers behind hinged doors, reduce width by 50mm</b>	300mm	<b>DWMAT3</b>
		400mm	<b>DWMAT4</b>
		450mm	<b>DWMAT45</b>
		500mm	<b>DWMAT5</b>
		550mm	<b>DWMAT55</b>
		600mm	<b>DWMAT6</b>
		800mm	<b>DWMAT8</b>
		900mm	<b>DWMAT9</b>
		1000mm	<b>DWMAT10</b>

# DRAWER INTERNALS

## TIMBER DRAWER ACCESSORIES (FOR ATIRA METAL DRAWER BOXES ONLY)

Timber Roll Dispenser  
for Atira Drawer Box  
(Not available with  
EKO Timber drawer boxes)



CODE: **ROLLHOLDINS**  
SIZE: 150mm wide

Timber Knife Block  
for Atira Drawer Box  
Knives not included  
(Not available with  
EKO Timber drawer boxes)



CODE: **KNIFEINS**  
SIZE: 150mm wide

Timber Spice Rack  
for Atira Drawer Box  
(Not available with  
EKO Timber drawer boxes)



CODE: **SPICEINS**  
SIZE: 150mm wide

Timber Slideable Tray  
for Atira Drawer Box  
(Not available with  
EKO Timber drawer boxes)



CODE: **SLIDEINS**  
SIZE: 110mm wide

Timber Deep Pan Drawer Insert  
for Atira Drawer Box  
(Not available with  
EKO Timber drawer boxes)  
For 450-600mm drawers order x1  
For 800-1000mm drawers order x2




CODE: **PANDRWINS**  
SIZE: 310mm wide (universal size)

## TIMBER DRAWER SETS (FOR 500mm & 600mm ATIRA METAL DRAWER BOXES ONLY)

WIDTH

CODE



Top Drawer Timber Accessory Systems for Atira Drawer Box  
(Not available with EKO Timber drawer boxes)  
For use with 500-600mm internal cutlery drawers  
(600mm drawer shown)

- **DRWTACC1**  
Universal combined width 260mm  
Includes: Slideable Tray & Roll Dispenser



Top Drawer Timber Accessory Systems for Atira Drawer Box  
(Not available with EKO Timber drawer boxes)  
For use with 500-600mm internal cutlery drawers  
(600mm drawer shown)

- **DRWTACC2**  
Universal combined width 260mm  
Includes: Slideable Tray & Knife Block



Top Drawer Timber Accessory Systems for Atira Drawer Box  
(Not available with EKO Timber drawer boxes)  
For use with 500-600mm internal cutlery drawers  
(600mm drawer shown)

- **DRWTACC3**  
Universal combined width 260mm  
Includes: Slideable Tray & Spice Rack



Top Drawer Timber Accessory Systems for Atira Drawer Box  
(Not available with EKO Timber drawer boxes)  
For use with 500-600mm internal cutlery drawers  
(600mm drawer shown)

- **DRWTACC4**  
Universal combined width 300mm  
Includes: Cutlery Tray & Knife Block  
(600mm drawer only)



Top Drawer Timber Accessory Systems for Atira Drawer Box  
(Not available with EKO Timber drawer boxes)  
For use with 500-600mm internal cutlery drawers  
(600mm drawer shown)

- **DRWTACC5**  
Universal combined width 300mm  
Includes: Cutlery Tray & Roll Dispenser  
(600mm drawer only)







Top Drawer Timber Accessory Systems for Atira Drawer Box  
(Not available with EKO Timber drawer boxes)  
For use with 500-600mm internal cutlery drawers  
(600mm drawer shown)





- **DRWTACC6**  
Universal combined width 300mm  
Includes: Cutlery Tray & Spice Rack  
(600mm drawer only)

# DRAWER INTERNALS

## TIMBER DRAWER SETS (FOR 800mm, 900mm & 1000mm ATIRA METAL DRAWER BOXES ONLY)





		WIDTH	CODE
	Top Drawer Timber Accessory Systems for Atira Drawer Box (Not available with EKO Timber drawer boxes) For use with 800-1000mm internal cutlery drawers (1000mm drawer shown)	-	<b>DRWTACC7</b> Universal combine width 610mm Includes: Cutlery Tray, Roll Dispenser & Knife Block
	Top Drawer Timber Accessory Systems for Atira Drawer Box (Not available with EKO Timber drawer boxes) For use with 800-1000mm internal cutlery drawers (1000mm drawer shown)	-	<b>DRWTACC8</b> Universal combine width 570mm Includes: Cutlery Tray, Knife Block & Slideable Tray
	Top Drawer Timber Accessory Systems for Atira Drawer Box (Not available with EKO Timber drawer boxes) For use with 800-1000mm internal cutlery drawers (1000mm drawer shown)	-	<b>DRWTACC9</b> Universal combine width 770mm Includes: x2 Cutlery Trays & Spice Rack
	Top Drawer Timber Accessory Systems for Atira Drawer Box (Not available with EKO Timber drawer boxes) For use with 800-1000mm internal cutlery drawers (1000mm drawer shown)	-	<b>DRWTACC10</b> Universal combine width 770mm Includes: x2 Cutlery Trays & Knife Block
	Top Drawer Timber Accessory Systems for Atira Drawer Box (Not available with EKO Timber drawer boxes) For use with 800-1000mm internal cutlery drawers (1000mm drawer shown)	-	<b>DRWTACC11</b> Universal combine width 770mm Includes: x2 Cutlery Trays & Roll Dispenser
	Top Drawer Timber Accessory Systems for Atira Drawer Box (Not available with EKO Timber drawer boxes) For use with 800-1000mm internal cutlery drawers (1000mm drawer shown)	-	<b>DRWTACC12</b> Universal combine width 410mm Includes: Roll Dispenser, Slideable Tray & Knife Block
	Top Drawer Timber Accessory Systems for Atira Drawer Box (Not available with EKO Timber drawer boxes) For use with 800-1000mm internal cutlery drawers (1000mm drawer shown)	-	<b>DRWTACC13</b> Universal combine width 410mm Includes: Spice Rack, Slideable Tray & Knife Block
	Top Drawer Timber Accessory Systems for Atira Drawer Box (Not available with EKO Timber drawer boxes) For use with 800-1000mm internal cutlery drawers (1000mm drawer shown)	-	<b>DRWTACC14</b> Universal combine width 410mm Includes: Spice Rack, Slideable Tray & Roll Dispenser

# DRAWER INTERNALS

DRAWER INTERNALS		CABINET SIZE	CODE
	Aluminium Pan Drawer Organisers for Atira Drawer Box (Not available in New England or with EKO Timber drawer boxes)	500mm	<b>DW47ORG5</b>
		600mm	<b>DW47ORG6</b>
		800mm	<b>DW47ORG8</b>
		900mm	<b>DW47ORG9</b>
		1000mm	<b>DW47ORG10</b>
	Org Flag Pan Drawer Management for Atira Drawer Box Supplied with Silver Matt and Anthracite flags only (Not available with New England or with EKO Timber drawer boxes)	500mm	<b>ORGAFLAG5</b>
		600mm	<b>ORGAFLAG6</b>
		800mm	<b>ORGAFLAG8</b>
		900mm	<b>ORGAFLAG9</b>
		1000mm	<b>ORGAFLAG10</b>
	Timber Plate Stack for Atira Drawer Box (276mm deep drawers only) Allow 4 weeks for delivery (Not compatible with New England or EKO timber drawer box)	500mm	<b>PDPLATESTK5</b>
		Includes: 8 x Wooden Dowels, 1 x Base Board	
		600mm	<b>PDPLATESTK6</b>
		Includes: 8 x Wooden Dowels, 1 x Base Board	
		800mm	<b>PDPLATESTK8</b>
		Includes: 8 x Wooden Dowels, 1 x Base Board	
	Timber Plate Stack for EKO Timber Drawer Box (276mm deep drawers only) Allow 4 weeks for delivery (Not compatible with New England or Atira drawer box)	900mm	<b>PDPLATESTK9</b>
		Includes: 8 x Wooden Dowels, 1 x Base Board	
		1000mm	<b>PDPLATESTK10</b>
		Includes: 10 x Wooden Dowels, 1 x Base Board	
		500mm	<b>PDPLATESTK5T</b>
		Includes: 8 x Wooden Dowels, 1 x Base Board	
		600mm	<b>PDPLATESTK6T</b>
		Includes: 8 x Wooden Dowels, 1 x Base Board	
		800mm	<b>PDPLATESTK8T</b>
		Includes: 8 x Wooden Dowels, 1 x Base Board	
		900mm	<b>PDPLATESTK9T</b>
		Includes: 8 x Wooden Dowels, 1 x Base Board	
		1000mm	<b>PDPLATESTK11T</b>
		Includes: 10 x Wooden Dowels, 1 x Base Board	



# ACCESSORIES

ACCESSORIES		SPEC	CODE
	Tea Tray (Pack of 2)	Oak	TEATRAY2
	Sink Cabinet Liners	500mm	SU5LINER
	Corner Cabinet Sink Liners Handing required	600mm	SU6LINER
		800mm	SU8LINER
		900mm	SU9LINER
		1000mm	SU10LINER
		1200mm	SU12LINER
	Shelf Brackets (Pack of 1)	800mm (For use with 800 corner with 300 or 500 door only)	SULINER835U
		1000mm (For use with 1000 corner with 400 or 600 door only)	SULINER1046U
		1200mm (For use with 1200 corner with 300 or 400 door only)	SULINER1234U
		1200mm (For use with 1200 corner with x2 400 doors)	SULINER1244U
	Hob Shields Recommended for use in full height base cabinets and pan drawers cabinets that are used underneath a hob	600mm	HOBSHIELD6
		800mm	HOBSHIELD8
		900mm	HOBSHIELD9
		1000mm	HOBSHIELD10

# WASTE DISPOSAL


WASTE DISPOSAL (Not compatible with New England)		W	D	H	CODE
	Tandem Eco Bin Comes with x3 10L bins (300mm unit min) Hinged door only	262mm	480mm	422mm	<b>ECOBIN3X10</b>
	Triple Eco Bin Comes with x1 20L & x2 10L bins (400mm unit min) Hinged door only	340mm	480mm	422mm	<b>ECOBIN4</b>
	Under Sink Waste Bin Comes with x1 18L & x2 8.5L bins (400mm unit min) Hinged door only A reduced height sink waste is also available for use with this waste bin (POPUPSAVER)	346mm	480mm	326mm	<b>BIN435L</b>
	Premium Waste Bin Comes with x2 32L bins (500mm unit) Option of hinged or pull out (For pull out version, frontal, cabinet and bin need to be ordered separately)	–	476mm	570mm	<b>BIN564L</b>
	Premium Waste Bin Comes with x2 32L bins & x1 21L bins (600mm unit) Option of hinged or pull out (For pull out version, frontal, cabinet and bin need to be ordered separately)	–	476mm	570mm	<b>BIN685L</b>
	60Litre Recycle Bin Comes with x1 34L & x2 17L - 540mm deep (600mm unit) Option of hinged or pull out (For pull out version, frontal, cabinet and bin need to be ordered separately)	530mm	492mm	525mm	<b>ECOBIN60L</b>
	Delux Chrome Swing Bin Comes with x1 12L bin (400mm unit min) Hinged door only	360mm	304mm	385mm	<b>SWINGBINCH</b>
	Triple Recycling Bin Comes with x1 19L, x1 12L & x1 9L bins (500mm or 600mm unit) Hinged door only	–	450mm	525mm	<b>RECYCLEBIN</b>

## HI-DEFINITION LED LIGHTS & ACCESSORIES

### EXAMPLE 1




HD Driver 24v/15w  
**LEDHDTFORM6**  
Six connections.  
Connected lights must  
not exceed driver  
wattage (15w)



TrioTone Under  
Cabinet Light  
**LEDSURFTRIO** 1.65w



HD Square Light  
Cool **LEDSQSURFHD** 1.25w  
Warm **LEDSQSURFHDWW** 1.25w



HD Delta Light  
Cool **LEDELTAHD** 1.65w  
Warm **LEDELTAHDWW** 1.65w



TrioTone Triangle Light  
**DELTATRIO** 1.65w



LED SLS Quadra Under Cabinet Light  
Cool **LEDUCABSLSCCW** 2.5w  
Warm **LEDUCABSLSCWW** 2.5w




# LIGHTING

## HI-DEFINITION LED LIGHTS & ACCESSORIES

### EXAMPLE 2




HD Driver 24v/15w  
**LEDHDTFORM6**  
Six connections.  
Connected lights must  
not exceed driver  
wattage (15w)



HD Delta Light with Touch Sensor  
Cool **LEDELTAHDS** 2.15w  
Warm **LEDELTAHDSWW** 2.15w



HD Delta Light  
Cool **LEDELTAHD** 1.65w  
Warm **LEDELTAHDWW** 1.65w




## HI-DEFINITION LED LIGHTS & ACCESSORIES

### EXAMPLE 3




HD Driver 24v/15w  
**LEDHDTFORM6**  
Six connections.  
Connected lights must  
not exceed driver  
wattage (15w)



TrioTone Under  
Cabinet Light  
**LEDSURFTRIO** 1.65w



HD Square Light  
Cool **LEDSQSURFHD** 1.25w  
Warm **LEDSQSURFHDDWW** 1.25w



HD Delta Light  
Cool **LEDDELTAHD** 1.65w  
Warm **LEDDELTAHDWW** 1.65w



TrioTone Triangle Light  
**DELTATRIO** 1.65w






# LIGHTING

## HI-DEFINITION LED LIGHTS & ACCESSORIES

HI-DEFINITION LED LIGHTS & ACCESSORIES		SPEC	CODE
	TrioTone Triangle Light One light fitting with 3 white colour shade settings (Cool, Neutral or Warm) Colour to be selected during installation Order driver separately LEDHDTFORM6	1.65w	<b>DELTATRIO</b>
	HD Square Light Order driver separately LEDHDTFORM6 - includes 2.5m cable	1.25w Cool	<b>LEDSQSURFHD</b>
		1.25w Warm	<b>LEDSQSURFHDWW</b>
	TrioTone Under Cabinet Light One light fitting with 3 white colour shade settings (Cool, Warm and Natural White) Colour to be selected during installation Order driver separately LEDHDTFORM6	1.65w	<b>LEDSURFTRIO</b>
	HD Delta Light with On/Off Touch Sensor Order driver separately LEDHDTFORM6 - includes 2.5m cable	2.15w Cool	<b>LEDELTAHDS</b>
		2.15w Warm	<b>LEDELTHDSWW</b>
	HD Delta Light Order driver separately LEDTFORMER6 - includes 2.5m cable	1.65w Cool	<b>LEDELTAHD</b>
		1.65w Warm	<b>LEDELTAHDWW</b>
	LED SLS Quadra Under Cabinet Light Order driver separately LEDHDTFORM6	2.5w Cool	<b>LEDUCABSLSCW</b>
		2.5w Warm	<b>LEDUCABSLSWW</b>
	HD Driver - 24v Six connections	15w	<b>LEDHDTFORM6</b>


## LED STRIP LIGHTS & ACCESSORIES





LED STRIP LIGHTS & ACCESSORIES		SPEC	CODE
	LED Task Strip Light (240v) Includes 1000mm mains cable and 200mm extension cable Driver not required Each light can be linked directly together, or with the optional link cable LEDSTRIPCON	2.7w - 250mm	<b>LEDSTRIP25</b>
		4.5w - 330mm	<b>LEDSTRIP33</b>
		8w - 550mm	<b>LEDSTRIP55</b>
	500mm Task Strip Light Link Cable	N/A	<b>LEDSTRIPCON</b>

# LIGHTING

## LED STRIP LIGHTS & ACCESSORIES



LED STRIP LIGHTS & ACCESSORIES		SPEC	CODE
	LED DuoFlex Flexible Strip Lights with Remote & Receiver Pack Complete kit to create a single continuous light run with remote control switch x1 2m Light Strip x1 2.5m Connection Cable x1 Receiver x1 Remote (excluding batteries) x1 Driver 24v (Potential to create 2 separate runs, order additional light and cable separately)	7.5w - 2m	<b>DUOFLXRC2P</b>
	LED DuoFlex Flexible Strip Lights - Additional strip lights Must order Inline Switch Pack or Remote & Receiver Pack then add additional strips can be connected together to create required length	3.75w - 1m (x2 500mm) 7.5w - 2m	<b>LEDDUOFLEX1</b> <b>LEDDUOFLEX2</b>
	Driver Connection Cable Connects each strip light to driver when used individually	2.5m	<b>FLEXRGBCON25</b>



LIGHTING & ELECTRICAL ACCESSORIES		SPEC	CODE
	LED Plinth Lights - x4 Lights/1.5m Cable 24v Driver included - maximum allowance of 4w (x22 lights)	1.5w (per light) Cool	<b>LEDSQPLINTCW</b>
		1.5w (per light) Warm	<b>LEDSQPLINTWW</b>
	HD LED InCabinet Strip Lights - 12v Order driver separately POWDRIVE15 (Suitable for pan drawers and single wall cabinets) Not compatible with New England (In-Frame)	3.9w - 300mm	<b>PANLIGHT3</b>
		3.9w - 400mm	<b>PANLIGHT4</b>
		4.3w - 450mm	<b>PANLIGHT45</b>
		5.5w - 500mm	<b>PANLIGHT5</b>
		7.8w - 600mm	<b>PANLIGHT6</b>
		9.1w - 800mm	<b>PANLIGHT8</b>
		9.1w - 900mm	<b>PANLIGHT9</b>
		12.4w - 1000mm	<b>PANLIGHT10</b>
	HD Driver - 12v For use with InCabinet Strip Lights. Connected wattage of lights must not exceed maximum wattage of driver	15w	<b>POWDRIVE15</b>
	ALA Illuminated Shelves Complete with touch LED dimmer switch, night light, memory function and safety function all in one Includes integrated driver	600mm wide shelf	<b>SHELFILU65W</b>
		900mm wide shelf	<b>SHELFILU98W</b>
	Evoline® Pop Up Socket with USB Ports - Premium stainless steel finish lid (Lid sits flush to work surface) Three plug sockets and two USB Ports - includes 2.5m cable	-	<b>POPUPSOCKUSS</b>
	Pop Up Socket with USB Port - Aluminium finish lid (Lid sits proud of the work surface) Three plug sockets and two USB Ports - includes 2.5m cable	-	<b>POPUPSOCKU</b>
	EVOline Back Flip Socket - Stainless steel finish lid Two plug sockets and 1 USB port Includes 3m cable and plug	-	<b>FLIPSOCKUSB</b>

# LIGHTING

All of our lighting is LED, which means it is low energy and inexpensive to run.

Any 240v light can be connected directly to the mains, either individually with the plug supplied or combined into one mains-powered distribution block.



Warm Lighting

Any light which is listed as 24v must be connected to the mains supply through a driver.

Adding up the wattage of the lights. Each driver has a maximum wattage. If the wattage of the lights exceeds the max wattage of the driver you will need a second driver



Cool Lighting


You should also consider where the wires from the driver to the lights will be hidden. You may need to supply extra drivers to prevent trailing wires between two sets of wall units.



## ILLUMINATED WALL CABINETS



The cable from the illuminated panel to the distributor is 3 metres. There is then a short cable (200mm) from the distributor to the driver. The cable from the driver to the mains is 2.2m long.



LED illuminated wall units can be connected in sequence, as long as the combined wattage of all the base panels does not exceed the maximum wattage of the driver (15w).

For example, if the wall unit base panels are all 2.3w, you can plug a maximum of five into the 15w driver. If you tried to plug in a sixth, the driver would fail. Please refer to the table below for the wattage of each size of unit.


UNIT	WATTAGE
300mm	2.3w
400mm	3.6w
450mm	4.2w
500mm	4.6w
600mm	5.9w
800mm	8.1w
900mm	9.4w
1000mm	10.4w

All units are supplied with a 15w driver with connections for up to six lights.

Please note, the 800mm, 900mm and 1000mm illuminated units are available with Bi Fold doors only.

Available on Premium 330mm deep cabinets only.

# LIGHTING



**TASK** lighting is positioned under wall cabinets.

**CONVENIENCE** lighting is placed in drawers and cabinets.

**MOOD** lighting enhances the design of the kitchen when used along the plinth or above the wall cabinets.

- 1 LED In-Cabinet Strip Lights
  - PANLIGHT3 (300mm)
  - PANLIGHT4 (400mm)
  - PANLIGHT45 (450mm)
  - PANLIGHT5 (500mm)
  - PANLIGHT6 (600mm)
  - PANLIGHT8 (800mm)
  - PANLIGHT9 (900mm)
  - PANLIGHT10 (1000mm)














- 2 Illuminated Wall Cabinets
  - 300-600 Single Wall and
  - 500-1000 Bi-Fold and Bridging Cabinets

- 3 LED SLS Quadra under Cabinet Light
  - LEDUCABSLSCW/WW

- 4 LED Plinth Lights
  - 4 Lights/1.5m Cable
  - LEDSOPLINTCW/WW

- 5 Pop Up Socket with USB Port
  - POPUPSOCKU (Aluminium Finish Lid)
  - POPUPSOCKUSS (Stainless Steel Lid - Evoline®)
  - or BACKFLIP Socket

# HANDLES

	DESCRIPTION	CENTRES	CODE
	Matt Nickel Square D Handle	128mm	HPK296
	Gothic D Handle	160mm	HPK346
	Iron D handle	128mm	HPK404
	Bright Chrome Handle	128mm	HPK423
	Satin Nickel Bow Handle	128/224mm	HPK434
	Chrome Swept D Handle	160mm	HPK438
	Stainless Steel T Knob (Not suitable for corner situations, excluding on In-Frame)	Knob	HPK440
	Stainless Steel Cup Handle	64mm	HPK441
	Pewter Effect Beehive Knob (Not suitable for corner situations, excluding on In-Frame)	Knob	HPK442
	Pewter Wave D Handle	128mm	HPK443
	Curve Box Polished Chrome Handle	160mm	HPK445
	Satin Nickel Strap Handle	128/160/192/224mm	HPK447
	Polished Chrome D Handle	160mm	HPK448















# HANDLES

	DESCRIPTION	CENTRES	CODE
	Natural Iron Fluted Knob & Backplate	Knob	HPK464
	Satin Nickel Grooved Bow Handle	160mm	HPK465
	Nickel Arched D Handle	160mm	HPK472
	Square Bar Polished Chrome Handle	96mm	HPK493
		320mm	HPK494
	Pewter Lamont D Handle	96mm	HPK600
	Libra 'Bullet' Handle	32mm	HPK606
		32mm (Pack of 2)	HPK606X2
	Chrome Concave D Handle	192mm	HPK607
		320mm	HPK608
	Vintage Nickel Pewter Handle	160mm	HPK629
	Stainless Steel Barrel D Handle	160mm	HPK630
	Matt Brushed Nickel Arch Handle	160mm	HPK631
	Square Chrome Bar Handle	192mm	HPK634
	Stainless Steel Jupiter Knob	Knob	HPK637
	Pewter Lamont Cup Handle	64mm	HPK638

# HANDLES

	DESCRIPTION	CENTRES	CODE
	Polished Chrome Chunky Bridge Handle	160mm	HPK640
	Chrome Square D Handle	128mm	HPK642
	Brushed Nickel Bow Handle	160mm	HPK643
	Matt Nickel Square D Handle	160mm	HPK644
	Modern Bright Chrome Bridge Handle	320mm	HPK649
	Satin Nickel Bridge Handle	320mm	HPK721
	Modern Bright Chrome Bridge Handle	128mm	HPK650
	Satin Nickel Bridge Handle	128mm	HPK720
	Modern Nickel Handle	160mm	HPK651
	Eight by Eight Nickel Handle	160mm	HPK652
	Grooved Pewter D Handle	128mm	HPK672
	Chrome Satin & Nickel Handle	160mm	HPK674
	Rialto Stainless Steel Handle	160mm	HPK712
	Brushed Nickel Angle Bridge Handle	160mm	HPK714
	Smoked Oak Yo-yo Knob	Knob	HPK718
	Oil Rubbed Bronze Knob	Knob	HPK723

# HANDLES

	DESCRIPTION	CENTRES	CODE
	Brushed Brass Knob	Knob	HPK724
	Vintage Matt Black & Copper Bar Handle	160mm	HPK727
	Graphite Osaka Pull Handle	96mm	HPK728
	Graphite Osaka Pull Handle	160mm	HPK729
	Graphite Osaka Pull Handle	320mm	HPK730
	Copper Osaka Pull Handle	96mm	HPK731
	Copper Osaka Pull Handle	160mm	HPK732
	Copper Osaka Pull Handle	320mm	HPK733
	Patterned Gunmetal Bar Handle	160mm	HPK734
		320mm	HPK735
	Burbridge Brushed Brass D Handle	128mm	HPK736
	Aged Brass Effect Knob	Knob	HPK739
	Aged Brass Effect Cup Handle	64mm	HPK750
	Aged Copper Sulky D Handle	128mm	HPK751
	Traditional Chrome D Handle	128mm	HPK752




# HANDLES

	DESCRIPTION	CENTRES	CODE
	Aged Brass Effect D Handle	128mm	HPK753
	Antique Copper D Handle	160mm	HPK754
	Traditional Antique Copper Knob	Knob	HPK784
	Traditional Antique Copper D Handle	128mm	HPK785

Inline Aluminium Trim




Inline Matt Black Trim



Inline Chrome Wave Trim



Wall Cabinet Inset Handle



# FRONTALS

	SPEC	CODE
720mm Wall/Full Height Frontals (KDRFH15 not available in Newport).	150 (W)	KDRFH15
	255 (W)	KDRFH25
	300 (W)	KDRFH3
	400 (W)	KDRFH4
	450 (W)	KDRFH45
	500 (W)	KDRFH5
	600 (W)	KDRFH6
Joined Frame and Door Frame and Frontal. 800, 900 and 1000 widths, two doors and one frame supplied Available in New England only	800 (W)	KDRFH8
	900 (W)	KDRFH9
	1000 (W)	KDRFH10
720mm Convex Curved Frontals Only available in Alta Gloss, Alta PTO, Ashbourne, Ashbourne PTO, Austin, Austin PTO, Cranbrook, New England PTO, New York Gloss, New York PTO, Oakham, Wexford and Woodbury	285 (W) Solid curve	KDRWWECU372
	274 (W) Flat base	KDRBWE372
Concave Curved Base Unit Available in Alta Gloss, Austin PTO, New England PTO, New York Gloss and New York PTO only	630mm	KDRCOBU3
Concave Curved Wall Unit Available in Alta Gloss, Austin PTO, New England PTO, New York Gloss and New York PTO only	330mm	KDRCOWU3
900mm Tall Wall Frontals KDRW65, KDRW69 and KDRW610 available in New England only (Includes Frame and x2 Doors).	250 (W)	KDRW625
	300 (W)	KDRW63
	400 (W)	KDRW64
	450 (W)	KDRW645
	500 (W)	KDRW65
	600 (W)	KDRW66
	800 (W)	KDRW68
	900 (W)	KDRW69
560mm Drawer Line/Low Wall Frontals Not available in New England	1000 (W)	KDRW610
	300 (W)	KDRDL3
	400 (W)	KDRDL4
	450 (W)	KDRDL45
	500 (W)	KDRDL5
159mm Drawer Frontals Not available in New England	600 (W)	KDRDL6
	300 (W)	KDWDF3
	400 (W)	KDWDF4
	450 (W)	KDWDF45
	500 (W)	KDWDF5
	600 (W)	KDWDF6
	800 (W)	KDWDF8
	900 (W)	KDWDF9
560mm Drawer Line Frontals 159mm Drawer Frontals/Frames Complete New England Frame and Frontal (800, 900 and 1000 widths two doors, two drawer fronts and one frame supplied)	1000 (W)	KDWDF10
	300 (W)	KDRDF3
	400 (W)	KDRDF4
	450 (W)	KDRDF45
	500 (W)	KDRDF5
	600 (W)	KDRDF6
	800 (W)	KDRDF8
	900 (W)	KDRDF9
3 Pan Drawer Unit Frontal Not available in New England	1000 (W)	KDRDF10
	500 (W) 276 (H)	KDWDPF5
	600 (W) 276 (H)	KDWDPF3
	800 (W) 276 (H)	KDWDPF83
	900 (W) 276 (H)	KDWDPF93
3 Pan Drawer Unit Frontals 159mm Drawer Line Frontal/ 276mm Drawer Frontals/Frames Complete New England	1000 (W) 276 (H)	KDWDPF103
	500 (W)	KDW3DPF5
	600 (W)	KDW3DPF6
	800 (W)	KDW3DPF8
	900 (W)	KDW3DPF9
	1000 (W)	KDW3DPF10

# FRONTALS

	SPEC	CODE
2 Pan Drawer Unit and Bi-fold Unit Bottom Frontals Not available in New England KDROCH1036B available in Contemporary and Inline ranges only	500 (W) 358 (H)	<b>KDROCH536B</b>
	600 (W) 358 (H)	<b>KDROCH636B</b>
	800 (W) 358 (H)	<b>KDROCH836B</b>
	900 (W) 358 (H)	<b>KDROCH936B</b>
	1000 (W) 358 (H)	<b>KDROCH1036B</b>
2 Pan Drawer Unit Frontals 358mm Drawer Frontals/Frames Complete New England	600 (W)	<b>KDW2DPF3</b>
	800 (W)	<b>KDW2DPF8</b>
	900 (W)	<b>KDW2DPF9</b>
	1000 (W)	<b>KDW2DPF10</b>
Multi Drawer Pack (4 fronts) (Includes Frame with New England) KDWM6 available in New England For other ranges order x1 KDWDF6 and x3 KDWPF6	400 (W) 159/183 (H)	<b>KDWMD4</b>
	500 (W) 159/183 (H)	<b>KDWMD5</b>
	600 (W) 159/183 (H)	<b>KDWMD6</b>
	600 (W) 159 (H)	<b>KDWDF6</b>
	600 (W) 183 (H)	<b>KDWPF6</b>
Tall Larder, Appliance and Fridge Housing Doors New England only Joined Frame and Door	300 (W) 720 (H)	<b>KDRFHLU3</b>
	500 (W) 720 (H)	<b>KDRFHLU5</b>
	600 (W) 720 (H)	<b>KDRFHLU6</b>
	300 (W) 900 (H)	<b>KDRWLU63</b>
	500 (W) 900 (H)	<b>KDRWLU65</b>
Tall Larder, Appliance and Fridge Housing Doors Joined Frame and Door for New England KFAAHBH and KFAAH7H available in New York only (supplied with J section)	300 (W) 1228 (H)	<b>KDRLU3</b>
	500 (W) 1228 (H)	<b>KDRLU5</b>
	600 (W) 1228 (H)	<b>KDRIF612</b>
	600 (W) 1106 (H)	<b>KDRIF611</b>
	600 (W) 1018 (H)	<b>KDRIF610</b>
	600 (W) 930 (H)	<b>KDRIF609</b>
	600 (W) 720 (H)	<b>KDRFH6</b>
	600 (W) 560 (H)	<b>KDRDL6</b>
	600 (W) 450 (H)	<b>KDRAH</b>
	600 (W) 296 (H)	<b>KDWDPF6</b>
	600 (W) 120 (H)	<b>KFAAHB</b>
	600 (W) 120 (H)	<b>KFAAHBH</b>
	600 (W) 72 (H)	<b>KFAAH7</b>
	600 (W) 72 (H)	<b>KFAAH7H</b>
	600 (W) 47 (H)	<b>KFAAH4</b>
Belfast Sink Frontals 600mm available in Classic ranges only 900mm available in Ashbourne, Ashbourne PTO, Austin, Austin PTO, Cranbrook, New England PTO and Wexford only	600 (W) 450 (H)	<b>KDRAH</b>
	600 (W) 47 (H)	<b>KFAAH4</b>
	450 (W) 450 (H)	<b>KDRBSU45</b>
	900 (W) 47 (H)	<b>KFAAH49</b>
Bridging Unit Frontal Joined Frame and Door for New England	600 (W) 296 (H)	<b>KDROCH63</b>
	1000 (W) 276(H)	<b>KDROCH1028</b>
Bi-fold Top Door and Bridging Unit Not available in New England KDROCH1036T available in Contemporary and Inline ranges only	500 (W) 358 (H)	<b>KDROCH536T</b>
	600 (W) 358 (H)	<b>KDROCH636T</b>
	800 (W) 358 (H)	<b>KDROCH836T</b>
	900 (W) 358 (H)	<b>KDROCH936T</b>
	1000 (W) 358 (H)	<b>KDROCH1036T</b>
Bridging Door Available in New England Joined Frame and Door only	500 (W) 358 (H)	<b>KDROCH536</b>
	600 (W) 358 (H)	<b>KDROCH636</b>
	800 (W) 358 (H)	<b>KDROCH836</b>
	900 (W) 358 (H)	<b>KDROCH936</b>
	1000 (W) 358 (H)	<b>KDROCH1036</b>
Ranged Glazed Unit Frontals See pages 08-17 for glazed unit availability	400 (W) 720 (H)	<b>KDRGW3</b>
	500 (W) 720 (H)	<b>KDRGW2</b>
	500 (W) 900 (H)	<b>KDRGW6</b>
	500 (W) 1025 (H)	<b>KDRWD2</b>
720mm (H) Diagonal and L Shape Corner Wall Unit Frontal (For 330mm Deep Premium Cabinet Only)	255mm	<b>KDRFH25</b>
	355mm	<b>KDRFH35</b>
	390mm	<b>KDRDWU24</b>
900mm (H) L Shape Corner Wall Unit Frontal (For 330mm Deep Premium Cabinet Only)	255mm	<b>KDRW625</b>

# FRONTALS

CONVEX BASE UNIT PLINTH	SPEC	CODE
(to suit BWE372CU) Available in ranges Alta Gloss, Alta PTO, Ashbourne, Ashbourne PTO, Austin, Austin PTO, Cranbrook, New England PTO, New York Gloss, New York PTO, Oakham, Wexford and Woodbury PTO	300mm	<b>PLINTHCU63V</b>
	300mm	<b>PLINTCU63PTO</b>
	(Paint to Order)	
CONCAVE BASE UNIT PLINTH	SPEC	CODE
(to suit COB991PCF) Available in ranges Alta Gloss, Austin PTO, New England PTO, New York Gloss and New York PTO only	300mm	<b>PLINTHCO</b>
	300mm	<b>PLINTHCOPTO</b>
	(Paint to Order)	

# CABINETS ONLY

BASE UNITS/SINK UNIT CABINETS ONLY	SPEC	CABINET
150mm Reduced Depth Base Unit (Add 'F' if Full Height Cabinet Required)	870 (H) 285 (D)	<b>BUC1503</b>
255mm Reduced Depth Base Unit (Add 'F' if Full Height Cabinet Required)	870 (H) 285 (D)	<b>BUC253</b>
300mm Reduced Depth Base Unit (Add 'F' if Full Height Cabinet Required)	870 (H) 285 (D)	<b>BUC33</b>
400mm Reduced Depth Base Unit (Add 'F' if Full Height Cabinet Required)	870 (H) 285 (D)	<b>BUC43</b>
450mm Reduced Depth Base Unit (Add 'F' if Full Height Cabinet Required)	870 (H) 285 (D)	<b>BUC453</b>
500mm Reduced Depth Base Unit (Add 'F' if Full Height Cabinet Required)	870 (H) 285 (D)	<b>BUC53</b>
600mm Reduced Depth Base Unit (Add 'F' if Full Height Cabinet Required)	870 (H) 285 (D)	<b>BUC63</b>
150mm Base Unit (Add 'F' if Full Height Cabinet Required)	870 (H) 570 (D)	<b>BUC1506</b>
255mm Base Unit (Add 'F' if Full Height Cabinet Required)	870 (H) 570 (D)	<b>BUC256</b>
300mm Base Unit (Add 'F' if Full Height Cabinet Required)	870 (H) 570 (D)	<b>BUC36</b>
400mm Base Unit (Add 'F' if Full Height Cabinet Required)	870 (H) 570 (D)	<b>BUC46</b>
450mm Base Unit (Add 'F' if Full Height Cabinet Required)	870 (H) 570 (D)	<b>BUC456</b>
500mm Base/Sink Unit (Add 'F' if Full Height Cabinet Required)	870 (H) 570 (D)	<b>BUC56</b>
600mm Base/Sink Unit (Add 'F' if Full Height Cabinet Required)	870 (H) 570 (D)	<b>BUC66</b>
800mm Base/sink Unit (Add 'F' if Full Height Cabinet Required)	870 (H) 570 (D)	<b>BUC86</b>
900mm Base/Sink Unit (Add 'F' if Full Height Cabinet Required)	870 (H) 570 (D)	<b>BUC96</b>
1000mm Base/Sink Unit (Add 'F' if Full Height Cabinet Required)	870 (H) 570 (D)	<b>BUC106</b>
1200mm Base/Sink Unit (Add 'F' if Full Height Cabinet Required)	870 (H) 570 (D)	<b>BUC126</b>
800mm Corner Base Unit (Add 'F' if Full Height Cabinet Required)	870 (H) 570 (D)	<b>CBC86A</b>
900mm Corner Base Unit (Add 'F' if Full Height Cabinet Required)	870 (H) 570 (D)	<b>CBC96A</b>
1000mm Corner Base Unit (Add 'F' if Full Height Cabinet Required)	870 (H) 570 (D)	<b>CBC106A</b>
1200mm Corner Base Unit (Add 'F' if Full Height Cabinet Required)	870 (H) 570 (D)	<b>CBC126A</b>
1 Piece L'Shape Corner Base Unit 930 x 930 - Excludes Side Panels	870 (H) 570 (D)	<b>LCBC991PC18</b>
1 Piece L'Shape Corner Base Unit 1030 x 1030 - Excludes Side Panels	870 (H) 570 (D)	<b>LCBC101PC18</b>
1 Piece L'Shape Corner Base Unit - Sides only	-	<b>DBUCA18</b>
Concave Base Unit	870 (H) 570 (D)	<b>COBC991PC18</b>
Curved Base End Unit	870 (H) 570 (D)	<b>BWEC372CU</b>
45 Degree Base End Unit	870 (H) 570 (D)	<b>KDBUC3645</b>
600mm Belfast Sink Unit	870 (H) 570 (D)	<b>BSUC66</b>
900mm Belfast Sink Unit	870 (H) 570 (D)	<b>BSUC96</b>

CORNER POSTS	SPEC	CABINET
Base Corner Post	720 (H)	<b>LPOSTCBU18F</b>
Flexible Base Corner Post x2 FPK345 (Fitting Packs) required	42 (W) 720 (H) 146 (W) 720 (H)	<b>CPOSTBUFL72</b> <b>CPOSTFL1572</b>
Wall Corner Post	720 (H) 900 (H)	<b>LPOSTWU7218F</b> <b>LPOSTWU9018F</b>
Flexible Wall Corner Post x2 FPK345 (Fitting Packs) required	27 (W) 720 (H) 146 (W) 720 (H)	<b>CPOSTWUFL72</b> <b>CPOSTFL1572</b>

DRAWER LINE UNITS CABINETS ONLY (EXCLUDES DRAWER BOX)	SPEC	CABINET
400mm 4 Drawer Base Unit	870 (H) 570 (D)	<b>DUC46</b>
500mm 4 Drawer Base Unit	870 (H) 570 (D)	<b>DUC56</b>
600mm 4 Drawer Base Unit	870 (H) 570 (D)	<b>DUC66</b>
500mm 3 Drawer Base Unit	870 (H) 570 (D)	<b>PDC56</b>
600mm 3 Drawer Base Unit	870 (H) 570 (D)	<b>PDC66</b>
800mm 3 Drawer Base/Sink Unit	870 (H) 570 (D)	<b>PDC86</b>
900mm 3 Drawer Base Unit	870 (H) 570 (D)	<b>PDC96</b>
1000mm 3 Drawer Base/Sink Unit	870 (H) 570 (D)	<b>PDC106</b>
500mm 2 Drawer Base Unit	870 (H) 570 (D)	<b>PDC56D2</b>
600mm 2 Drawer Base Unit	870 (H) 570 (D)	<b>PDC66D2</b>
800mm 2 Drawer Base/Sink Unit	870 (H) 570 (D)	<b>PDC86D2</b>
900mm 2 Drawer Base/Sink Unit	870 (H) 570 (D)	<b>PDC96D2</b>
1000mm 2 Drawer Base Unit	870 (H) 570 (D)	<b>PDC106D2</b>

# CABINETS ONLY

BUILT UNDER OVEN HOUSING CABINETS ONLY	SPEC	CABINET
600mm Built Under Oven Housing	-	<b>BOHC66</b>
600mm Built Under Oven Housing with Drawer	-	<b>BOHC6618D</b>
600mm Microwave Built Under Housing	-	<b>MBOHC66</b>

LARDER/OVEN/FRIDGE FREEZER/PANTRY UNIT (2100mm HIGH) CABINETS ONLY	SPEC	CABINET 1 (SIDES)	CABINET 2 (INTERNALS)
300mm Larder Unit	570 (D)	<b>LUC36</b>	<b>N/A</b>
500mm Larder Unit	570 (D)	<b>LUC56</b>	<b>N/A</b>
600mm Larder Unit	570 (D)	<b>LUC66</b>	<b>N/A</b>
1000mm Corner Larder	570 (D)	<b>CNLUC106</b>	<b>N/A</b>
600mm Pantry Unit - with 2 Drawers	570 (D)	<b>PUC6621D2</b>	<b>N/A</b>
600mm Pantry Unit - with 3 Drawers	570 (D)	<b>PUC6621D3</b>	<b>N/A</b>
600mm Pantry Unit - with 4 Drawers	570 (D)	<b>PUC6621D4</b>	<b>N/A</b>
1000mm Pantry Unit	570 (D)	<b>PUC106</b>	<b>N/A</b>
600mm Oven Housing (all styles)	570 (D)	<b>OHCA18</b>	<b>OHCB18</b>
600mm Integrated Housings (all styles)	570 (D)	<b>IFCA18</b>	<b>IFCB18</b>
600mm Oven Housing Fascia Cap	-	<b>OHUCAP6</b>	<b>N/A</b>

TALL LARDER/OVEN /FRIDGE FREEZER UNIT (2276mm HIGH) CABINETS ONLY	SPEC	CABINET 1	CABINET 2 (INTERNALS)	CABINET 3 (SHELVES)
300mm Larder Unit	570 (D)	<b>LUC3623</b>	<b>N/A</b>	<b>N/A</b>
500mm Larder Unit	570 (D)	<b>LUC5623</b>	<b>N/A</b>	<b>N/A</b>
600mm Larder Unit	570 (D)	<b>LUC6623</b>	<b>N/A</b>	<b>N/A</b>
1000mm Corner Larder	570 (D)	<b>CNLUC1023</b>	<b>N/A</b>	<b>N/A</b>
1000mm Pantry Unit	570 (D)	<b>PUC10623</b>	<b>N/A</b>	<b>N/A</b>
600mm Oven Housing (all styles)	570 (D)	<b>OHUC23A18</b>	<b>OHCB18</b>	<b>OHCC18</b>
600mm Integrated Housings (all styles)	570 (D)	<b>IFHC23A18</b>	<b>IFCB18</b>	<b>IFHC23C18</b>
600mm Oven Housing Fascia Cap	-	<b>OHUCAP6</b>	<b>N/A</b>	<b>N/A</b>

MID-HEIGHT LARDER /OVEN/FRIDGE FREEZER UNIT (1381mm HIGH) CABINETS ONLY	SPEC	CABINET
600mm 4 Drawer Unit	-	<b>PDC664</b>
600mm Single Oven Housing	-	<b>SOHC6613</b>
600mm Single Oven/Microwave Housing	-	<b>SOHC6613A</b>
600mm Double Oven Housing	-	<b>DOHC6613</b>
600mm Fridge Housing	-	<b>AHC6613</b>
600mm Microwave Oven Housing	-	<b>MOHC6613D3</b>
500mm Larder Unit	-	<b>LUC5613</b>
600mm Larder Unit	-	<b>LUC6613</b>
600mm Oven Housing Fascia Cap	-	<b>OHUCAP6</b>

# CABINETS ONLY

<b>LOW WALL UNITS (561mm HIGH) CABINETS ONLY</b>	<b>SPEC</b>	<b>CABINET</b>
300mm Wall Unit	330 (D) Premium	<b>WUC356P</b>
400mm Wall Unit	330 (D) Premium	<b>WUC456P</b>
450mm Wall Unit	330 (D) Premium	<b>WUC4556P</b>
500mm Wall Unit	330 (D) Premium	<b>WUC556P</b>
600mm Wall Unit	330 (D) Premium	<b>WUC656P</b>
800mm Wall Unit	330 (D) Premium	<b>WUC856P</b>
900mm Wall Unit	330 (D) Premium	<b>WUC956P</b>
1000mm Wall Unit	330 (D) Premium	<b>WUC1056P</b>

<b>STANDARD WALL UNITS (724mm HIGH) CABINETS ONLY</b>	<b>SPEC</b>	<b>CABINET</b>
150mm Wall Unit	330 (D) Premium	<b>WUC15072P</b>
255mm Wall Unit	330 (D) Premium	<b>WUC2572P</b>
300mm Wall Unit	330 (D) Premium	<b>WUC372P</b>
400mm Wall Unit	330 (D) Premium	<b>WUC472P</b>
450mm Wall Unit	330 (D) Premium	<b>WUC4572P</b>
500mm Wall Unit	330 (D) Premium	<b>WUC572P</b>
600mm Wall Unit	330 (D) Premium	<b>WUC672P</b>
800mm Wall Unit	330 (D) Premium	<b>WUC872P</b>
900mm Wall Unit	330 (D) Premium	<b>WUC972P</b>
1000mm Wall Unit	330 (D) Premium	<b>WUC1072P</b>
500mm Bi-Fold Wall Unit	330 (D) Premium	<b>HFWUC572P</b>
600mm Bi-Fold Wall Unit	330 (D) Premium	<b>HFWUC672P</b>
800mm Bi-Fold Wall Unit	330 (D) Premium	<b>HFWUC872P</b>
900mm Bi-Fold Wall Unit	330 (D) Premium	<b>HFWUC972P</b>
1000mm Bi-Fold Wall Unit	330 (D) Premium	<b>HFWUC1072P</b>
Corner Wall Unit	330 (D) Premium	<b>CWUC672P</b>
Diagonal Corner Wall Unit	330 (D) Premium	<b>DWUC4572P</b>
45° Wall End Unit	330 (D) Premium	<b>WUC372145P</b>
L'Shape Corner Wall Unit 630 x 630	330 (D) Premium	<b>LCWUC672P</b>
L'Shape Corner Wall Unit 730 x 730	330 (D) Premium	<b>LCWUC772P</b>

<b>STANDARD WALL UNITS (724mm HIGH) CABINETS ONLY</b>	<b>SPEC</b>	<b>CABINET</b>
Concave Wall Unit	330 (D) Premium	<b>COCWUC67218P</b>
Curved Wall End Unit	330 (D) Premium	<b>WWEC372CUP</b>
600mm Microwave Wall Unit	330 (D)	<b>MWUC672</b>
400mm Glazed Wall Unit	330 (D) Premium	<b>GDUC472P</b>
500mm Glazed Wall Unit	330 (D) Premium	<b>GDUC572P</b>
400mm Glazed Wall Unit - Paint to Order (Only available in Ashbourne PTO, Austin PTO, New England PTO and Wexford PTO)	330 (D) Premium	<b>GDUC472PPTO</b>
500mm Glazed Wall Unit - Paint to Order (Only available in Ashbourne PTO, Austin PTO, New England PTO and Wexford PTO)	330 (D) Premium	<b>GDUC572PPTO</b>

# CABINETS ONLY

<b>TALL WALL UNITS (900mm HIGH) CABINETS ONLY</b>	<b>SPEC</b>	<b>CABINET</b>
255mm Wall Unit	330 (D) Premium	<b>WUC2590P</b>
300mm Wall Unit	330 (D) Premium	<b>WUC390P</b>
400mm Wall Unit	330 (D) Premium	<b>WUC490P</b>
450mm Wall Unit	330 (D) Premium	<b>WUC4590P</b>
500mm Wall Unit	330 (D) Premium	<b>WUC590P</b>
600mm Wall Unit	330 (D) Premium	<b>WUC690P</b>
800mm Wall Unit	330 (D) Premium	<b>WUC890P</b>
900mm Wall Unit	330 (D) Premium	<b>WUC990P</b>
1000mm Wall Unit	330 (D) Premium	<b>WUC1090P</b>
Corner Wall Unit	330 (D) Premium	<b>CWUC690P</b>
Diagonal Corner Wall Unit	330 (D) Premium	<b>DWUC4590P</b>
600mm Microwave Wall Unit	330 (D)	<b>MWUC690</b>
500mm Glazed Wall Unit	330 (D) Premium	<b>GDUC590P</b>
500mm Glazed Wall Unit - Paint to Order (Only available in Ashbourne PTO, Austin PTO, New England PTO and Wexford PTO)	330 (D) Premium	<b>GDUC590PPTO</b>

<b>BRIDGING CUPBOARD CABINETS ONLY</b>	<b>SPEC</b>	<b>CABINET</b>
500mm OCH Unit 360 high	330 (D) Premium	<b>OCHC536P</b>
600mm OCH Unit 360 high	330 (D) Premium	<b>OCHC636P</b>
800mm OCH Unit 360 high	330 (D) Premium	<b>OCHC836P</b>
900mm OCH Unit 360 high	330 (D) Premium	<b>OCHC936P</b>
1000mm OCH Unit 360 high	330 (D) Premium	<b>OCHC1036P</b>
600mm OCH Unit 300 high	330 (D) Premium	<b>OCHC63P</b>
1000mm OCH Unit 280 high	330 (D) Premium	<b>OCHC1028P</b>

<b>DRESSER UNITS (1190mm HIGH) CABINETS ONLY</b>	<b>SPEC</b>	<b>CABINET</b>
500mm Worktop Dresser	330 (D) Premium	<b>WDUC512P</b>
500mm Worktop Dresser - Paint to Order (Ashbourne PTO, Austin PTO, New England PTO and Wexford PTO only)	330 (D) Premium	<b>WDUC512PPTO</b>
10mm Worktop Dresser Spacer Panel	-	<b>WDUSPACER5</b>

<b>DRESSER UNITS (1336mm HIGH) CABINETS ONLY</b>	<b>SPEC</b>	<b>CABINET</b>
500mm Worktop Dresser	330 (D) Premium	<b>WDUC513P</b>
500mm Worktop Dresser - Paint to Order (Ashbourne PTO, Austin PTO, New England PTO and Wexford PTO only)	330 (D) Premium	<b>WDUC513PPTO</b>
10mm Worktop Dresser Spacer Panel	-	<b>WDUSPACER5</b>



# DRAWER BOXES

ATIRA METAL DRAWER BOXES (EXCLUDING NEW ENGLAND)	SPEC	CODE
Full Extension/Soft Close Shallow Drawer Box (H159mm) (includes drawer runners and frontal fixings)	300 (W)	INNO3BOX
	400 (W)	INNO4BOX
	450 (W)	INNO45BOX
	500 (W)	INNO5BOX
	600 (W)	INNO6BOX
	800 (W)	INNO8BOX
	900 (W)	INNO9BOX
	1000 (W)	INNO10BOX
Pan Drawer Box Conversion Kit for 3 Drawer Units (H276mm) (includes glass sides and drawer back) (excludes drawer runners)	500 (W)	PD14CON5PK
	600 (W)	PD14CON6PK
	800 (W)	PD14CON8PK
	900 (W)	PD14CON9PK
	1000 (W)	PD14CON10PK
Pan Drawer Box Conversion Kit for 2 Drawer Units (H358mm) (includes glass sides and drawer back) (excludes drawer runners)	500 (W)	PD17CON5PK
	600 (W)	PD17CON6PK
	800 (W)	PD17CON8PK
	900 (W)	PD17CON9PK
	1000 (W)	PD17CON10PK
Drawer Runners (pack of 2, Left and Right hand supplied)	470 (D)	DS47



ATIRA METAL DRAWER BOXES (NEW ENGLAND ONLY)	SPEC	CODE
Full Extension/Soft Close Shallow Drawer Box (H159mm) (includes drawer runners and frontal fixings)	300 (W)	R3BOX
	400 (W)	R4BOX
	450 (W)	R45BOX
	500 (W)	R5BOX
	600 (W)	R6BOX
	800 (W)	R8BOX
	900 (W)	R9BOX
	1000 (W)	R10BOX
Full Extension/Soft Close Pan Drawer Box (H276mm and H358mm drawers) (includes drawer runners and frontal fixings)	500 (W)	RPD5BOX
	600 (W)	RPD6BOX
	800 (W)	RPD8BOX
	900 (W)	RPD9BOX
	1000 (W)	RPD10BOX
Drawer Runners (pack of 2, Left and Right hand supplied)	470 (D)	DS47
Frontal Fixings	-	GALDRWBAY



TIMBER EKO DRAWER BOXES (EXCLUDING NEW ENGLAND)	SPEC	CODE
Full Extension/Soft Close Shallow Drawer Box (H159mm) (includes drawer runners and frontal fixings)	300 (W)	3BOXT
	400 (W)	4BOXT
	450 (W)	45BOXT
	500 (W)	5BOXT
	600 (W)	6BOXT
	800 (W)	8BOXT
	900 (W)	9BOXT
	1000 (W)	10BOXT
3 Drawer Pan Drawer Boxes (H276mm) (excludes drawer runners and drawer clips)	500 (W)	PD528BOXT
	600 (W)	PD628BOXT
	800 (W)	PD828BOXT
	900 (W)	PD928BOXT
	1000 (W)	PD1028BOXT

# DRAWER BOXES

TIMBER EKO DRAWER BOXES (EXCLUDING NEW ENGLAND)		SPEC	CODE
2 Drawer Pan Drawer Boxes (H358mm) (excludes drawer runners and drawer clips)		500 (W)	PD536BOXT
		600 (W)	PD636BOXT
		800 (W)	PD836BOXT
		900 (W)	PD936BOXT
		1000 (W)	PD1036BOXT
Drawer Runners (pack of 2, Left and Right hand supplied)		470 (D)	DS47
Replacement Drawer Clips		-	TCLIP

TIMBER EKO DRAWER BOXES (NEW ENGLAND ONLY)		SPEC	CODE
Full Extension Soft Close Shallow Drawer Boxes (H159mm) (includes drawer runners and frontal fixings)		300 (W)	IFT3BOX
		400 (W)	IFT4BOX
		450 (W)	IFT45BOX
		500 (W)	IFT5BOX
		600 (W)	IFT6BOX
		800 (W)	IFT8BOX
		900 (W)	IFT9BOX
		1000 (W)	IFT10BOX
Full Extension Soft Close Pan Drawer Boxes (H276mm and H358mm drawers) (includes drawer runners and frontal fixings)		500 (W)	IFTPD5BOX
		600 (W)	IFTPD6BOX
		800 (W)	IFTPD8BOX
		900 (W)	IFTPD9BOX
		1000 (W)	IFTPD10BOX
Drawer Runners (pack of 2, Left and Right hand supplied)		470 (D)	DS47
Replacement Drawer Clips		-	TCLIP

INTERNAL DRAWERS – INCLUDES FRONTAL AND DRAWER RUNNERS		CABINET SIZE	CODE
	Internal Drawer for Cupboards and Larders (Atira) (If using with In-Frame ranges the unit must have joined Frame and Frontals)	300mm	IDWBU3
		400mm	IDWBU4
		450mm	IDWBU45
		500mm	IDWBU5
		600mm	IDWBU6
	Internal Drawer for Cupboards and Larders (EKO Timber) (If using with In-Frame ranges the unit must have joined Frame and Frontals)	300mm	IDWBU3T
		400mm	IDWBU4T
		450mm	IDWBU45T
		500mm	IDWBU5T
		600mm	IDWBU6T

INTERNAL DRAWERS FOR PAN DRAWER UNITS – INCLUDES FRONTAL AND DRAWER RUNNERS		CABINET SIZE	CODE
	Internal Drawer for 2 Pan Drawers (Atira) (Not available in New England)	500mm	IDWPD5
		600mm	IDWPD6
		800mm	IDWPD8
		900mm	IDWPD9
		1000mm	IDWPD10
	Internal Drawer for 2 Pan Drawers (EKO Timber) (Not available in New England)	500mm	IDWPD5T
		600mm	IDWPD6T
		800mm	IDWPD8T
		900mm	IDWPD9T
		1000mm	IDWPD10T

# DRAWER BOXES

INTERNAL DRAWERS FOR PAN DRAWER UNITS – INCLUDES FRONTAL AND DRAWER RUNNERS		CABINET SIZE	CODE
	In-Frame Internal Drawer for 2 Pan Drawers (Atira) (Available in New England only)	500mm	IDWPD5IF
		600mm	IDWPD6IF
		800mm	IDWPD8IF
		900mm	IDWPD9IF
		1000mm	IDWPD10IF
	In-Frame Internal Drawer for 2 Pan Drawers (EKO Timber) (Available in New England only)	500mm	IDWPD5IFT
		600mm	IDWPD6IFT
		800mm	IDWPD8IFT
		900mm	IDWPD9IFT
		1000mm	IDWPD10IFT
INTERNAL DRAWERS FOR CUPBOARDS – EXCLUDES DRAWER RUNNER BOXES		CABINET SIZE	CODE
	Internal Deep Drawer for Cupboards and Larders (Atira) (If using with In-Frame ranges the unit must have joined Frame and Frontals)	300mm	IDDWBU36
		400mm	IDDWBU46
		450mm	IDDWBU456
		500mm	IDDWBU56
		600mm	IDDWBU66
	Internal Deep Drawer for Cupboards and Larders (EKO Timber) (If using with In-Frame ranges the unit must have joined Frame and Frontals)	300mm	IDDWBU36T
		400mm	IDDWBU46T
		450mm	IDDWBU456T
		500mm	IDDWBU56T
		600mm	IDDWBU66T
Drawer Runners (pack of 2, Left and Right hand supplied)		470 (D)	DS47
SPICE DRAWERS		SPEC	CODE
	Spice Drawers Set of 3 for Dresser Cabinets Available with Cabinet Matched MFC frontal only (excluding Paint to Order)	Oak Drawer (Premium Specification only)	SPICE5P
		Paint to Order Oak Drawer (Premium Specification only)	SPICE5PPTO
	Spice Drawers (Single) - For use with 150mm Spice/Wine Rack SPWR15/P Available with Cabinet Matched MFC frontal only (excluding Paint to Order)	Oak Drawer (Premium Specification only)	SPICE15P
		Paint to Order Oak Drawer (Premium Specification only)	SPICE15PPTO
	Spice Drawer Single drawer for Dresser Cabinets only Not compatible with New England	Oak Drawer (Premium Specification only)	SPICE1P

# 18MM CABINET INSTALLATION

## WALL UNITS

Wall units are supplied with wall hanging brackets fitted to the unit. The brackets are adjustable for height and distance from the wall. When fitting the units, attach to the wall the hanging plates and make all adjustments. Remove the unit from the wall and drill through the back and vertical upright as indicated (A). Secure the unit with additional screws to a structural part of the wall. Any screws and other fixings used must be suitable to support units, when loaded, into the material to which they are to be fitted.

Please refer to separate fixing instructions provided in hanging bracket plate pack for further information.

### IMPORTANT


It is the responsibility of the customer:

- \* to ensure that the wall is of a suitable quality and structure to hold the unit fixing in place.
- \* to use the proper hardware fittings for the wall type. Screw must be a minimum of 5mm diameter and rawl plug should be appropriate for the wall used by the bracket.

We recommend two screw lengths:

- \* 60mm length for plasterboard walls with noggins/patresses.
- \* 100mm length for brick and block walls.

- \* Wall fixings not supplied.
- \* All dimensions in mm.



Ensure you have checked wall construction prior to attempt to fix wall bracket. All screws must make a solid fixing in either timber noggins, patress boards or through to wall. If there are no firm fixing points then seek expert advice before fitting the unit, to ensure the walls are able to withstand appropriate strength for use. Under no circumstances should plasterboard fixings be used.



# 18MM CABINET INSTALLATION

## WEIGHT LIMITS OF WALL CABINETS



Please see below the maximum weight limits of wall cabinets. The weights shown below are the maximum load capacity as a result of testing and should not be exceeded.

CABINET WIDTH	RECOMMENDED WEIGHT LIMIT PER CABINET
Single Door Cabinet (150mm – 600mm)	20kg (Approx. 20 bags of 1kg sugar or 50 tins of 400g soup)
Double Door Cabinet (800mm – 1200mm)	30kg (Approx. 30 bags of 1kg sugar or 75 tins of 400g soup)


Please ensure that the weight in wall cabinets is equally distributed and is not exceeded.



**Gallery Standard**



**Gallery Premium**





Determine the location of the unit(s) and mark a horizontal line 2176/2000mm from the floor. Mark the position of each unit. Fit the hanging bracket plates to the wall as illustrated.

# 18MM CABINET INSTALLATION



## BASE UNITS

Brackets are secured to the side panel of the unit and screwed through to the wall. Legs can be adjusted as required.

**Gallery Standard**



**Gallery Premium**



## For the installation of kitchen fitments (in compliance with bs6222 part 4, 1998)

### Delivery and Storage on Site

#### ALWAYS:

- Store units, worktops and other items under cover, in dry conditions, immediately
- Store loose shelves separate from units
- Protect unit fronts
- Cover units during storage to prevent dirt and debris collecting on moving parts such as drawer runners and hinges
- Avoid twisting and distortion
- Store worktops upright or flat, face to face on bearers with the top surface protected against damage

#### NEVER:

- Store units on their sides unless they have soft, grit-free material underneath
- Stack base units more than three high
- Stack wall units more than four high
- Stack frontals against each other or against a wall
- Store units, worktops and other items near direct heat
- Remove tapes from doors or drawers until immediately before fitting

Customers must check units as they are delivered and sign for them as being in good condition. If they are not, the driver's copy of the advice note must be marked accordingly and signed by the customer.

### Installation Methods

Consideration should be given to following trades when allowing access to electrical points, rodding eyes, stop taps, waste traps and any other items or areas where post completion access will be required.

To prevent any accidental damage to the doors and drawers always remove them from the units and store carefully away from the working area. Any sleeving protection should remain on until they are refitted to the units and adjustment has been carried out.

Having checked the plot for level and square, commence by marking a level line on the wall around the base unit area to indicate the finished unit height.

### Fitting Kitchen Units

Units should be packed up or scribed down as little as possible. We recommend a maximum of 6mm packing with firm material where required.

Scribing down should be 10mm maximum, but this depends on any appliances fitting under worktops. Please check manufacturers appliance sizes before scribing down in excess of 10mm.

If ceramic tiles are to be fitted to the floor after the kitchen has been installed, scribing down of the units will be unnecessary.

Should it be necessary to scribe the rear of the units, then this must be as little as possible especially if integrated appliances are to be fitted into tall units or under worktops.

Kitchen base units should be fixed to the wall using the metal cabinet fixing bracket supplied (18mm Excel). The appropriate fixing should be dependent upon the surface being fixed to. It is not necessary to fix through every bracket on a run of units, but fixings either side of an appliance space and on the ends of each run of units must be made.

Tall units (oven housings, larders, etc.) should be level and plumb on all faces and fixed to the wall at four points.

Wall units are to be fixed level and square using hanging brackets if appropriate, or directly to the wall through the back rail where the following number of fixings should be used:

Up to 600mm wide unit	4 fixings
800mm to 1000mm wide unit	5 to 6 fixings
1200mm wide unit	6 fixings

Fixings for standard walls should be 2 1/2"

No. 10 counter sunk screws or longer. Dryline walls (dot and dab) will require longer hollow wall fixings, depending on the thickness of the dab and the type of block work being screwed into. It is essential to use the correct fixings and to check screws match the correct plug size being used.

Units should be screwed together at three positions, preferably hidden from view (e.g. by hinge block, back rail on base units and behind shelf on wall units). All visible screw heads should be capped with colour caps. Recessed caps (10mm) are available for white carcass interiors.

Extended voids (over 600mm wide between end panels) under worktops, especially corner units, and adjacent to worktop joints, should have supporting battens fixed to the wall beneath.

Do not fit wall units directly onto stud walls. In this scenario, noggins are required to provide extra support.

### Appliance Spaces

Care should be taken when leaving spaces for freestanding and integrated built-under appliances.

Built-under integrated spaces should be 603mm maximum. This will allow for easy installation and removal without causing problems with door alignment. 600mm integrated and cantilever cooker hoods require 600mm at the back and front of the void.

Freestanding appliances should have a minimum space 10mm greater than their width to allow easy installation/removal.

Adjacent units to appliance spaces must be plumb and parallel.

Hose positions for dishwasher and washing machines are critical especially on integrated appliances.

Dishwasher hoses should be led through an aperture, cut at low level into the side panel at the rear of the adjacent sink unit, for connection to services within that unit. Washer hoses will have holes drilled at top level in the side panel at the rear of the sink unit if connecting to service in the unit.

# GUIDANCE NOTES

## For the installation of kitchen fitments (in compliance with BS6222 part 4, 1998)

When fitting any appliances the manufacturer's installation instructions must always be read prior to any installation and followed throughout.

When fitting 'wet' appliances ensure that hoses do not become kinked or trapped when the appliance is pushed home.

### Fillers

Filler panels are to be scribed to walls and sealed with matching decorator's filler and not silicone.

15mm or smaller fillers where seen, should be edged in exterior cabinet matching colour.

Tray spaces or any site constructed platforms should have the front edges to match the cabinet colour exterior.

### Plinth

Continuous plinth will be cut and edged at the unit run ends to finish flush with the cabinet end panel. Cabinet exterior matching edging tape should be applied to the raw coreboard with contact adhesive. Peel and stick edging or hot melt adhesive is not recommended.

Ventilation slots as found cut on standard transit plinths on kitchen units must be cut in the continuous plinth for oven, fridge or freezer housings. The slot is approximately 500mm long and 40mm deep and must be cut on the upper edge of the plinth.

Plinths should be fitted tight to the underside of the bottom panel of the base unit and not pushed to the floor. The plinth adds additional support to the bottom panel by keeping it up tight.

Plinths should never be glued or nailed to cabinets as this prevents easy removal.

### Cornice and Pelmet

Cornice and light pelmet mitres should be clean and accurately cut using a fine mitre saw.

Fixing cornice should be from above. If this is impossible, fixing from the inside of the cabinet is recommended. When fixing from the inside of the cabinet, 10mm recessed screw caps should be used and 1" x No. 6 CS screw. If longer screws are used and not recessed they should be covered by a matching cover cap.

Light pelmet can be fixed direct through the wall unit bottom or with half blocks/L brackets. A mixture of both methods of fixing is acceptable especially when fixing to display feature units.

All mitres should be glued using PVA wood glue or Cyanoacrylate adhesive. Under no circumstances must hot melt adhesive be used.

Only minor discrepancies in the cut should be filled with matching filler waxes, (not silicone).

Direct fixing should be positioned as close to the end panels as possible for both pelmet and cornice. The number of fixings per unit size are as follows:

300mm to 600mm wide unit	2 fixings
800mm to 1000mm wide unit	3 fixings

The third fixing for 800/1200 units to be by the centre post.

Cornice should be inset on all wall unit/tall unit returns so that the front lip of the flat (fixing) base of the cornice is inset by 15mm, but fitted with the front edge of the unit's top panel on the elevation.

Pelmet should be inset by 15mm on wall unit returns but flush with the front edge of the bottom shelf on the elevation. In this way the appearance of a uniform recess will be achieved when the unit door is closed.

### Worktop Fixing

Worktops should be fixed to the base units and independent tops to wall battens, and levelled in both directions.

The tops are fixed through the brackets or half blocks on the base unit end panels, and up through the front rail.

The fixings in the front rail should be as close to the end panel as possible and by the centre post on a double base or corner unit.

Mason Mitre and butt joints should be flush fitted. And three jointing bolts need to be used on all kitchen worktops unless they are reduced in depth or width. A coat of silicone\* should be used to seal the worktop ends prior to jointing.

If the back of the worktop has been scribed to the wall it should then be re sealed with silicone\* before installation. Take special care if sealing behind a sink.

Hob and sink cut outs should also be sealed with silicone\* and the chipboard should be cut and the dust then cleared away. Then silicone\* should be applied to ensure all holes are filled.

\*It is recommended that Silicone to BSEN150 11600 or BSS889 be used in all cases.

### Aftercare Instructions

- The tape from all doors and drawers should be removed by hand, without the use of a sharp implement
- Any marks subsequently left should be cleaned off using warm water and a mild detergent
- DO NOT attempt to clean units, worktops or sink tops with cleaning powder or any form of abrasive material or agent
- Drawer runners and hinges should be cleaned to ensure that no plaster, grit or other material will impede their action



# CARE FOR YOUR SYMPHONY KITCHEN

**We set standards of quality to which others can only aspire**

At Symphony, our commitment to quality is total. From our choice of raw materials, right through to the design, manufacture and installation of our products. What's more, every stage of our operation is constantly monitored to ensure that standards are not only maintained but also continuously improved.

In fact, our whole philosophy is one of providing not only the very best products to customers but also complete peace of mind.

## Your Symphony Kitchen Cabinet

Symphony kitchens are manufactured from high density, fine surface particle board, which complies with the British Standard BS EN 312-P2. You can be assured that all cabinets are tested to and pass FIRA Gold product certification. Cabinets are supplied on adjustable legs to cater for uneven floors and to protect against moisture ingress. Vulnerable cabinet edges are lipped to resist moisture see page in to the panels.

## General Cabinet Cleaning Advice

Sensible general cleaning practice includes avoiding use of an abrasive cleaner or strong chemicals (such as vinegar, nail varnish remover, solvents and bleach) on surfaces and always wiping off any water with a soft cloth rather than leaving it to stand. It should be noted that cabinets are not resistant to water and will swell if wet, so any spillage should be dried immediately. To clean your cabinets simply use a slightly damp non-abrasive cloth with a little liquid soap.

All Symphony frontals and doors have been made to withstand the normal wear and tear associated with kitchen life and are treated to resist normal household cleaning chemicals. However, any spills should be rinsed immediately and dried thoroughly. Avoid placing electric kettles and steamers directly below wall units and on worktop joints to minimise condensation. Naturally, you should also regularly check that all handle screws are secure and never rest heavy objects on partly opened doors or drawers.



# CARE FOR YOUR SYMPHONY KITCHEN

## Adjustable Shelves

Unit shelves are adjustable to suit your needs. Whilst units have been FIRA Gold approved and tested to withstand strong weights, we recommend that you load the heaviest items on the base of the cabinet with lighter items on the shelves. It is recommended to evenly distribute items within a cabinet to avoid minor distortion of the unit. Adjustable metal hanging brackets secure wall units to the wall, though we recommend that heavy items are not placed in wall units for both accessibility and safety reasons.

In addition to the specific guidelines detailed in this brochure, you should naturally take extra care when working near to hot surfaces or using cleaning agents. For example, keep all chemicals, detergents, hot pans and sharp objects out of children's reach and never allow them to be unattended in the kitchen and to swing on doors or drawers.

A wide range of base and wall units and colour options are available in flat pack format for ease of storage and quick, easy assembly on site. Please ask your Symphony representative for information.


## Characteristics of Various Timbers

As a natural material, wood reflects the endless variety of grains and textures found in nature and such variances

must be expected. All timbers mellow when exposed to sunlight so a colour change is possible overtime. Whilst such definitive characteristics make them a perfect vehicle for furniture design, it is important that they are treated with care. The risk of contact with sharp or heavy objects, scratching, exposure to chemicals, etc. must be avoided before, during and after installation.

### Oak (Oakham)

Oak is a finely grained, mature timber notable for its stability and straight graining. Because it can be used for a variety of styles and stained in a number of different colours, it is the traditional favourite of both craftsmen and, of course, homeowners.



### Ash (Austin/New England & Wexford)

Ash belongs to the olive tree family and due to its high flexibility it is used in a variety of furniture and flooring products. It is easy to work with and can be stained, waxed or polished very well.



## Cabinet/Frontal Surface Consistency

Timbers and veneers are natural materials and are subject to the variations in colours and grain differences that nature promotes. All timbers feature small graining marks and knots. These are part of the timber's natural properties and do not represent faults in the door or drawer. It is virtually impossible to guarantee a totally accurate match between timber veneered frontals and accessories. Notwithstanding the difficulties involved, Symphony endeavours wherever possible to produce the closest match that manufacturing and finishing technology allow.

These timber variations are also apparent on our painted veneered timber doors. It should also be noted that painted products (both veneered timber and foil wrapped doors) are subject to variations in colour/tonal over time owing to the effect of ultra-violet light on the doors' painted surface.

Melamine and laminates are synthetic materials and so have a very stable finish, however they are still liable for changes in colour over time.

## PAINTED PRODUCTS

High quality durable water-based paint has been used in the manufacture of all doors, drawers and accessories. Spillages should be wiped away quickly. To clean, use a clean, damp cloth, apply a small amount of soft soap (a mild washing-up liquid) and water to the area to be cleaned, and gently wipe over the surface in one direction. Then wipe over the surface with a clean, dry cloth. Avoid the use of abrasive agents, creams, industrial cleaners, detergents or liquid sprays that contain wax. Scratches and scrapes, if they occur, should be treated with an application of a matching touch-up paint.

## Care of your Kitchen Frontals

Doors and drawers should be wiped clean with warm water and a damp cloth containing a mild detergent. For best results, do not over wet. Also, you should avoid the use of scouring pads or wire wool and not use abrasive cleaning agents.


## Solid timbers and veneers

High quality wood and veneer have been used in the manufacture of all door and drawer fronts. Although the lacquered finish gives a tough hard-wearing surface, spills should be wiped clean immediately and then a wipe over with a damp cloth will restore the finish. Once dry, a final polish with a soft cloth and a reputable household furniture polish will preserve and enhance the wood's natural beauty.



# UNIT ELEVATIONS

HEIGHT: 2100mm




1. 500/600/800/900 2-Drawer Pan units, 362mm (h) Bridging units and 724mm (h) Bi-fold Wall units available in contemporary, inline and classic ranges.
2. 1000 2-Drawer Pan unit, 362mm (h) Bridging unit and 724mm (h) Bi-fold Wall unit available in all contemporary ranges.
3. 150 Base units available in Contemporary and Classic ranges.
4. 500/600/800/900/1000 3-Drawer Pan units available in all ranges.
5. Convex curved Base and Wall units available in Alta Gloss, Alta PTO, Ashbourne, Ashbourne PTO, Austin, Austin PTO, Cranbrook, New England PTO, New York Gloss, New York PTO, Oakham, Wexford and Woodbury only.

NB: Base cabinet height to underside of worktop is 870mm. Actual base cabinet depth is 570mm (600mm with frontal). Actual wall cabinet depth is 285mm (300mm with frontal) Assembled and 330mm (350mm with frontal) on Premium.

# UNIT ELEVATIONS

HEIGHT: 2276mm



6. Concave curved Base units available in Alta Gloss, Austin PTO, New England PTO, New York Gloss and New York PTO. Concave Wall units available in Alta Gloss, Austin PTO, New England PTO, New York Gloss and New York PTO. (330mm Cabinets) only.
7. 500/600/800/900/1000 Flap Down units available in all contemporary ranges.
8. Full Height Appliance and Larder Frontals available in Alta Gloss, Alta Matt and Alta PTO only.
9. 561, 724 and 900 High Wall units in all ranges (561 not available in New England).

NB: Base cabinet height to underside of worktop is 870mm. Actual base cabinet depth is 570mm (600mm with frontal). Actual wall cabinet depth is 285mm (300mm with frontal) Assembled and 330mm (350mm with frontal) on Premium.



# CORNER UNITS

All corner base units have centre hung doors with 110° hinges. Corner posts and blanking panels are fitted as standard. On corner base units with a corner post, a blanking panel covers the void of the unit.

A 600mm colour co-ordinated blanking panel is fitted where corner posts are NOT required - e.g. when the blank abuts a void for a freestanding appliance or tray space.

**IMPORTANT:** Please specify the handing of the side of the blanking panel when ordering.

Some of our corner base cabinets are available with a shelf or with a range of internal storage (not fitted). Storage options include Le Mans and a ½ Carousel.

Symphony's range of corner base units allows wide flexibility in the positioning of corner units for the clearance of water or soil vent pipes when required. Please specify the handing of the blanking panel side when ordering.

## Corner Sink Base Units

1000mm corner base units can also be supplied as corner sink units. To specify a corner sink unit, change the prefix letters on the standard corner base unit code from 'CB' to 'CS' as shown in the example below.

Unit Code	Description
CS106DC	1000mm Corner Sink Base Cabinet, 600mm Door

## Corner Base Units Variations


To specify a corner base or corner sink unit with a manufacturing variation, suffix the standard unit code as shown in the examples.

Variation	Suffix	Unit Code	Description
One piece corner post	-	CB106DC	Corner base unit 1000 x 600 x 870. 600 door, one piece corner post
No corner post	BO	CB106DCBO	Corner base unit 1000 x 600 x 870. 600 door, no corner post
Dummy drawer with flexible corner post	DFP	CB106DADFP	Corner base unit 1000 x 600 x 870. 500 door, dummy drawer
No corner post and dummy drawer	BS	CB106DABS	Corner sink unit 1000 x 600 x 870. 500 door, no corner post, dummy drawer
Flexible corner post	FP	CB106DCFP*	Corner base unit 1000 x 600 x 870. 600 door, flexible corner post


\* Please note that the flexible corner posts are not available on L-shaped cabinets, corner ladder cabinets or 900mm high wall cabinets.

## CORNER BASE UNIT


### 800mm



Full Height **CB86FBFP**  
Drawer Line **CB86DBFP**




Full Height **CB86FAFP**  
Drawer Line **CB86DAFP**




Full Height **CB86FCFP**  
Drawer Line **CB86DCFP**

### 900mm




Full Height **CB96FAFP**  
Drawer Line **CB96DAFP**


### 1000mm



Full Height **CB106FBFP**  
Drawer Line **CB106DBFP**




Full Height **CB106FAFP**  
Drawer Line **CB106DAFP**




Full Height **CB106FCFP**  
Drawer Line **CB106DCFP**


### 1200mm



Full Height **CB126FAFP**  
Drawer Line **CB126DAFP**



Full Height **CB126FFFP**  
Drawer Line **CB126DFFP**



Full Height **CB126FEFP**  
Drawer Line **CB126DEFP**


All 'FP' codes are for frontal matched corner posts. For cabinet matched corner posts, the 'FP' should be replaced with 'BO' and separate CPOSTPNL72/90 panels used and cut down to suit on site.

# CORNER UNITS

## L Shape Corner Base Unit


A corner unit with either a shelf or a revolving carousel, supplied with 170° hinges. The two doors are hinged on the end panels. In order to facilitate transportation, the unit is supplied in two parts, one assembled and one ready for assembly (RFA) and the carousel or shelf must be fitted on site. Full height door or door and dummy drawer front styles are available. The dummy drawer fronts are fixed to the doors.

### L SHAPED CORNER BASE UNIT



Full Height **LSB99F**  
Drawer Line **LSB99D**

### L SHAPED CORNER BASE CABINET WITH CAROUSEL




Full Height **LCB99F**  
Drawer Line **LCB99D**

## Concave Base Units

Concave corner base units have a single hinged door that opens to 110°. Concave corner base units are available with a full height door only.

Our range of corner base units allows wide flexibility in the positioning of corner units for the clearance of water or soil vent pipes when required.

### CONCAVE




Full Height **COB991PCF**


## Corner Wall Cabinet

Conventional corner wall cabinets should be positioned 30mm from the return cabinet. If a corner post is supplied, this is to space out the return cabinet to avoid the clashing of protruding handles.

### 600mm




561mm High Door **CWU656FP**  
724mm High Door **CWU672FP**  
900mm High Door **CWU690\***



561mm High Door **CWU656FBFP**  
724mm High Door **CWU672FBFP**  
900mm High Door **CWU690FB\***


\* For 900mm high wall units, the standard code is to be used with separate panels FRONTPNL90 to be cut down to suit on site.

### 800mm



561mm High Door **CWU856FAFP**  
724mm High Door **CWU872FAFP**  
900mm High Door **CWU890FA\***

### 900mm



561mm High Door **CWU956FCFP**  
724mm High Door **CWU972FCFP**  
900mm High Door **CWU990FC\***


All 'FP' codes are for frontal matched corner posts. For cabinet matched corner posts, the 'FP' should be replaced with 'BO' and separate CPOSTPNL72/90 panels used and cut down to suit on site.

# CORNER UNITS

## Diagonal and Concave Corner Wall Unit


The Diagonal and Concave corner wall units, including spacers, fits into a corner situation measuring 630mm x 630mm. Diagonal and Concave corner wall units cannot be hung separately or at the end of a run of units.

### CONCAVE CORNER WALL UNIT



720mm High Door **COCWU672**


### 330mm CORNER WALL CABINET PLANNING




## L Shaped Corner Wall Unit

'L' corner wall units are designed to provide an additional 30mm in both directions. Consequently, no additional spacing is required.

### L SHAPED CORNER WALL CABINET



720mm High Door **LCWU672**




720mm High Door **LCWU772**


## Corner Larder Unit

Corner larder units should be positioned 60mm from the return unit. The corner post when fitted will space out the unit to avoid clash of handles. If the larder adjoins a base or wall unit then a full blanking panel (supplied) should be fitted.

### CORNER LARDER UNIT



2100mm high **CNLU106/A/F**  
2276mm high **CNLU10623/A/F**



2100mm high **CNLU106C/A/F**  
2276mm high **CNLU10623C/A/F**

All 'FP' codes are for frontal matched corner posts. For cabinet matched corner posts, the 'FP' should be replaced with 'BO' and separate CPOSTPNL72/90 panels used and cut down to suit on site.



# CORNER UNITS


## Corner Post

The corner post allows product ranges with protruding handles to be offset by 60mm in order to avoid possible clashing of drawer handles in a corner. The corner post automatically spaces out the units to the correct size across Dimension A. However, the fitter must remember to position the corner units (as appropriate) from the wall.

## Flexible Corner Posts

All standard corner base units are supplied with a flexible corner post, to allow for adjustment of the position of return units in-situ. This allows the unit width to be increased by 70mm (note: the unit depth is not flexible). Flexible corner units are supplied with a fixed corner post panel, a fixed blanking panel and an adjustable corner post panel which is supplied loose. All flexible corner units will co-ordinate with the kitchen frontal. To order the flexible corner post please add 'FP' to the current unit code where available.

## CORNER POST



All 'FP' codes are for frontal matched corner posts. For cabinet matched corner posts, the 'FP' should be replaced with 'BO' and separate CPOSTPNL72/90 panels used and cut down to suit on site.

# FLEXIBLE CORNER POSTS

To allow for flexibility when fitting corner units we can supply the unit with x2 fascia panel (see below for details) instead of the fixed corner post.

To order the flexible corner post option please add 'FP' to the unit code. (Example CB106FAFP)

## Corner Base Units

Corner base units will be supplied with the following fascias;

- x1 42mm x 720mm
- x1 146mm x 720mm

For assembled units the 146mm x 720mm fascia and blanking panel will be fitted. The 42mm x 720mm fascia will require fitting on site. (See diagram opposite).




## Corner Wall Units

724mm high corner wall unit will be supplied with the following fascias;

- x1 27mm x 720mm
- x1 146mm x 720mm

For assembled units the 146mm x 720mm fascia and blanking panel will be fitted. The 27mm x 720mm fascia will require fitting on site. (See diagram opposite).




Flexible corner posts are not available on L shape, diagonal, 900 high wall units or corner larders.

**Please note:** Where current ranges are supplied with cabinet matched corner posts these will also be supplied with cabinet matched fascia panels.

The above shows 724mm high wall units. 561mm high wall units are also available.



# FLEXIBLE CORNER POSTS

The flexible corner post on the 'FP' units consists of a 146mm frontal matched panel that is factory fitted to the corner base cabinet and a small loose frontal matched panel. This smaller panel is sent out in the plot box and is attached on site to the fixed panel as required. A cabinet matched panel is also factory fitted to blank off the remainder of the corner base. This is sized to suit the style of corner base e.g. A, B or C.



The loose panel is attached to the fixed frontal matched panel, on site, at the correct point to suit the design.



**Flexible corner units can be pulled out by a maximum of 70mm.**





The loose frontal matched panel is always sent out as 720mm high.

# DIAGONAL CORNER LARDER UNIT

2100





2276



## Diagonal Corner Larder Unit - Planning

As a result of the fact the side panels are screw fixed from the outside of the unit, either blender panels or full height units are required to hide the screws.



# MINOR ADJUSTMENTS

Because your kitchen doors and drawers will be in constant use, they may require adjustment from time to time to ensure perfect working order. This can be done easily with a simple screwdriver, a brush and some lubricating oil.


## Door Hinges and Drawer Runners

It's a good idea to inspect the door hinges and drawer runners from time to time so that any dirt, fluff or general grime can be removed.

This can be done with a soft, dry brush or a duster, or even the nozzle of a vacuum cleaner. Although lubrication is usually not required a small amount of household spray polish may be used.




## ADJUSTING THE DOOR




### Side Adjustment

The side adjustment is made by rotating the appropriate screw on the hinge arm.



### Height Adjustment

For height adjustment the two mounting plate fixing screws have to be temporarily released while making the manual adjustment.



### Depth Adjustment


The depth adjustment is made by temporarily releasing the adjustment/fixing screw. After the adjustment is made the screw has to be re-tightened.

## ADJUSTING THE DRAWER FRONTS

### ATIRA Silver Drawer Box


To adjust the drawer front vertically clip off the cap, rotate the grooved wheel clockwise/anti-clockwise.

To adjust the drawer front horizontally, rotate the screw clockwise/anti-clockwise.



### Timber Drawer Box

Using a screwdriver, slacken the screws that attach the frontal to the drawer box, align the frontal accordingly and re-tighten the screws. It may be easier to remove the lower screws completely for alignment.



## Weight Limit of Drawer Boxes

All kitchen cabinets are tested to FIRA Gold award certification to British standards BS EN 6222 Test Level H, to ensure complete confidence of your kitchen for many years to come. A 30kg weight limit applies to all drawer boxes. This is the maximum load capacity of a drawer and should not be exceeded.

# WORKTOP MAINTENANCE

## General Maintenance

All Symphony laminate worktop surfaces are designed for easy maintenance and long life. Everyday stains such as coffee spills and finger marks clean up easily with a quick wipe with a damp cloth. Although laminates are exceptionally resistant to scratches and normal wear and tear, always use a cutting board when using sharp knives.

## Cleaning Stains

Always start with the gentlest method. If stains persist, try the following steps:

- 1 Use a damp cloth and mild detergent.
- 2 For difficult stains, use a mild household cleaner with a soft bristled brush.
- 3 If stubborn stains remain, try a paste of baking soda or a non-scratch cleaner such as Flash, scrubbing lightly with a soft bristled brush.

## Do's and Don'ts

Never place hot pans or dishes directly onto the worktops. Instead, use a heat shield, hot pad or trivet to avoid blistering or cracking the laminate. Never use acidic or abrasive cleaners, or apply excessive scrubbing, especially on surfaces with a gloss finish.

## Earthstone Work Surfaces

Through a simple cleaning regime the unique surface can be maintained to look good longer and has the added benefit of being repairable.

You will have received a care and maintenance kit with your Earthstone worksurface along with a leaflet to explain how you can keep your worktop in a good condition.

Once installed your worktop will have been given a final sand and polish. Over time the worksurface will eventually acquire a smoother, slightly higher sheen to it.

## Daily Cleaning

It is recommended to wipe down the surface with warm soapy water during the first week of installation. Then buff the surface dry and apply a thin, even coat of Countertop Magic (included in your Care and Maintenance kit) and wipe off immediately with clean microfibre cloth.

## Weekly Polish

It is recommended to polish your Earthstone worksurface once a week to maintain its deep, rich lustre. Use the Earthstone Care and Maintenance kit and refer to the leaflet for information on how to do this.


## Recommendations

- Do protect your worksurface from heat damage by using heat resistant mats
- Do wipe spills away quickly
- Do follow the weekly cleaning regime
- Don't place hot objects directly onto the worksurface
- Don't cut directly onto the worksurface
- Don't use abrasive cleaners or solvents as cleaning fluids
- Don't drop heavy objects onto the worksurface

Please note: Darker colours will show excessive marking, scratching, wear and tear more noticeably than lighter colours.



# SYMPHONY BRANDS



Symphony presents a diverse range of brands spanning kitchen, bedroom and bathroom furniture. Our kitchens incorporate modern handleless kitchens in Linear, to the highest quality contemporary and classic kitchens in Gallery. The Laura Ashley Kitchen Collection and Fitted Bedrooms bring the rich design heritage of the brand to two inspirational and distinctive collections of furniture.

Our Urbano bedroom furniture includes front frame, Glide sliding robes, chests and bedside cabinets. Our Aquadi bathroom brand encompasses a range of en suite designs to complement the chosen bedroom.

For further information please visit [www.symphony-group.co.uk](http://www.symphony-group.co.uk) or email [enquiries@symphony-group.co.uk](mailto:enquiries@symphony-group.co.uk).





---

The Symphony Group PLC, Pen Hill Estate, Park Spring Road, South Yorkshire S72 7EZ  
General Enquiries: Tel: 01226 446000 Fax: 01226 711185  
[www.symphony-group.co.uk](http://www.symphony-group.co.uk)